

## **Cordell Hull Birthplace State Park**

1300 Cordell Hull Memorial Drive  
Byrdstown, TN 38549

### **Cordell Hull Birthplace Log Cabin Repairs**

#### **General:**

The Contractor shall be responsible for all labor, materials, and equipment necessary for this project at Cordell Hull Birthplace State Park. All work shall be done in accordance with the latest industry standards. Any deviations from this scope of work will be executed only after written approval is received. The Contractor shall be responsible for the safety and security of the site during this project. The Contractor shall use barriers where necessary. The Contractor shall be responsible for notifying park staff at the end of each day before leaving to ensure site is secure. All containers and trash shall be removed and disposed of off state property. The Contractor shall visit site to obtain accurate measurements.

**BC or a BC-A contractor is required for this project.**

**This project must be completed by MAY 20<sup>th</sup>, 2024.**

#### **Existing:**

Cordell Hull Birthplace Log Cabin's deterioration is severe and is expected to deteriorate further to the point of falling down if repairs aren't made soon.

#### **Scope:**

- A. The Contractor shall remove existing shake shingle roofing, felt paper, and flashing.
- B. The Contractor shall install ice and water shield on the entire roof.
- C. The Contractor shall install synthetic felt over the entire roof and shall install all necessary flashing on both chimneys.
- D. The Contractor shall install new Blue Label Cedar Shake pressure treated #1 heavy shingles using #8 ring shank nails.
- E. The Contractor shall install new copper flashing around shingles to ensure no leaks and to have the ORIGINAL LOOK.
- F. The Contractor shall remove and replace all damaged and deteriorated logs with same type logs that look as close to existing as possible.
- G. The Contractor shall remove chinking everywhere that is needed and shall install chinking as close as to original as possible.
- H. The Contractor shall cut and adjust all doors so that they open and close properly.
- I. The Contractor shall install beveled wood strips at all door entrances to make it wheelchair assessable.
- J. The Contractor shall level building floors as close to level as possible.

- K. This building is very old, and the utmost care is to be used in the repairs being done during this project.
- L. The chimney on the front cabin has a large crack 4-inches wide between cabin and chimney, when leveling cabin floors close crack as close to building as possible.

**Additional Conditions:**

This is a turnkey job. All aspects of this job shall be left in a finished condition: All finish work, interior and exterior walls and trim, finish painting, caulking and final cleanup are included in this contract.

All bidders are advised to visit site to verify all conditions and dimensions. No allowances shall be made by the agency due to any bidder neglecting to visit the site and verifying dimensions and conditions.

*All bids over \$100,000 shall include provisions for a payment bond in the amount of twenty-five percent (25%) of the contract price.*

Contractor shall be responsible for determining where all utilities are on the job site and care should be taken to protect the utilities from any damage caused by the demo/construction. This shall include any underground utilities around the job site area. If damage occurs, it shall be repaired within a 24-hour period from the time damage occurs.

Contractor shall perform work on regular time and shall invoice work time and material not to exceed the quoted price. Any variance in quote shall be addressed with a representative of Facilities Management, East TN Regional Office (ETRO) before additional work or materials are supplied.

Work shall be scheduled to avoid any interference with normal operation of the park as much as possible. During the construction period, coordinate construction schedules and operations with the agency. Work shall be conducted during the normal business hours of Monday through Friday, 8:00 a.m. to 4:30 p.m., unless approval for an alternate schedule is arranged with Facilities Management.

Successful contractor shall schedule and attend a pre-construction conference where a pre-construction form shall be signed by Facilities Management, Contractor and Park Manager or park representative before work can begin. Contractor shall also schedule and attend a final inspection where a final inspection form shall be signed by Facilities Management, Contractor and Park Manager or park representative before invoice shall be paid.

The contractor shall protect areas adjacent to his work and shall be required to repair any damage he may cause. Contractor shall protect work of other trades. Contractor shall correct any painting related damage by cleaning, repairing, or replacing, and refinishing as directed by Facilities Management.

Workmanship is to be warranted for not less than one year from date of final inspection. Materials shall be warranted as per manufacturer warranty.

All materials, equipment, and supplies shall be new and in good condition, UL listed when applicable, and all work accomplished in a manner acceptable to Facilities Management.

Submittals shall be required on all materials and shall be presented for approval by the State of Tennessee representative: Facilities Surveyor, Facilities Manager or Park Manager.

Clean up of the project site shall be the responsibility of the contractor. Contractor shall assure that job site is clean of nails, debris, etc., at end of each day to ensure safety. Contractor shall clean up and haul away all scrap when work is completed to an approved location off state property.

Contractor, employees, or sub-contractors shall be licensed, certified, or registered as required. They shall be registered in the State of Tennessee Edison purchasing system.

The contractor shall have a Certificate of Insurance on file with Facilities Management.

The State of Tennessee shall not be held liable for any damage, loss of property, or injury of personnel resulting from actions of the contractor and/or his/her sub-contractors or employees.

Contractor shall obtain all fees and permits required for project. Contractor shall have a copy of project specifications, permits, and certificate of insurance on project site at all times.

Contractor shall comply with all applicable codes, standards, and regulations in execution of project.

All work shall conform to the state's current approved codes, such as the International Building Code. All electrical and plumbing shall conform to the latest and most current codes. All Fire Marshall approved projects shall have a Certificate of Occupancy issued at the completion of the project. All ADA projects shall have approval of the State of Tennessee Facilities Design Coordinator and shall be in compliance with the latest ADA code at the completion of the project.

Invoice shall be submitted for payment within 10 days of project completion. A copy of the invoice shall be submitted to Facilities Management, East TN Regional Office, 160 State Circle, Rocky Top, TN 37769, or to [deborah.g.smith@tn.gov](mailto:deborah.g.smith@tn.gov).

For scheduling contact:

Facilities Manager: Chad Young, 865-606-1551, [chad.young@tn.gov](mailto:chad.young@tn.gov)

Facilities Surveyor: Gary Greenwood, 865-806-8300, [gary.greenwood@tn.gov](mailto:gary.greenwood@tn.gov)