

# **Standing Stone State Park**

1674 Standing Stone State Park Highway  
Hilham, TN 38568

## **Group Cabin #3 Roofing & Painting**

### General:

The Contractor shall be responsible for all equipment, labor, and materials necessary for this project at Standing Stone State Park. All work shall be done in accordance with the latest industry standards. Any deviations from the scope of work will be executed only after written approval is received. The Contractor shall be responsible for the safety and security of the site during this project. The Contractor shall be responsible for notifying park staff at the end of each day before leaving to ensure the site is secure. The Contractor shall use barriers where necessary. All containers and trash shall be removed and disposed of off state property. The Contractor shall visit site to obtain accurate measurements.

**This project must start on March 4<sup>th</sup>, 2024, and must be completed by April 4<sup>th</sup>, 2024.**

**Licensing requirements are BC, or a BC-B contractor for this project.**

### Scope:

- A. The Contractor shall remove shingles, felt paper, and any damaged roof sheathing.
- B. The Contractor shall install ice and water shield around perimeter of roof as well as all valleys and ridge line.
- C. The Contractor shall install 30# synthetic felt over entire roof and shall install new sheathing to repair any that is damaged. Park shall supply sheathing lumber.
- D. The Contractor shall install 29ga, brown metal roof with all trim rake, drip edge, valley, chimney flashing, and ridge cap.
- E. All roof metal shall be installed using 1-inch screws, and all ridge cap and trim shall be installed using 1½ screws. Install new pipe boots. Lexel roof sealant shall be used, NO Silicone.
- F. The Contractor shall replace all damaged siding with same material as existing.
- G. The Contractor shall replace all damaged and deteriorated window and door trim with same material as existing.
- H. The Contractor shall remove and replace eight damaged logs. Park shall furnish new logs.
- I. The Contractor shall repair deteriorated porch beam and rafters as needed. Park shall furnish beams and rafter materials.

- J. The Contractor shall scrape all exterior paint and prime with Sherwin Williams primer or equal.
- K. The Contractor shall caulk all cracks and joints with Dap Dynaflex 230 paintable caulking or equal.
- L. The Contractor shall paint entire building using two coats of Sherwin Williams lifetime warranty exterior paint.
- M. The Contractor shall install new 6-inch gutters with gutter guards on entire building. K -style gutters color to be royal brown or musket.

**Additional Conditions:**

This is a turnkey job. All aspects of this job shall be left in a finished condition: All finish work, interior and exterior walls and trim, finish painting, caulking and final cleanup are included in this contract.

All bidders are advised to visit site to verify all conditions and dimensions. No allowances shall be made by the agency due to any bidder neglecting to visit the site and verifying dimensions and conditions.

*All bids over \$100,000 shall include provisions for a payment bond in the amount of twenty-five percent (25%) of the contract price.*

Contractor shall be responsible for determining where all utilities are on the job site and care should be taken to protect the utilities from any damage caused by the demo/construction. This shall include any underground utilities around the job site area. If damage occurs, it shall be repaired within a 24-hour period from the time damage occurs.

Contractor shall perform work on regular time and shall invoice work time and material not to exceed the quoted price. Any variance in quote shall be addressed with a representative of Facilities Management, East TN Regional Office (ETRO) before additional work or materials are supplied.

Work shall be scheduled to avoid any interference with normal operation of the park as much as possible. During the construction period, coordinate construction schedules and operations with the agency. Work shall be conducted during the normal business hours of Monday through Friday, 8:00 a.m. to 4:30 p.m., unless approval for an alternate schedule is arranged with Facilities Management.

Successful contractor shall schedule and attend a pre-construction conference where a pre-construction form shall be signed by Facilities Management, Contractor and Park Manager or park representative before work can begin. Contractor shall also schedule and attend a final inspection where a final inspection form shall be signed by Facilities Management, Contractor and Park Manager or park representative before invoice shall be paid.

The contractor shall protect areas adjacent to his work and shall be required to repair any damage he may cause. Contractor shall protect work of other trades. Contractor shall correct

any painting related damage by cleaning, repairing, or replacing, and refinishing as directed by Facilities Management.

Workmanship is to be warranted for not less than one year from date of final inspection. Materials shall be warranted as per manufacturer warranty.

All materials, equipment, and supplies shall be new and in good condition, UL listed when applicable, and all work accomplished in a manner acceptable to Facilities Management.

Submittals shall be required on all materials and shall be presented for approval by the State of Tennessee representative: Facilities Surveyor, Facilities Manager or Park Manager.

Clean up of the project site shall be the responsibility of the contractor. Contractor shall assure that job site is clean of nails, debris, etc., at end of each day to ensure safety. Contractor shall clean up and haul away all scrap when work is completed to an approved location off state property.

Contractor, employees, or sub-contractors shall be licensed, certified, or registered as required. They shall be registered in the State of Tennessee Edison purchasing system.

The contractor shall have a Certificate of Insurance on file with Facilities Management.

The State of Tennessee shall not be held liable for any damage, loss of property, or injury of personnel resulting from actions of the contractor and/or his/her sub-contractors or employees.

Contractor shall obtain all fees and permits required for project. Contractor shall have a copy of project specifications, permits, and certificate of insurance on project site at all times.

Contractor shall comply with all applicable codes, standards, and regulations in execution of project.

All work shall conform to the state's current approved codes, such as the International Building Code. All electrical and plumbing shall conform to the latest and most current codes. All Fire Marshall approved projects shall have a Certificate of Occupancy issued at the completion of the project. All ADA projects shall have approval of the State of Tennessee Facilities Design Coordinator and shall be in compliance with the latest ADA code at the completion of the project.

Invoice shall be submitted for payment within 10 days of project completion. A copy of the invoice shall be submitted to Facilities Management, East TN Regional Office, 160 State Circle, Rocky Top, TN 37769, or to [deborah.g.smith@tn.gov](mailto:deborah.g.smith@tn.gov).

For scheduling contact:

Facilities Manager: Chad Young, 865-606-1551, [chad.young@tn.gov](mailto:chad.young@tn.gov)

Facilities Surveyor: Gary Greenwood, 865-806-8300, [gary.greenwood@tn.gov](mailto:gary.greenwood@tn.gov)