

Estimated Quantities -- Letting May 12, 2023

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNX904 - COCKE & JEFFERSON

Contract ID: CNX904

Letting Date: May 12, 2023	10:00 AM	Projects: 15002-3218-94	STP/HSIP-9(115)
		15002-8218-14	STP/HSIP-9(115)
		45004-3245-94	STP/HSIP-9(116)
		45004-8245-14	STP/HSIP-9(116)

Counties: COCKE, JEFFERSON

District: **DBE Goal Percent:** 8.50

Description: The resurfacing on U.S. 25W (U.S. 70, S.R. 9) from near the French Broad River (L.M. 17.08) in Jefferson County to near I-40 (L.M. 1.59) in Cocke County.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	13.200	L.M.
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	515.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	175.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	8.000	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	142.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,165.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	579.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	146.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	387.000	EACH

Contract ID CNX904 - COCKE & JEFFERSON

Item No.	Description	Quantity	Units
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	46.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	75.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	4,191.000	L.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	3.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	7.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	7.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	21.000	L.M.
717-01	MOBILIZATION	(1)	LS
411-03.07	ACS MIX(PG64-22) THIN LIFT ASPHALT	3,995.000	TON
411-03.08	ACS MIX(PG70-22) THIN LIFT ASPHALT	2,573.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	3,995.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	2,573.000	TON

() Item will be bid as lump sum.

Contract ID CNX148 - ANDERSON

Contract ID: CNX148

Letting Date: May 12, 2023 10:00 AM

Projects: 01034-3222-94

HSIP/PHSIP-330(4)

Counties: ANDERSON

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on S.R. 330 from Dutch Valley Road (L.M. 1.60) to Half Moon Road (L.M. 5.71).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	15,270.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	288.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	462.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,697.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	236.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	265.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	39.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	88.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX176 - ANDERSON , BLOUNT, ETC.

Contract ID: CNX176

Letting Date: May 12, 2023 10:00 AM

Projects: R1BVAR-M3-029

NA

Counties: ANDERSON, BLOUNT, CAMPBELL, CARTER,
CLAIBORNE, COCKE, GRAINGER, GREENE,
HAMBLEN, HANCOCK, HAWKINS,
JEFFERSON, JOHNSON, KNOX, LOUDON,
MONROE, MORGAN, ROANE, SCOTT,
SEVIER, SULLIVAN, UNICOI, UNION,
WASHINGTON

District:

DBE Goal Percent:

Description: The random on-call signing on various Interstate and State Routes.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
712-01.02	LANE CLOSURE	2.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	25.000	DAY
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	10.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	3,000.000	LB.
713-04.02	STEEL I-BEAMS & W-F BEAMS FOR SIGN SUPPORTS	5,500.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	6,000.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	23.000	LB.
713-11.05	SQUARE TUBE SIGN SUPPORT	15.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	10.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	30.000	S.F.
713-13.12	FLAT SHEET ALUM SIGNS OVERLAY (0.080" THICK)	30.000	S.F.
713-13.14	FLORESCENT YELLOW SIGN SHEETING	300.000	S.F.

Contract ID CNX176 - ANDERSON , BLOUNT, ETC.

Item No.	Description	Quantity	Units
713-14	EXTRUDED ALUMINUM PANEL SIGNS	4,800.000	S.F.
713-15.01	REMOVAL OF EXISTING SIGN POST	5.000	EACH
713-15.03	REMOVAL OF LARGER BARRIER MOUNTED SIGNS WITH SADDLE SUPPORTS	15.000	EACH
713-15.10	REMOVAL OF SMALL BARRIER MOUNTED SIGNS W/ FLAT PLAT SUPPORTS	30.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	5.000	EACH
713-15.37	INSTALLATION OF SIGN MESSAGE(LETTER,#,ARROW,SHIELD)	10.000	S.F.
713-15.38	EXTRUDED ALUMINUM PANELS FOR OVERLAYING BACKGROUND	10.000	S.F.
713-16.90	RESET GROUND MOUNTED SIGN	10.000	EACH
713-17.02	INSTALL AUXILIARY SUPPORT FOR EXIT NUMBER PANEL	24.000	EACH
713-17.04	INSTALL AUXILIARY SUPPORT ON EXISTING SIGN	100.000	L.F.
713-20.30	SIGN ADJUSTMENTS	5.000	EACH
713-20.40	GRAFFITI REMOVAL	250.000	S.F.
713-30.09	BARRIER MOUNTED SIGN SUPPORT (DESCRIPTION) (SADDLE)	8.000	EACH
713-30.10	BARRIER MOUNTED SIGN SUPPORT (PERF/KNOCKOUT) (PERF/KNOCKOUT)	5.000	EACH

() Item will be bid as lump sum.

Contract ID CNX081 - BEDFORD

Contract ID: CNX081

Letting Date: May 12, 2023 10:00 AM

Projects: 02S016-F3-005
02S016-F8-005

NH/HSIP-16(68)
NH/HSIP-16(68)

Counties: BEDFORD

District:

DBE Goal Percent: 8.50

Description: The resurfacing on U.S. 41A (S.R. 16) from Evans Street (L.M. 18.62) to S.R. 64 (L.M. 21.58).

Contract Time: DT - 11/15/2023

Item No.	Description	Quantity	Units
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (CATCH BASIN REPAIR)	148.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	44.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	222.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	50.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	9,022.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,936.000	TON
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	27,470.000	LB.
611-09.02	REWORK CATCHBASIN	41.000	EACH
702-03	CONCRETE COMBINED CURB & GUTTER	10.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,156.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	430.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	390.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	13.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,038.000	L.F.

Contract ID CNX081 - BEDFORD

Item No.	Description	Quantity	Units
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	25.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	550.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	1,734.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.300	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	5.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	3.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	14.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	14.800	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	1,220.000	L.F.
730-14.03	LOOP WIRE	2,540.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX164 - BEDFORD , CHEATHAM, ETC.

Contract ID: CNX164

Letting Date: May 12, 2023 10:00 AM

Projects: R3BVAR-M3-036

NA

Counties: BEDFORD, CHEATHAM, DAVIDSON,
DICKSON, GILES, HICKMAN, HOUSTON,
HUMPHREYS, LAWRENCE, LEWIS,
LINCOLN, MACON, MARSHALL, MAURY,
MONTGOMERY, MOORE, PERRY,
ROBERTSON, RUTHERFORD, SMITH,
STEWART, SUMNER, TROUSDALE, WAYNE,
WILLIAMSON, WILSON

District:

DBE Goal Percent:

Description: The random on-call signing on various Interstate and State Routes.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
712-01.02	LANE CLOSURE	1.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	22.000	EACH
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	30.000	DAY
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	15.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	5,000.000	LB.
713-04.02	STEEL I-BEAMS & W-F BEAMS FOR SIGN SUPPORTS	1,000.000	LB.
713-05	STEEL HOLLOW SQUARE POST (BREAKAWAY) SIGN SUPPORTS	23.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	14,000.000	LB.
713-11.01	"U" SECTION STEEL POSTS	23.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	35.000	LB.
713-11.05	SQUARE TUBE SIGN SUPPORT	23.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	100.000	S.F.

Contract ID CNX164 - BEDFORD , CHEATHAM, ETC.

Item No.	Description	Quantity	Units
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	100.000	S.F.
713-13.12	FLAT SHEET ALUM SIGNS OVERLAY (0.080" THICK)	90.000	S.F.
713-13.14	FLORESCENT YELLOW SIGN SHEETING	150.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	5,000.000	S.F.
713-15.01	REMOVAL OF EXISTING SIGN POST	3.000	EACH
713-15.03	REMOVAL OF LARGER BARRIER MOUNTED SIGNS WITH SADDLE SUPPORTS	5.000	EACH
713-15.10	REMOVAL OF SMALL BARRIER MOUNTED SIGNS W/ FLAT PLAT SUPPORTS	5.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	30.000	EACH
713-15.37	INSTALLATION OF SIGN MESSAGE(LETTER,#,ARROW,SHIELD)	10.000	S.F.
713-15.38	EXTRUDED ALUMINUM PANELS FOR OVERLAYING BACKGROUND	12.000	S.F.
713-16.90	RESET GROUND MOUNTED SIGN	40.000	EACH
713-17.02	INSTALL AUXILIARY SUPPORT FOR EXIT NUMBER PANEL	40.000	EACH
713-17.04	INSTALL AUXILIARY SUPPORT ON EXISTING SIGN	50.000	L.F.
713-20.30	SIGN ADJUSTMENTS	40.000	EACH
713-20.40	GRAFFITI REMOVAL	250.000	S.F.
713-30.09	BARRIER MOUNTED SIGN SUPPORT (DESCRIPTION) (SADDLE)	1.000	EACH
713-30.10	BARRIER MOUNTED SIGN SUPPORT (PERF/KNOCKOUT) (PERF/KNOCKOUT)	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNX172 - BEDFORD & MOORE

Contract ID: CNX172

Letting Date: May 12, 2023 10:00 AM

Projects: 02S130-M8-002 n/a
64S130-M8-002 n/a

Counties: BEDFORD, MOORE

District: **DBE Goal Percent:**

Description: The resurfacing on S.R. 130 from east of Little Flat Creek (L.M. 17.00) in Bedford County to the Coffee County line (L.M. 2.86) in Moore County.

Contract Time: DT - 10/15/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	14.720	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	400.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	200.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	37.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	7,386.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	11.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	200.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,156.000	S.F.
713-02.16	FLEXIBLE TYPE II OBJECT MARKER	34.000	EACH
713-02.34	DELINEATORS (ALL)	33.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	512.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	512.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	45.000	S.Y.

Contract ID CNX172 - BEDFORD & MOORE

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	239.000	L.F.
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	2.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	360.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	2.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	28.800	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	224.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	202.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX211 - BENTON

Contract ID: CNX211

Letting Date: May 12, 2023 10:00 AM

Projects: 03S001-F3-002
03S001-F8-002

STP/HSIP-1(450)
STP/HSIP-1(450)

Counties: BENTON

District:

DBE Goal Percent: 5.00

Description: The resurfacing on U.S. 70 (S.R. 1) from S.R. 391 (U.S. 70 BR) (L.M. 4.25) to S.R. 391 (U.S. 70 BR) (L.M. 8.63).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	150.000	S.Y.
203-06	WATER	9.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	8.560	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	1,227.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	69.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	8,922.000	TON
403-02.01	TRACKLESS TACK COAT	118.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	3,640.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	14.260	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	5,681.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	17,182.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	11.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	11.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,450.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (BIKE ROUTE D11-1)	11.000	EACH

Contract ID CNX211 - BENTON

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	374.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	100.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	474.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	429.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	291.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	1,267.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.215	L.M.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	5.000	EACH
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	6.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	141.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	16.784	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	16.784	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX163 - BENTON , CARROLL, ETC.

Contract ID: CNX163

Letting Date: May 12, 2023 10:00 AM

Projects: R4BVAR-M3-037

NA

Counties: BENTON, CARROLL, CHESTER, CROCKETT,
 DECATUR, DYER, FAYETTE, GIBSON,
 HARDEMAN, HARDIN, HAYWOOD,
 HENDERSON, HENRY, LAKE, LAUDERDALE,
 MADISON, MCNAIRY, OBION, SHELBY,
 TIPTON, WEAKLEY

District:

DBE Goal Percent:

Description: The random on-call signing on various Interstate and State Routes.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
712-01.02	LANE CLOSURE	2.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	20.000	EACH
712-08.03	ARROW BOARD (TYPE C)	12.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	15.000	DAY
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	5.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	1,000.000	LB.
713-04.02	STEEL I-BEAMS & W-F BEAMS FOR SIGN SUPPORTS	3,000.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	3,300.000	LB.
713-11.01	"U" SECTION STEEL POSTS	30.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	40.000	LB.
713-11.05	SQUARE TUBE SIGN SUPPORT	15.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	10.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	10.000	S.F.
713-13.12	FLAT SHEET ALUM SIGNS OVERLAY (0.080" THICK)	125.000	S.F.
713-13.14	FLORESCENT YELLOW SIGN SHEETING	500.000	S.F.

Contract ID CNX163 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
713-14	EXTRUDED ALUMINUM PANEL SIGNS	6,000.000	S.F.
713-15.01	REMOVAL OF EXISTING SIGN POST	10.000	EACH
713-15.03	REMOVAL OF LARGER BARRIER MOUNTED SIGNS WITH SADDLE SUPPORTS	15.000	EACH
713-15.10	REMOVAL OF SMALL BARRIER MOUNTED SIGNS W/ FLAT PLAT SUPPORTS	15.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	6.000	EACH
713-15.37	INSTALLATION OF SIGN MESSAGE(LETTER,#,ARROW,SHIELD)	10.000	S.F.
713-15.38	EXTRUDED ALUMINUM PANELS FOR OVERLAYING BACKGROUND	10.000	S.F.
713-16.90	RESET GROUND MOUNTED SIGN	10.000	EACH
713-17.02	INSTALL AUXILIARY SUPPORT FOR EXIT NUMBER PANEL	30.000	EACH
713-17.04	INSTALL AUXILIARY SUPPORT ON EXISTING SIGN	100.000	L.F.
713-20.30	SIGN ADJUSTMENTS	50.000	EACH
713-20.40	GRAFFITI REMOVAL	250.000	S.F.
713-30.08	BARRIER MOUNTED PERFORATED/KNOCKOUT SIGN SUPPORT	50.000	LB.
713-30.09	BARRIER MOUNTED SIGN SUPPORT (DESCRIPTION) (SADDLE)	1.000	EACH
713-30.10	BARRIER MOUNTED SIGN SUPPORT (PERF/KNOCKOUT) (PERF/KNOCKOUT)	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNX183 - BLEDSOE , BRADLEY, ETC.

Contract ID: CNX183

Letting Date: May 12, 2023 10:00 AM

Projects: R2BVAR-M3-023

NA

Counties: BLEDSOE, BRADLEY, CANNON, CLAY,
COFFEE, CUMBERLAND, DEKALB,
FENTRESS, FRANKLIN, GRUNDY,
HAMILTON, JACKSON, MARION, MCMINN,
MEIGS, OVERTON, PICKETT, POLK,
PUTNAM, RHEA, SEQUATCHIE, VAN BUREN,
WARREN, WHITE

District:

DBE Goal Percent:

Description: The random on-call signing on various Interstate and State Routes.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
712-01.02	LANE CLOSURE	10.000	EACH
712-01.03	LANE CLOSURE(NIGHT WORK)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	5.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	20.000	DAY
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	10.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	2,800.000	LB.
713-04.02	STEEL I-BEAMS & W-F BEAMS FOR SIGN SUPPORTS	2,200.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	12,500.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	23.000	LB.
713-11.05	SQUARE TUBE SIGN SUPPORT	15.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	140.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	10.000	S.F.
713-13.12	FLAT SHEET ALUM SIGNS OVERLAY (0.080" THICK)	15.000	S.F.
713-13.14	FLORESCENT YELLOW SIGN SHEETING	75.000	S.F.

Contract ID CNX183 - BLEDSOE , BRADLEY, ETC.

Item No.	Description	Quantity	Units
713-14	EXTRUDED ALUMINUM PANEL SIGNS	2,600.000	S.F.
713-15.01	REMOVAL OF EXISTING SIGN POST	3.000	EACH
713-15.03	REMOVAL OF LARGER BARRIER MOUNTED SIGNS WITH SADDLE SUPPORTS	15.000	EACH
713-15.10	REMOVAL OF SMALL BARRIER MOUNTED SIGNS W/ FLAT PLAT SUPPORTS	15.000	EACH
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	20.000	EACH
713-15.37	INSTALLATION OF SIGN MESSAGE(LETTER,#,ARROW,SHIELD)	15.000	S.F.
713-15.38	EXTRUDED ALUMINUM PANELS FOR OVERLAYING BACKGROUND	10.000	S.F.
713-16.90	RESET GROUND MOUNTED SIGN	10.000	EACH
713-17.02	INSTALL AUXILIARY SUPPORT FOR EXIT NUMBER PANEL	15.000	EACH
713-17.04	INSTALL AUXILIARY SUPPORT ON EXISTING SIGN	30.000	L.F.
713-20.30	SIGN ADJUSTMENTS	2.000	EACH
713-20.40	GRAFFITI REMOVAL	250.000	S.F.
713-30.09	BARRIER MOUNTED SIGN SUPPORT (DESCRIPTION) (SADDLE)	2.000	EACH
713-30.10	BARRIER MOUNTED SIGN SUPPORT (PERF/KNOCKOUT) (PERF/KNOCKOUT)	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNX165 - CHEATHAM

Contract ID: CNX165

Letting Date: May 12, 2023 10:00 AM

Projects: 11S249-M8-003
11S251-M8-002

N/A
N/A

Counties: CHEATHAM

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 251 from S.R. 249 (L.M. 0.00) to the Davidson County line (L.M. 4.01) and on S.R. 249 from S.R. 251 (L.M. 12.71) to S.R. 49 (L.M. 16.50).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	15.600	L.M.
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	250.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	500.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	60.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	8,890.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	6.400	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	5.600	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	9,056.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	80.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	2.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,838.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	516.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	516.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	110.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	282.000	L.F.

Contract ID CNX165 - CHEATHAM

Item No.	Description	Quantity	Units
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	290.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	45.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	30.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	30.600	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX166 - CLAIBORNE

Contract ID: CNX166

Letting Date: May 12, 2023 10:00 AM

Projects: 13S032-F3-003 HSIP-32(101)
 13S032-M8-003 HSIP-32(101)
 13S383-F3-002 HSIP-383(10)
 13S383-M8-002 HSIP-383(10)

Counties: CLAIBORNE

District:

DBE Goal Percent:

Description: The resurfacing on U.S. 25E (S.R. 32) from near S.R. 63 (L.M. 18.06) to near Tiprell Road (L.M. 20.56) and on S.R. 383 from U.S. 25E (S.R. 32) (L.M. 0.00) to the Virginia State line (L.M. 0.68).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	12.700	L.M.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	71.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	1,937.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	9,109.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	2.000	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	1.100	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	2.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	10,935.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	4.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	1.000	EACH
705-11.42	GR TERMINAL (ENERGY ABSORBING) MASH TL-2 (POWDER COATED)	4.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	500.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	250.000	EACH

Contract ID CNX166 - CLAIBORNE

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	1,938.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	827.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	827.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	683.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	300.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	38.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	403.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	48.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	14.500	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	14.500	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	2,000.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	11,500.000	L.F.
730-14.03	LOOP WIRE	23,000.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX159 - CUMBERLAND

Contract ID: CNX159

Letting Date: May 12, 2023 10:00 AM

Projects: 18S001-F3-005
18S001-F8-005

STP/HSIP-1(475)
STP/HSIP-1(475)

Counties: CUMBERLAND

District:

DBE Goal Percent: 7.00

Description: The resurfacing on U.S. 70 (S.R. 1) from east of Arthur Seagraves Road (L.M. 2.00) to Deep Water Road (L.M. 5.27).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	6.500	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	267.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	30.000	TON
403-02.01	TRACKLESS TACK COAT	34.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	5,247.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	10.300	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	5.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	5,107.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	10.000	EACH
712-06	SIGNS (CONSTRUCTION)	752.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	523.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	86.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	577.000	EACH

Contract ID CNX159 - CUMBERLAND

Item No.	Description	Quantity	Units
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	110.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	169.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	18.700	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	149.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	13.500	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	840.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	301.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX189 - CUMBERLAND

Contract ID: CNX189

Letting Date: May 12, 2023 10:00 AM

Projects: 18S298-F3-003 STP/HSIP-298(16)
 18S298-F8-003 STP/HSIP-298(16)
 18S298-M3-004 STP/HSIP-298(16)
 18S392-F3-002 STP/HSIP-392(7)
 18S392-F8-002 STP/HSIP-392(7)

Counties: CUMBERLAND

District: **DBE Goal Percent:** 10.00

Description: The resurfacing on S.R. 298 from U.S. 127 (S.R. 28) (L.M. 0.00) to near Jackie Drive (L.M. 2.70) and on S.R. 392 from U.S. 127 (S.R. 28) (L.M. 0.00) to near Old Mail Road (L.M. 1.90).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	9.200	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	225.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	1,408.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	4,159.000	TON
403-02.01	TRACKLESS TACK COAT	94.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	15.900	L.M.
411-03.10	ACS MIX(PG76-22) GRADING D	9,834.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	15,139.000	TON
701-02.01	CONCRETE CURB RAMP (RETROFIT)	3,225.000	S.F.
702-03	CONCRETE COMBINED CURB & GUTTER	2.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	290.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	82.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,548.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	186.000	L.F.

Contract ID CNX189 - CUMBERLAND

Item No.	Description	Quantity	Units
712-08.03	ARROW BOARD (TYPE C)	3.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	8.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	5.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	665.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	544.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	814.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	1,187.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,652.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	98.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	86.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	60.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	1,255.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.100	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	14.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	21.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	142.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	11.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	30.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	3.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	42.000	L.M.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	1,207.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	1,604.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	23.400	L.M.

Contract ID CNX189 - CUMBERLAND

Item No.	Description	Quantity	Units
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,396.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	395.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	17,994.000	L.F.
730-14.03	LOOP WIRE	42,000.000	L.F.
604-10.44	EXPANSION JOINT REPAIRS	170.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX038 - CUMBERLAND & WHITE

Contract ID: CNX038

Letting Date: May 12, 2023 10:00 AM

Projects: 18S001-F3-003 STP/HSIP-1(470)
 18S001-F8-003 STP/HSIP-1(470)
 18S001-M3-006 STP/HSIP-1(470)
 93S111-F8-003 NH-111(123)
 93S111-M3-006 NH-111(123)

Counties: CUMBERLAND, WHITE

District: **DBE Goal Percent:** 3.00

Description: The microsurfacing on U.S. 70 (S.R. 1) in Cumberland County from west of Dorton Access Road to west of Bullard Road and on S.R. 111 in White County from the Van Buren County line to Shady Oak Road.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	41.000	L.M.
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	45.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	126,587.000	S.Y.
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	425.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	3,542.000	TON
705-04.22	GUARDRAIL DELINEATION ENHANCEMENT (BI-DIRECTIONAL)	3,420.000	EACH
711-04.21	CONCRETE BARRIER DELINEATION ENHANCEMENT	372.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	212.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	52.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,877.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	122.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH

Contract ID CNX038 - CUMBERLAND & WHITE

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,087.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	570.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	373.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	2,030.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	2,890.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	893.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	23.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,680.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	1.100	L.M.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	4.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	188.000	S.F.
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	624.000	L.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	41.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	64.600	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,053.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	500.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	162.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	85.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	82.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	4,123.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX114 - DAVIDSON

Contract ID: CNX114

Letting Date: May 12, 2023 10:00 AM

Projects: 19041-3281-94
 19041-8281-14
 19S024-F3-003
 19S024-F8-003

NH/HSIP-24(80)
 NH/HSIP-24(80)
 STP-NH/HSIP-24(91)
 STP-NH/HSIP-24(91)

Counties: DAVIDSON

District:

DBE Goal Percent: 9.00

Description: The resurfacing on U.S. 70 (S.R. 24, Lebanon Pike) from near Stones River Road (L.M. 21.90) to the Wilson County line (L.M. 25.63).

Contract Time: DT - 11/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	8.700	L.M.
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	400.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	1,175.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	82.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	14,386.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	1.500	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	3.100	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	12,545.000	TON
611-01.20	ADJUSTMENT OF EXISTING MANHOLE	29.000	EACH
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	15,000.000	LB.
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	77.000	EACH
701-01.01	CONCRETE SIDEWALK (4 ")	2,175.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	4,130.000	S.F.
702-01	CONCRETE CURB	50.000	C.Y.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH

Contract ID CNX114 - DAVIDSON

Item No.	Description	Quantity	Units
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	1.000	EACH
706-01	GUARDRAIL REMOVED	25.000	L.F.
706-06.03	RADIUS RAIL	25.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	200.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,265.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	1,068.000	EACH
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	14.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (M6-6, TWO-DIRECTION STRAIGHT/TURN ARROW)	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (R10-15, TURNING VEHICLES YIELD TO PEDS/CYCLISTS)	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (D11-1, BIKE ROUTE GUIDE)	3.000	EACH
713-16.23	SIGNS (DESCRIPTION) (M1-4B, US ROUTE MARKER, US-70)	2.000	EACH
713-16.24	SIGNS (DESCRIPTION) (M3-2, DIRECTIONAL MARKER, EAST)	1.000	EACH
713-16.25	SIGNS (DESCRIPTION) (M3-4, DIRECTIONAL MARKER, WEST)	1.000	EACH
713-16.26	SIGNS (DESCRIPTION) (M6-1, ARROW, BIKE ROUTE)	2.000	EACH
713-16.27	SIGNS (DESCRIPTION) (R1-2, YIELD)	4.000	EACH
713-16.28	SIGNS (DESCRIPTION) (R3-9B, TWO WAY LEFT TURN ONLY)	1.000	EACH
713-16.29	SIGNS (DESCRIPTION) (R3-7R, RIGHT LANE MUST TURN RIGHT)	10.000	EACH
713-16.30	SIGNS (DESCRIPTION) (R3-17, BIKE LANE)	7.000	EACH

Contract ID CNX114 - DAVIDSON

Item No.	Description	Quantity	Units
713-16.31	SIGNS (DESCRIPTION) (R4-4, BEGIN RIGHT TURN LANE YIELD TO BIKES)	11.000	EACH
713-16.32	SIGNS (DESCRIPTION) (R5-2, NO TRUCKS SYMBOL)	1.000	EACH
713-16.33	SIGNS (DESCRIPTION) (R8-7, EMERGENCY STOPPING ONLY)	2.000	EACH
713-16.34	SIGNS (DESCRIPTION) (R12-1, WEIGHT LIMIT 10 TONS)	2.000	EACH
713-16.35	SIGNS (DESCRIPTION) (TN-7A, SPEED LIMIT 45 MPH)	1.000	EACH
713-16.36	SIGNS (DESCRIPTION) (W10-1, RxR)	2.000	EACH
713-16.37	SIGNS (DESCRIPTION) (W3-3, SIGNAL AHEAD)	1.000	EACH
713-16.38	SIGNS (DESCRIPTION) (W11-1, BICYCLE SYMBOL)	2.000	EACH
713-16.39	SIGNS (DESCRIPTION) (W16-18P, NOTICE)	18.000	EACH
713-20.30	SIGN ADJUSTMENTS	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	539.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	704.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	572.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	180.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,887.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	86.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	390.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	1,779.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	2,697.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	14.000	EACH
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	5.000	EACH
716-03.09	PLASTIC WORD PAVEMENT MARKING (BIKE)	9.000	EACH
716-03.10	PLASTIC WORD PAVEMENT MARKING (BUS)	11.000	EACH

Contract ID CNX114 - DAVIDSON

Item No.	Description	Quantity	Units
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	11.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	1,382.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	82.000	S.F.
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	84.000	EACH
716-04.15	PLASTIC PAVEMENT MARKING-BIKE SYMBOL/ARROW SHARED	5.000	EACH
716-04.21	GREEN TEXTURED BIKE LANE	2,824.000	S.Y.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	22.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	22.600	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	19,010.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	3,651.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	6,349.000	L.F.
730-14.03	LOOP WIRE	14,398.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX173 - DAVIDSON

Contract ID: CNX173

Letting Date: May 12, 2023 10:00 AM

Projects: 19I024-M3-012

NA

Counties: DAVIDSON

District:

DBE Goal Percent:

Description: The installation of an overhead sign structure on I-24 EB at LM 12.01 (MM 44.0).

Contract Time: DT - 2/29/2024

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-01.03	LANE CLOSURE(NIGHT WORK)	10.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	150.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	100.000	HOUR
713-09.20	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (73' +/-)	1.000	EACH
713-14	EXTRUDED ALUMINUM PANEL SIGNS	311.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	1.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX171 - DAVIDSON

Contract ID: CNX171

Letting Date: May 12, 2023 10:00 AM

Projects: 19S011-M8-003

NA

Counties: DAVIDSON

District:

DBE Goal Percent:

Description: The resurfacing on U.S. 41 (S.R. 11) from the Sumner County line (L.M. 0.00) to the Robertson County line (L.M. 3.42).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	6.900	L.M.
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	2,000.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	76.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	11,317.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	2.600	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	11,641.000	TON
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	5.000	EACH
701-02.01	CONCRETE CURB RAMP (RETROFIT)	440.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,087.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	451.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	451.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	902.000	EACH
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	10.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL	72.000	L.F.

Contract ID CNX171 - DAVIDSON

Item No.	Description	Quantity	Units
716-03.04	CROSS-WALK) PLASTIC WORD PAVEMENT MARKING (SCHOOL)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	17.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	17.100	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX174 - DAVIDSON

Contract ID: CNX174

Letting Date: May 12, 2023 10:00 AM

Projects: 19S155-M3-007

NA

Counties: DAVIDSON

District:

DBE Goal Percent:

Description: The tunnel cleaning of the Thompson Lane Underpass on S.R. 155.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
712-01.56	MAINTENANCE OF TRAFFIC () (THOMPSON LANE UNDERPASS)	12.000	EACH
713-20.40	GRAFFITI REMOVAL	250.000	S.F.
717-01	MOBILIZATION	(1)	LS
760-01.05	TUNNEL CLEANING (THOMPSON LANE TUNNELS)	12.000	EACH

() Item will be bid as lump sum.

Contract ID CNX175 - DYER

Contract ID: CNX175

Letting Date: May 12, 2023 10:00 AM

Projects: 23S003-F3-004
23S003-M8-004

HSIP-3(170)
HSIP-3(170)

Counties: DYER

District:

DBE Goal Percent:

Description: The resurfacing on U.S. 51 (S.R. 3) from the Lauderdale County line (L.M. 0.00) to Ragen Levee Road (L.M. 6.20).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	385.000	S.Y.
203-06	WATER	25.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	24.000	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (DESCRIPTION)	3,343.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	178.000	TON
403-02.01	TRACKLESS TACK COAT	127.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	4,095.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	24.000	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	15,679.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	11.000	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	9.100	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	19,003.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	11.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	7.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	2,848.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH

Contract ID CNX175 - DYER

Item No.	Description	Quantity	Units
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	820.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	32.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	852.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	186.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	412.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	269.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.130	L.M.
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	28.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	28.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,164.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-12.01	CONDUIT 1" DIAMETER (PVC SCHEDULE 40)	50.000	L.F.
730-14.01	SHIELDED DETECTOR CABLE	50.000	L.F.
730-14.02	SAW SLOT	956.000	L.F.
730-14.03	LOOP WIRE	2,352.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX153 - FENTRESS & PICKETT

Contract ID: CNX153

Letting Date: May 12, 2023 10:00 AM

Projects: 25S028-F3-006 HSIP-28(89)
 25S028-M8-006 n/a
 69S028-F3-002 NH/HSIP-28(88)
 69S028-F8-002 NH/HSIP-28(88)

Counties: FENTRESS, PICKETT

District:

DBE Goal Percent:

Description: The resurfacing on U.S. 127 (S.R. 28) from north of Joe York Road (L.M. 29.72) in Fentress County to north of Joe Sells Road (L.M. 1.59) in Pickett County.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	10.900	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	384.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	60.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	63.000	TON
403-02.01	TRACKLESS TACK COAT	40.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	6,140.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	6.300	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	8.700	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	5,664.000	TON
705-04.22	GUARDRAIL DELINEATION ENHANCEMENT (BI-DIRECTIONAL)	1,850.000	EACH
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	3.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	40.000	EACH
712-06	SIGNS (CONSTRUCTION)	693.000	S.F.

Contract ID CNX153 - FENTRESS & PICKETT

Item No.	Description	Quantity	Units
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	455.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	184.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	225.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	32.700	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	184.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	21.900	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	525.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX184 - FRANKLIN

Contract ID: CNX184

Letting Date: May 12, 2023 10:00 AM

Projects: 26455-3419-04

NA

Counties: FRANKLIN

District:

DBE Goal Percent:

Description: The construction of a concrete I-beam bridge on Old Decherd Road over Wagner Creek (L.M. 0.25), including grading, drainage, and paving.

Contract Time: DT - 8/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (24" CMP ,20+50.28)	150.000	L.F.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (SEE PLANS)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	950.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	670.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	231.000	C.Y.
203-06	WATER	9.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	236.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	1,594.000	C.Y.
209-05	SEDIMENT REMOVAL	95.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	5,852.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	10.000	EACH
209-09.01	SANDBAGS	20.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	300.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	399.000	TON
303-01.02	GRANULAR BACKFILL (BRIDGES)	76.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	619.000	TON

Contract ID CNX184 - FRANKLIN

Item No.	Description	Quantity	Units
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	86.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	1.300	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	4.500	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	938.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	143.200	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	88.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	73,311.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	822.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	206,304.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	214.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	230.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,147.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
606-03.03	STEEL PILES (12 INCH)	2,977.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	62.000	EACH
607-39.04	30" PIPE CULVERT (SIDE DRAIN)	146.000	L.F.
610-10.46	DECK DRAINS (DESCRIPTION) (SEE PLANS)	27.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	2.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	93.000	LB.
611-07.33	30IN ENDWALL (SIDE DRAIN)	1.000	EACH
615-01.02	PRESTRESSED CONCRETE I-BEAM (TYPE II)	1,011.000	L.F.
620-05	CONCRETE PARAPET WITH STRUCTURAL TUBING	405.000	L.F.
621-03.03	24" TEMPORARY DRAINAGE PIPE	182.000	L.F.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	4.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	4.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	50.000	L.F.
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH

Contract ID CNX184 - FRANKLIN

Item No.	Description	Quantity	Units
706-01	GUARDRAIL REMOVED	186.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	2,500.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	368.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	23.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	834.000	TON
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	184.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	28.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	44.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	46.000	EACH
712-06	SIGNS (CONSTRUCTION)	474.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	108.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-09.03	WET REFLECTIVE PAVEMENT MARKING(6" LINE)	0.200	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	0.700	L.M.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	880.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	589.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	220.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	1,700.000	L.F.
801-01.37	NATVE SEED MX ENCAPSULATION & CLEAR ZONE	24.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	32.000	UNIT
801-03	WATER (SEEDING & SODDING)	22.000	M.G.
803-01	SODDING (NEW SOD)	1,638.000	S.Y.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	4,000.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX177 - GILES

Contract ID: CNX177

Letting Date: May 12, 2023 10:00 AM

Projects: 28NMSC-S3-002 NA

Counties: GILES

District:

DBE Goal Percent:

Description: The installation of a new 40' x 120' covered salt bin, roof only, located at 2375 Industrial Loop Road in Pulaski.

Contract Time: DT - 8/31/2023

Item No.	Description	Quantity	Units
680-01.09	SALT BIN, ROOF ONLY (40' x 120')	(1)	LS
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX194 - GILES & LINCOLN

Contract ID: CNX194

Letting Date: May 12, 2023 10:00 AM

Projects: 52S110-F3-003
52S110-F8-003

STP/HSIP-110(8)
STP/HSIP-110(8)

Counties: GILES, LINCOLN

District:

DBE Goal Percent: 6.00

Description: The resurfacing on S.R. 110 from S.R. 7 (L.M. 0.00) in Giles County to S.R. 274 (L.M. 8.61) in Lincoln County.

Contract Time: DT - 10/15/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	17.900	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	200.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	200.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	4,500.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	48.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	9,697.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	12.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	188.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,247.000	S.F.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	25.000	EACH
713-02.16	FLEXIBLE TYPE II OBJECT MARKER	59.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	605.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	6.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	55.000	S.Y.

Contract ID CNX194 - GILES & LINCOLN

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	423.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	3.000	EACH
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	93.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.100	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	1.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	110.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	34.500	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX210 - HAMILTON

Contract ID: CNX210

Letting Date: May 12, 2023 10:00 AM

Projects: 33052-4259-04

NH-153(18)

Counties: HAMILTON

District:

DBE Goal Percent: 5.00

Description: The slope stabilization on S.R. 153 near L.M. 7.10.

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (RT SIDE STA. 10+20.00 TO STA. 11+15.00)	95.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	10,327.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	14,663.000	TON
203-04	PLACING AND SPREADING TOPSOIL	91.000	C.Y.
203-06	WATER	1.100	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-05	SEDIMENT REMOVAL	27.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	72.000	L.F.
209-09.04	SEDIMENT FILTER BAG(15' X 10')	1.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	380.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	210.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	7,620.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	39.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	38.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	0.500	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	1.700	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.210	TON

Contract ID CNX210 - HAMILTON

Item No.	Description	Quantity	Units
407-20.05	SAW CUTTING ASPHALT PAVEMENT	349.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	40.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	245.000	S.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	6.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	302.000	L.F.
706-01	GUARDRAIL REMOVED	300.000	L.F.
706-05	GUARDRAIL ADJUSTMENT	300.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	45.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	20.000	EACH
712-06	SIGNS (CONSTRUCTION)	332.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	35.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	12.000	S.Y.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.200	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	257.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	2,161.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	70.000	L.F.
801-02.08	TEMPORARY SEEDING (WITHOUT MULCH)	1.000	UNIT
801-03	WATER (SEEDING & SODDING)	4.000	M.G.

() Item will be bid as lump sum.

Contract ID CNX181 - HAMILTON

Contract ID: CNX181

Letting Date: May 12, 2023 10:00 AM

Projects: 33PARK-M8-002
33PARK-M8-003

N/A
N/A

Counties: HAMILTON

District:

DBE Goal Percent:

Description: The resurfacing in Harrison Bay State Park including cold planing, bituminous seal coat and full depth reclamation on various routes.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
203-06	WATER	12.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	11.200	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,725.000	TON
304-01.04	PROCESSING (RECLAIMED BASE MATERIAL)	4,653.000	S.Y.
304-01.08	PORTLAND CEMENT (FULL DEPTH PAVEMENT RECLAMATION)	64.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	4,312.000	TON
403-02.01	TRACKLESS TACK COAT	37.000	TON
405-01.01	BITUMINOUS MATERIAL (BSC)	7.000	TON
405-01.02	MINERAL AGGREGATE (BSC)	55.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	4,633.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	207.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,595.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	231.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R1-1, STOP SIGN, (36"x36"))	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (R2-1, YEILD SIGN,	1.000	EACH

Contract ID CNX181 - HAMILTON

Item No.	Description	Quantity	Units
716-01.21	(36"x36"x36") SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	150.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	40.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	317.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	380.000	L.F.
716-02.22	PLASTIC AERIAL SPEED BARS	24.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	61.000	EACH
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	12.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	220.000	S.F.
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	96.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	13.200	L.M.
716-12.01	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)	14.500	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX190 - HAMILTON

Contract ID: CNX190

Letting Date: May 12, 2023 10:00 AM

Projects: 33SVAR-M3-003

NA

Counties: HAMILTON

District:

DBE Goal Percent:

Description: The tunnel cleaning of the McCallie Tunnel on U.S. 11 (U.S. 64, S.R. 2), the Stringers Ridge Tunnel on U.S. 127 (S.R. 8), and the Bachman Tubes on U.S. 41 (U.S. 76, S.R. 8).

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
104-03.71	ADDITIONAL WORK (DESCRIPTION) (CLEANING OF PORTAL FACADES @ MCCALLIE TUNNELS)	7,850.000	S.F.
712-01.52	MAINTENANCE OF TRAFFIC () (MCCALLIE TUNNELS)	12.000	EACH
712-01.53	MAINTENANCE OF TRAFFIC () (BACHMAN TUNNELS)	12.000	EACH
712-01.54	MAINTENANCE OF TRAFFIC () (STRINGERS RIDGE TUNNEL)	12.000	EACH
713-20.40	GRAFFITI REMOVAL	250.000	S.F.
717-01	MOBILIZATION	(1)	LS
719-02.01	REMOVAL AND DISPOSAL OF LITTER	36.000	CYCL
760-01.01	TUNNEL CLEANING (MCCALLIE TUNNELS)	12.000	EACH
760-01.02	TUNNEL CLEANING (BACHMAN TUNNELS)	12.000	EACH
760-01.03	TUNNEL CLEANING (STRINGER RIDGE TUNNEL)	12.000	EACH

() Item will be bid as lump sum.

Contract ID CNX091 - HARDIN

Contract ID: CNX091

Letting Date: May 12, 2023 10:00 AM

Projects: 36010-3227-94

BH-STP/HIP-128(29)

Counties: HARDIN

District:

DBE Goal Percent: 6.00

Description: The rehabilitation of the bridge on S.R. 128 over the Pickwick Dam (L.M. 0.84).

Contract Time: DT - 8/31/2026

Item No.	Description	Quantity	Units
109-10.01	TRAINEE	4,500.000	HOUR
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE DECK, PARAPETS AND SIDEWALKS)	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CANTILEVER BRACKETS)	(1)	LS
203-01.60	ROAD & DRAINAGE EXCAVATION (DESCRIPTION) (DRAINAGE DITCH)	136.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	450.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	14.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	119.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.200	TON
411-02.10	ACS MIX(PG70-22) GRADING D	92.000	TON
411-02.11	ACS MIX(PG70-22) GRADING E RDWY	45.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	678.000	S.Y.
602-10.34	MISCELLANEOUS STRUCTURAL STEEL REPAIRS	95,181.000	LB.
602-10.70	STRUCTURAL STEEL CRACK REPAIR	6.000	EACH
603-01	PAINT STEEL STRUCTURE	(1)	LS
603-02.20	SPOT PAINTING EXISTING STEEL STRUCTURES	24,657.000	S.F.
604-02.03	EPOXY COATED REINFORCING STEEL	1,213,119.000	LB.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	8,054.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	12,577.000	S.Y.
604-06.01	LIGHTWEIGHT CONCRETE (BRIDGES)	3,997.000	C.Y.

Contract ID CNX091 - HARDIN

Item No.	Description	Quantity	Units
604-10.05	CONCRETE	40.000	S.F.
604-10.32	EXPANSION JOINT REPAIRS (TYPE A)	69.000	L.F.
604-10.54	CONCRETE REPAIRS	21.000	S.F.
604-10.60	EXPANSION JOINT REPAIRS (MODULAR TYPE)	173.000	L.F.
604-10.90	MISCELLANEOUS BRIDGE ITEMS	(1)	LS
604-11.01	EXPANSION DEVICE (DESCRIPTION) (STRIPSEAL)	207.000	L.F.
610-10.04	DRAINAGE SYSTEM - BRIDGE DECK(DESCRIPTION) (PVC)	(1)	LS
621-05.02	TEMPORARY SHORING	(1)	LS
702-03	CONCRETE COMBINED CURB & GUTTER	3.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	75.000	L.F.
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	3.000	EACH
707-07.01	CHAIN-LINK FENCE (BRIDGES)	8,536.000	S.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	450.000	L.F.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	178.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	4,474.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	3.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	17.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	57.000	EACH
712-06	SIGNS (CONSTRUCTION)	816.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	120.000	L.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	43,616.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	96.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
714-01	STRUCTURAL LIGHTING	(1)	LS
714-04.03	CONDUIT (DESCRIPTION) (2 1/2" FEED CONDUIT)	20.000	L.F.
714-06.06	CABLE (1/C # 4 AWG)	10,930.000	L.F.
714-08.30	REMOVE & RELOCATE LIGHT STANDARD	40.000	EACH

Contract ID CNX091 - HARDIN

Item No.	Description	Quantity	Units
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	3.010	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	231.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX191 - HAYWOOD & TIPTON

Contract ID: CNX191

Letting Date: May 12, 2023 10:00 AM

Projects: 38010-3205-94
84014-3221-94

HSIP/PHSIP-180(12)
PHSIP-206(13)

Counties: HAYWOOD, TIPTON

District:

DBE Goal Percent: 8.00

Description: Miscellaneous safety improvements on S.R. 180 from Saint Luke Road to near the bridge over Branch (L.M. 3.00 - 9.00) and on S.R. 206 from Harris Road to near Old Memphis Road (L.M. 3.29 - 6.40), including resurfacing.

Contract Time: DT - 11/30/2023

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	194.000	S.Y.
203-05	UNDERCUTTING	35.000	C.Y.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	14.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	58.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	8.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	0.500	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	0.500	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	13.500	TON
411-01.10	ACS MIX(PG64-22) GRADING D	3,039.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (4IN WIDTH)	6.250	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	42,205.000	S.Y.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	5.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	1,621.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	720.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	5.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CNX191 - HAYWOOD & TIPTON

Item No.	Description	Quantity	Units
712-04.50	BARRIER RAIL DELINEATOR	3.000	EACH
713-02.04	DELINEATOR (MILE MARKER) & STEEL POST	6.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	100.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	74.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	496.000	L.F.
713-02.22	BARRIER WALL DELINEATION ENHANCEMENT	210.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	1,141.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	3,147.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	478.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	509.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	58.000	EACH
713-20.30	SIGN ADJUSTMENTS	1.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	25.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	635.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	215.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	223.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	4.000	EACH
716-03.07	PLASTIC WORD PAVEMENT MARKING (STOP)	4.000	EACH
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	111,344.000	L.F.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	125.000	L.F.
716-12.01	ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)	10.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	13.000	L.M.
716-14.01	PROFILED THERMO PVMT MRKNG AUDIBLE (4IN)	12.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX215 - HENRY

Contract ID: CNX215

Letting Date: May 12, 2023 10:00 AM

Projects: 40S069-F3-002
40S069-F8-002

STP/HSIP-69(110)
STP/HSIP-69(110)

Counties: HENRY

District:

DBE Goal Percent: 6.00

Description: The resurfacing on S.R. 69A from near Mays Bridge Road (L.M. 6.21) to S.R. 69 (L.M. 12.54).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	150.000	S.Y.
203-06	WATER	13.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	12.660	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	760.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	69.000	TON
307-02.09	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING CAM	7,411.000	TON
403-02.01	TRACKLESS TACK COAT	112.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	9,146.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	7.180	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	8.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	15,578.000	TON
611-03.04	GRAY IRON CASTINGS (CATCHBASIN)	1,250.000	LB.
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	5.000	EACH
701-01.01	CONCRETE SIDEWALK (4 ")	75.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	665.000	S.F.
701-02.03	CONCRETE CURB RAMP	165.000	S.F.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH

Contract ID CNX215 - HENRY

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,253.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	428.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	18.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	14.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	965.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	432.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	4.000	EACH
716-03.06	PLASTIC WORD PAVEMENT MARKING (SIGNAL AHEAD)	3.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	24.860	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	24.860	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	600.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-12.01	CONDUIT 1" DIAMETER (PVC SCHEDULE 40)	50.000	L.F.
730-14.01	SHIELDED DETECTOR CABLE	50.000	L.F.
730-14.02	SAW SLOT	650.000	L.F.
730-14.03	LOOP WIRE	1,644.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX203 - HOUSTON

Contract ID: CNX203

Letting Date: May 12, 2023 10:00 AM

Projects: 42950-3507-04

N/A

Counties: HOUSTON

District:

DBE Goal Percent:

Description: The construction of two concrete box bridges on a S.I.A. route serving Magnum Manufacturing, including grading, drainage, and paving.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (66" CMP, STA 171+16.01 AND 66" CMP, STA 171+23.82)	101.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (66" CMP, STA 2+01.40 AND 66" CMP, STA 2+11.70)	88.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	600.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	241.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	92.000	C.Y.
203-20.01	CHANNEL SUBSTRATE	142.000	C.Y.
209-05	SEDIMENT REMOVAL	30.000	C.Y.
209-06.02	12" DIA COIR LOG (DESCRIPTION) (FOR HIGH FLOW LOW FLOW CHANNEL)	235.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,026.000	L.F.
209-09.03	SEDIMENT FILTER BAG (15' X 15')	6.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	286.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,329.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	38.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	276.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	168.000	TON

Contract ID CNX203 - HOUSTON

Item No.	Description	Quantity	Units
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	3.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	10.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	168.000	TON
707-03.20	DRIVE GATE (STOCK FENCE) (DESCRIPTION)	1.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	637.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	178.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	245.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	25.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	18.000	EACH
712-06	SIGNS (CONSTRUCTION)	204.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	108.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	556.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	15.000	UNIT
801-01.35	GRASS SEED MIX (RIPZN/FLPL) W/MULCH	2.000	UNIT
801-03	WATER (SEEDING & SODDING)	10.000	M.G.
803-01	SODDING (NEW SOD)	842.000	S.Y.
204-08	FOUNDATION FILL MATERIAL	50.000	C.Y.
303-01.01	GRANULAR BACKFILL (ROADWAY)	863.000	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	269.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	62,840.000	LB.
790-42.02	CONDUIT - ROLLED PLASTIC 2IN DIA	105.000	L.F.
797-40.03	MULTIPAIR SHIELDED INSTRUMENTATION CABLE	125.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX118 - HUMPHREYS

Contract ID: CNX118

Letting Date: May 12, 2023 10:00 AM

Projects: 43S001-F3-005
43S001-M3-003

BR-HIP-1(462)
ER-STP-1(478)

Counties: HUMPHREYS

District: **DBE Goal Percent:** 9.50

Description: The construction of concrete box beam bridges on U.S. 70 (S.R. 1) over Trace Creek (EB - L.M. 6.53, WB - L.M. 6.55), including grading, drainage, and paving.

Contract Time: DT - 5/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,680.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,116.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	12,724.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	5,225.000	C.Y.
203-06	WATER	103.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	1,110.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-05	SEDIMENT REMOVAL	153.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	6,122.000	L.F.
209-08.05	ENHANCED SILT FENCE CHECK (V-DITCH)	6.000	EACH
209-08.06	ENHANCED SILT FENCE CHECK (TRAPEZOIDAL)	4.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	4.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	500.000	S.Y.
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	3.000	EACH

Contract ID CNX118 - HUMPHREYS

Item No.	Description	Quantity	Units
209-65.04	TEMPORARY IN STREAM DIVERSION	670.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	5,922.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,493.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	1,214.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	15.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	54.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	101.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	966.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	1.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	276.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	54.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	216.000	L.F.
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	52.000	L.F.
611-07.32	24IN ENDWALL (SIDE DRAIN)	4.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.73	18IN ENDWALL (MEDIAN DRAIN)	3.000	EACH
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	2.000	EACH
621-01.01	TEMPORARY STRUCTURE (DESCRIPTION - STATION) (MEDIAN CROSSOVER PIPE - STATION 1466+77.00)	(1)	LS
621-01.02	TEMPORARY STRUCTURE (DESCRIPTION - STATION) (MEDIAN CROSSOVER PIPE - STATION 1476+89.50)	(1)	LS
621-01.03	TEMPORARY STRUCTURE (DESCRIPTION - STATION) (HAUL ROAD 2 - STATION 20+50.00)	(1)	LS
621-01.04	TEMPORARY STRUCTURE (DESCRIPTION - STATION) (HAUL ROAD 3 - STATION 30+50.00)	(1)	LS
621-05.01	TEMPORARY SHORING	2,730.000	S.F.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	1.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	788.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	8.000	EACH

Contract ID CNX118 - HUMPHREYS

Item No.	Description	Quantity	Units
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	8.000	EACH
706-01	GUARDRAIL REMOVED	1,012.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	202.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	6.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	4,688.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	100.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	720.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,053.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	500.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	28,385.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	36.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,090.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	72.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	188.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	52.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	10.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	144.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	104.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.300	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	344.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	1,820.000	L.F.
801-01	SEEDING (WITH MULCH)	97.000	UNIT

Contract ID CNX118 - HUMPHREYS

Item No.	Description	Quantity	Units
801-01.07	TEMPORARY SEEDING (WITH MULCH)	91.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	4.000	UNIT
801-02.08	TEMPORARY SEEDING (WITHOUT MULCH)	12.000	UNIT
801-02.15	FERTILIZER	1.000	TON
801-03	WATER (SEEDING & SODDING)	45.000	M.G.
803-01	SODDING (NEW SOD)	3,399.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	1,292.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXT BR 43-SR001-6.53-LT (EB))	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXT BR 43-SR001-6.53-LT (WB))	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	200.000	C.Y.
204-05.15	EXPLORATORY DRILLING	403.000	L.F.
204-14	CORE DRILLING FOR PILES(ROCK)	434.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	100.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	185,770.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	364.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	45,644.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	336.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	594.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	2,606.000	S.Y.
604-04.03	BRIDGE END DRAINS(2'X8')	4.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	2,120.000	S.Y.
606-20.01	TEST PILES (STEEL PIPE PILES, 18-INCH)	240.000	L.F.
606-20.02	LOADING TEST (STEEL PIPE PILES, 18-INCH)	1.000	EACH
606-20.03	STEEL PIPE PILES (18-INCH)	2,000.000	L.F.
606-20.06	PILE TIPS (STEEL PIPE PILES, 18-INCH)	44.000	EACH
606-22.13	STEEL PIPE PILES (24 IN)	1,680.000	L.F.
606-22.14	PILE TIPS (STEEL PIPE PILES 24 IN)	28.000	EACH
606-22.15	TEST PILES (STEEL PIPE PILES 24 IN)	320.000	L.F.
606-22.16	LOAD TESTING (STEEL PIPE PILES 24 IN)	1.000	EACH

Contract ID CNX118 - HUMPHREYS

Item No.	Description	Quantity	Units
615-02.25	PRESTRESSED CONCRETE BOX BEAM (39" X 48")	2,094.000	L.F.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	1,256.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	336.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	60.000	L.F.
791-01.04	4IN STEEL GAS MAIN	75.000	L.F.
791-04.22	HDD 4IN STEEL PIPE - UNCONSOLIDATED	630.000	L.F.
791-06.32	CONNECT TO 4IN EX. STL MAIN W/ STOPPLE	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNX170 - HUMPHREYS

Contract ID: CNX170

Letting Date: May 12, 2023 10:00 AM

Projects: 43003-3243-94
43003-4243-04

HSIP-1(415)
HSIP-1(415)

Counties: HUMPHREYS

District:

DBE Goal Percent:

Description: The resurfacing on U.S. 70 (S.R. 1) from the Benton County line (L.M. 0.00) to west of the Trace Creek bridge (L.M. 5.75).

Contract Time: DT - 11/15/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	3.500	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	463.000	TON
307-01.07	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M	500.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	83.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	13,158.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	2.800	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	13,038.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	3.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	3.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	75.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
706-01	GUARDRAIL REMOVED	150.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	2.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,532.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (W10-1, RAILROAD	2.000	EACH

Contract ID CNX170 - HUMPHREYS

Item No.	Description	Quantity	Units
713-16.21	CROSSING) SIGNS (DESCRIPTION) (W10-3R, RAILROAD CROSSING ON SIDE ROAD)	2.000	EACH
713-16.22	SIGNS (DESCRIPTION) (W10-3L, RAILROAD CROSSING ON SIDE ROAD)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	617.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	788.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	202.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	166.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	9.000	EACH
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.100	L.M.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	6.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	9.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	375.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	1.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	25.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	26.500	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,790.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,200.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX151 - HUMPHREYS

Contract ID: CNX151

Letting Date: May 12, 2023 10:00 AM

Projects: 43455-3433-04

N/A

Counties: HUMPHREYS

District:

DBE Goal Percent:

Description: The construction of a concrete box beam bridge on Weed Lane over Blue Creek (L.M. 0.17), including grading, drainage, and paving.

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,061.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	9,500.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	237.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	563.000	C.Y.
203-05	UNDERCUTTING	3,650.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-05	SEDIMENT REMOVAL	34.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	2,100.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	854.000	L.F.
209-08.07	ROCK CHECK DAM	12.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	248.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,068.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	458.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	261.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	4.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	12.000	TON

Contract ID CNX151 - HUMPHREYS

Item No.	Description	Quantity	Units
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	153.000	TON
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	767.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	155.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	1,919.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	30.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	112.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	781.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	368.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	218.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	367.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	58.000	UNIT
801-03	WATER (SEEDING & SODDING)	35.000	M.G.
803-01	SODDING (NEW SOD)	2,883.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 43-0A279-0.17)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	160.000	C.Y.
303-01.02	GRANULAR BACKFILL (BRIDGES)	40.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	29,931.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	56.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	10,026.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	101.000	C.Y.
604-03.74	CLASS X CONCRETE	14.000	C.Y.

Contract ID CNX151 - HUMPHREYS

Item No.	Description	Quantity	Units
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	625.000	S.Y.
606-02.03	STEEL PILES (10 INCH)	606.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	12.000	EACH
606-22.13	STEEL PIPE PILES (24 IN)	254.000	L.F.
606-22.14	PILE TIPS (STEEL PIPE PILES 24 IN)	4.000	EACH
615-02.37	PRESTRESSED CONCRETE BOX BEAM (30" X 36")	406.000	L.F.
620-06	CONCRETE RAILING	328.000	L.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	32.000	C.Y.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	90.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	48.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX086 - HUMPHREYS

Contract ID: CNX086

Letting Date: May 12, 2023 10:00 AM

Projects: 43HPB1-S3-002
43HPB1-S3-003

NA
NA

Counties: HUMPHREYS

District:

DBE Goal Percent:

Description: The construction of concrete box beam bridges on East Blue Creek Road over Blue Creek (L.M. 4.26 and L.M. 5.20), including grading, drainage, and paving.

Contract Time: DT - 10/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,145.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	873.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	231.000	C.Y.
209-05	SEDIMENT REMOVAL	45.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	3,320.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	20.000	EACH
209-09.04	SEDIMENT FILTER BAG(15' X 10')	4.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	290.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	875.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE A)	90.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	224.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	4.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	11.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	138.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	101.000	S.Y.
604-07.01	RETAINING WALL (DESCRIPTION) (WALL NO. 1)	565.000	S.F.

Contract ID CNX086 - HUMPHREYS

Item No.	Description	Quantity	Units
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	275.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	2.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	8.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	6.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	350.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	160.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-05.01	WARNING LIGHTS (TYPE A)	12.000	EACH
712-06	SIGNS (CONSTRUCTION)	285.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	144.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	280.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	250.000	L.F.
801-01	SEEDING (WITH MULCH)	33.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	33.000	UNIT
801-03	WATER (SEEDING & SODDING)	7.000	M.G.
803-01	SODDING (NEW SOD)	650.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	2,950.000	S.Y.
806-02.03	PROJECT MOWING	4.000	CYCL
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BR. NO. 43-0A254-5.20)	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BR. NO. 43-0A254-04.26)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	808.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	292.000	C.Y.
204-05	ROCK DRILLING (BRIDGES)	60.000	L.F.
204-05.01	CORE DRILLING AND SAMPLING	70.000	L.F.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (BENT NO. 1, STA. 56+64.85)	(1)	LS
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (BENT NO 1, STA. 56+73.92)	(1)	LS
303-01.02	GRANULAR BACKFILL (BRIDGES)	90.000	TON

Contract ID CNX086 - HUMPHREYS

Item No.	Description	Quantity	Units
604-02.03	EPOXY COATED REINFORCING STEEL	51,025.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	198.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	31,950.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	153.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,061.000	S.Y.
606-02.03	STEEL PILES (10 INCH)	936.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	24.000	EACH
615-02.04	PRESTRESSED CONCRETE BOX BEAM (27" X 36")	602.000	L.F.
620-06	CONCRETE RAILING	518.000	L.F.
625-02.01	DRILLED SHAFT-SOIL (DIA.) (4'-6" DIAMETER)	51.000	V.F.
625-02.13	DRILLED SHAFT-ROCK (DIA.) (4'-0" DIAMETER)	16.000	V.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	38.000	C.Y.
625-02.44	DRILLED SHAFT REINFORCING STEEL	6,881.000	LB.
709-05.08	MACHINED RIP-RAP (CLASS B)	1,079.000	TON
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	178.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	80.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX137 - JEFFERSON

Contract ID: CNX137

Letting Date: May 12, 2023 10:00 AM

Projects: 45945-3694-14

STP-4500(31)

Counties: JEFFERSON

District:

DBE Goal Percent: 6.00

Description: The stream mitigation for Anderson Branch on the Bush Brothers property.

Contract Time: DT - 4/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (18"x24" OVAL CONC., STR-1 STA. 26+64.23)	20.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (48" CMP, STR-1 STA. 27+31.37)	20.000	L.F.
202-02.03	REMOVAL OF PIPE (SIZE ,STA.) (36" CMP , STR-1 STA. 32+62.80)	20.000	L.F.
202-02.04	REMOVAL OF PIPE (SIZE ,STA.) (36" CMP, STR-1 STA. 37+73.48)	40.000	L.F.
202-02.05	REMOVAL OF PIPE (SIZE ,STA.) (48" CMP, STR-1 STA. 48+03.23)	20.000	L.F.
202-02.06	REMOVAL OF PIPE (SIZE ,STA.) (48" CMP, STR-4 STA. 07+05.33)	31.000	L.F.
202-02.07	REMOVAL OF PIPE (SIZE ,STA.) (24" CMP, STR-4 TRIB STA. 00+11.73)	29.000	L.F.
202-02.08	REMOVAL OF PIPE (SIZE ,STA.) (24" CMP, STR-5 STA. 06+76.78)	28.000	L.F.
202-02.09	REMOVAL OF PIPE (SIZE ,STA.) (48" HDPE, STR-5 STA. 14+59.80)	21.000	L.F.
203-01.13	ROAD & DRAINAGE EXCAVATION (STREAM MITIGATION)	3,581.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	6,084.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	1,464.000	C.Y.
203-06	WATER	10.000	M.G.

Contract ID CNX137 - JEFFERSON

Item No.	Description	Quantity	Units
203-15.03	COMPACTED CLAY	435.000	C.Y.
203-20.01	CHANNEL SUBSTRATE	67.000	C.Y.
209-03.34	STREAM MITIGATION-LOG VANES	215.000	L.F.
209-03.36	STREAM MITIGATION-STEP POOL	41.000	EACH
209-03.37	STREAM MITIGATION CROSS VANE STRUCTURE	88.000	EACH
209-03.38	STREAM MITIGATION -J -HOOK	98.000	EACH
209-03.40	STREAM MITIGATION - LOG RIFFLE	1,310.000	L.F.
209-03.41	STREAM MITIGATION - BOULDER RIFFLE	1,000.000	L.F.
209-03.42	STREAM MITIGATION - LIVE BRUSH LAYERING	1,780.000	L.F.
209-03.54	STREAM MITIGATION - CROSS VANE STRUCTURE W/STEP	58.000	EACH
209-03.62	STREAM MITIGATION - ROOT WAD	29.000	EACH
209-03.67	STREAM MITIGATION – WOOD TOE W/REINFORCED EARTH	1,780.000	L.F.
209-03.68	STREAM MITIGATION – BOULDER TOE	255.000	L.F.
209-03.99	PROTECTED AREA MARKER (WHITE WITH DECAL)	132.000	EACH
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	18,840.000	L.F.
209-09.01	SANDBAGS	300.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	30.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	38.000	S.Y.
209-65.01	TEMPORARY STREAM DIVERSION (DESCRIPTION) (PUMP AROUND)	(1)	LS
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,067.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	100.000	TON
607-03.30	18" PIPE CULVERT	40.000	L.F.
607-09.30	48" PIPE CULVERT	120.000	L.F.
607-11.30	60" PIPE CULVERT	80.000	L.F.
621-03.02	18" TEMPORARY DRAINAGE PIPE	180.000	L.F.
621-03.04	30" TEMPORARY DRAINAGE PIPE	30.000	L.F.
707-03.01	STOCK FENCE	22,250.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY(STOCK FENCE)	66.000	EACH

Contract ID CNX137 - JEFFERSON

Item No.	Description	Quantity	Units
707-06.05	REMOVAL OF FENCE (DESCRIPTION) (EXISTING CATTLE FENCE WITHIN EASEMENT BNDRY)	(1)	LS
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,609.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	668.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	284.000	TON
709-05.81	ROCK RIFFLES	(1)	LS
709-11.01	BOULDER RIP-RAP (SIZE) (2.5 FT X 2 FT X 1 FT)	15.000	C.Y.
709-11.02	BOULDER RIP-RAP (SIZE) (3 FT X 2.5 FT X 1 FT)	13.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	80.000	S.F.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,735.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	282.000	S.Y.
795-02.04	6IN HDPE WATER LINE	800.000	L.F.
795-02.05	8IN HDPE WATER LINE	1,100.000	L.F.
795-13.02	HDPE FITTINGS	170.000	LB.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	1,146.000	UNIT
801-01.35	GRASS SEED MIX (RIPZN/FLPL) W/MULCH	793.000	UNIT
801-02.15	FERTILIZER	7.000	TON
801-03	WATER (SEEDING & SODDING)	10.000	M.G.
801-09	AGRICULTURAL LIME	19.000	TON
802-02.30	CUTTINGS: SALIX NIGRA (18IN-24IN LENGTH)	2,761.000	EACH
802-02.32	CUTTINGS: CORNUS AMOMUM (18IN-24IN)	2,761.000	EACH
802-02.33	CUTTINGS: SAMBUCUS CANADENSIS (18IN-24IN)	2,761.000	EACH
802-02.37	CUTTINGS: ALNUS SERRULATA (18IN-24IN)	2,761.000	EACH
802-12.14	DIOSPYROS VIRGINIANA (PERSIMMON SEEDLNG B.R.)	1,122.000	EACH
802-12.17	JUGLANS NIGRA (BLACK WALNUT SEEDLNG B.R.)	1,683.000	EACH
802-12.19	LIRIODENDRON TULIPIFERA (TULIP POPLAR SEEDLNG B.R.)	1,683.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	1,683.000	EACH

Contract ID CNX137 - JEFFERSON

Item No.	Description	Quantity	Units
802-12.40	SALIX NIGRA (BLACK WILLOW SEEDLING B.R.)	1,122.000	EACH
802-12.45	CARPINUS CAROLINIANA (AMERICAN HORNBEAM SEEDLING B.R.)	1,683.000	EACH
802-12.46	QUERCUS SHUMARDII (SHUMARD OAK SEEDLING B.R.)	1,122.000	EACH
802-12.53	QUERCUS PAGODA (CHERRYBARK OAK SEEDLING B.R.)	1,122.000	EACH
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	11,375.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNX208 - KNOX

Contract ID: CNX208

Letting Date: May 12, 2023 10:00 AM

Projects: 47S131-F3-004 HSIP-131(55)
 47S131-M3-005 HSIP-131(55)
 47S131-M8-004 HSIP-131(55)

Counties: KNOX

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 131 from U.S. 11 (U.S. 70, S.R. 1) (L.M. 0.00) to near S.R. 162 (L.M. 3.07), including bridge expansion joint repair.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	6.100	L.M.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	54.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	8,262.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,007.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	228.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	114.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,225.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	405.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	325.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	405.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	275.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	1,070.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	1,275.000	S.Y.

Contract ID CNX208 - KNOX

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,420.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	98.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	2,298.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	1.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	4.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	2.000	EACH
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	11.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	15.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	15.100	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,775.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	32,500.000	L.F.
730-14.03	LOOP WIRE	65,000.000	L.F.
604-10.44	EXPANSION JOINT REPAIRS	273.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX074 - KNOX

Contract ID: CNX074

Letting Date: May 12, 2023 10:00 AM

Projects: 47026-3280-14

R-STP/NH-115(29)

Counties: KNOX

District:

DBE Goal Percent: 10.00

Description: The grading, drainage, construction of bridges and retaining walls, ITS, signals and paving on U.S. 129 (S.R. 115, Alcoa Highway) from Woodson Drive (L.M. 3.76) to Cherokee Trail interchange (L.M. 5.36).

Contract Time: DT - 9/30/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
108-03	CPM PROJECT SCHEDULE	(1)	LS
109-10.01	TRAINEE	7,180.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.56	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (DESCRIPTION)	(1)	LS
202-01.57	REMOVAL OF STRUCTURES & OBSTRUCTIONS (DESCRIPTION) (WIRE MESH)	(1)	LS
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT 8 RESIDENCE, STA. 139+00)	(1)	LS
202-08.28	REMOVAL OF MEDIAN BARRIER (DESCRIPTION) (DESCRIPTION)	4,530.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	971,161.000	C.Y.
203-01.11	PRESPLITTING OF ROCK EXCAVATION	15,472.000	S.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	13,580.000	TON
203-04	PLACING AND SPREADING TOPSOIL	22,972.000	C.Y.
203-05	UNDERCUTTING	125.000	C.Y.
203-06	WATER	2,805.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	2,300.000	C.Y.
203-40.19	TIE-BACK ANCHORS (7-STRAND UNCLASSIFIED)	720.000	L.F.
203-40.22	TIE-BACK ANCHORS (1-3/4" 150 KSI BAR)	42,068.000	L.F.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
204-01	CULVERT EXCAVATION (UNCLASSIFIED)	300.000	C.Y.
204-05.20	GROUT CASING INSTALLATION	2,200.000	L.F.
204-06.01	FLOWABLE FILL (GENERAL)	200.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	100.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	1,250.000	C.Y.
209-01.31	TEMPORARY MULCH FILTER BERM	9,000.000	C.Y.
209-02.07	18" TEMPORARY SLOPE DRAIN	14,000.000	L.F.
209-04	BRUSH BARRIERS	6,000.000	L.F.
209-05	SEDIMENT REMOVAL	5,000.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	14,000.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	80,000.000	L.F.
209-08.07	ROCK CHECK DAM	130.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	35.000	EACH
209-09.01	SANDBAGS	10,000.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-09.21	POLYACRYLAMIDE GEL LOGS	1,000.000	EACH
209-09.22	POLYACRYLAMIDE POWDER	10,000.000	LB.
209-09.23	POLYACRYLAMIDE LIQUID	1,000.000	GAL.
209-09.43	CURB INLET PROTECTION (TYPE 4)	140.000	EACH
209-10.20	TEMPORARY SEDIMENT TRAP	9,000.000	C.Y.
209-13.04	TURBIDITY CURTAIN(DESCRIPTION) (DESCRIPTION)	1,150.000	L.F.
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	1,000.000	S.Y.
209-40.30	CATCH BASIN PROTECTION (TYPE A)	8.000	EACH
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	125.000	EACH
209-40.43	CATCH BASIN FILTER ASSEMBLY(TYPE 3)	22.000	EACH
209-40.44	CATCH BASIN FILTER ASSEMBLY(TYPE 4)	1.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	200.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	199,614.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	2,500.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	5,598.000	TON

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	320.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	2,157.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	22,672.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	48,097.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	27,402.000	TON
313-03	TREATED PERMEABLE BASE	53,949.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	373.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	1,475.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	235.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	1,528.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	1,636.000	TON
411-01.11	ACS MIX(PG64-22) GRADING E RDWY	345.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	10,792.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	6.000	L.M.
415-01.03	COLD PLANING BITUMINOUS PAVEMENT	775.000	C.Y.
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	49,044.000	S.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	510.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	103,203.000	LB.
604-01.20	BOX TUBE SAFETY RAIL	1,006.000	L.F.
604-03.07	CLASS A CONCRETE (DESCRIPTION) (RETAINING WALL 6)	1,384.000	C.Y.
604-03.08	CLASS A CONCRETE (DESCRIPTION) (RETAINING WALL 18, 21 and 22)	47.000	C.Y.
604-07.02	RETAINING WALL (DESCRIPTION) (RETAINING WALL 1)	10,293.000	S.F.
604-07.03	RETAINING WALL (DESCRIPTION) (RETAINING WALL 2)	1,281.000	S.F.
604-07.04	RETAINING WALL (DESCRIPTION) (RETAINING WALL 3A)	5,392.000	S.F.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
604-07.05	RETAINING WALL (DESCRIPTION) (RETAINING WALL 3B)	9,331.000	S.F.
604-07.06	RETAINING WALL (DESCRIPTION) (RETAINING WALL 3C)	22,187.000	S.F.
604-07.07	RETAINING WALL (DESCRIPTION) (RETAINING WALL 5)	2,470.000	S.F.
604-07.11	RETAINING WALL (DESCRIPTION) (RETAINING WALL 7)	5,887.000	S.F.
604-07.12	RETAINING WALL (DESCRIPTION) (RETAINING WALL 8)	15,880.000	S.F.
604-07.13	RETAINING WALL (DESCRIPTION) (RETAINING WALL 9A)	2,116.000	S.F.
604-07.14	RETAINING WALL (DESCRIPTION) (RETAINING WALL 9B)	891.000	S.F.
604-07.15	RETAINING WALL (DESCRIPTION) (RETAINING WALL 10)	2,334.000	S.F.
604-07.16	RETAINING WALL (DESCRIPTION) (RETAINING WALL 11)	520.000	S.F.
604-07.17	RETAINING WALL (DESCRIPTION) (RETAINING WALL 12)	742.000	S.F.
604-07.18	RETAINING WALL (DESCRIPTION) (RETAINING WALL 13)	2,060.000	S.F.
604-07.19	RETAINING WALL (DESCRIPTION) (RETAINING WALL 14)	1,477.000	S.F.
604-07.20	RETAINING WALL (DESCRIPTION) (RETAINING WALL 15)	1,366.000	S.F.
604-07.21	RETAINING WALL (DESCRIPTION) (RETAINING WALL 16)	684.000	S.F.
604-07.22	RETAINING WALL (DESCRIPTION) (RETAINING WALL 17)	3,151.000	S.F.
604-15.01	PORTLAND CEMENT GROUT	500.000	C.Y.
604-15.20	COMPACTION GROUT	13,500.000	C.F.
606-04.03	STEEL PILES (14 INCH)	1,450.000	L.F.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	12,945.000	L.F.
607-03.04	18" CONCRETE PIPE CULVERT (CLASS V)	69.000	L.F.
607-03.30	18" PIPE CULVERT	106.000	L.F.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	5,540.000	L.F.
607-05.30	24" PIPE CULVERT	316.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	1,173.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	817.000	L.F.
607-08.02	42" CONCRETE PIPE CULVERT (CLASS III)	483.000	L.F.
607-09.02	48" CONCRETE PIPE CULVERT (CLASS III)	521.000	L.F.
607-11.03	60" CONCRETE PIPE CULVERT (CLASS III)	35.000	L.F.
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	35.000	L.F.
607-45.02	18" SLOTTED DRAIN PIPE	32.000	L.F.
610-07.03	18" PIPE DRAIN (BRIDGE DRAIN)	240.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH
611-02.01	SPRING DRAIN BOX, TYPE 1	2.000	EACH
611-02.11	JUNCTION BOX, TYPE 2	7.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	49.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	1,417.000	LB.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	9.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	3.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	3.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
611-07.59	24IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-07.60	30IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.61	30IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
611-07.66	42IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	24.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	59.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	8.000	EACH
611-12.08	CATCH BASINS, TYPE 12, >(' - ' DEPTH) (28')	2.000	EACH
611-25.01	CATCH BASINS, TYPE 25, 0' - 4' DEPTH	1.000	EACH
611-25.02	CATCH BASINS, TYPE 25, > 4' - 8' DEPTH	2.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
611-41.01	CATCH BASINS, TYPE 41, 0' - 4' DEPTH	17.000	EACH
611-41.02	CATCH BASINS, TYPE 41, > 4' - 8' DEPTH	32.000	EACH
611-41.03	CATCH BASINS, TYPE 41, > 8' - 12' DEPTH	4.000	EACH
611-41.04	CATCH BASINS, TYPE 41, > 12' - 16' DEPTH	8.000	EACH
611-41.05	CATCH BASINS, TYPE 41, > 16' - 20' DEPTH	1.000	EACH
611-41.08	CATCH BASINS, TYPE 41, >(' - ' DEPTH) (28')	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	5.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	8.000	EACH
611-43.01	CATCH BASINS, TYPE 43, 0' - 4' DEPTH	1.000	EACH
611-43.02	CATCH BASINS, TYPE 43, > 4' - 8' DEPTH	3.000	EACH
611-51.02	CATCH BASINS, TYPE 51, > 4' - 8' DEPTH	4.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	170.000	L.F.
622-01.04	SHOTCRETE 4 IN THICKNESS	33,310.000	S.F.
622-01.05	SHOTCRETE 6 IN THICKNESS	115,928.000	S.F.
622-01.07	SHOTCRETE 8 IN THICKNESS	20,362.000	S.F.
622-01.20	SHOTCRETE ARCHITECTURAL FACING	36,288.000	S.F.
630-01.16	6" CONCRETE BOLLARD/GUARD POST	30.000	EACH
701-01.01	CONCRETE SIDEWALK (4 ")	35,400.000	S.F.
701-02	CONCRETE DRIVEWAY	7,125.000	S.F.
702-01	CONCRETE CURB	283.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	1,398.000	C.Y.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	274.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	5,394.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	6.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	9.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	3.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	18.000	EACH
705-08.51	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	36.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
705-20.20	LOW MAINT CRASH CUSHN NARROW (MASH TL-3)	2.000	EACH
705-20.25	TEMPORARY CRASH CUSHION (MASH TL-3)	36.000	EACH
706-01	GUARDRAIL REMOVED	10,550.000	L.F.
707-01.02	END & CORNER POST ASSEMBLY(CHAIN-LINK FENCE 4')	67.000	EACH
707-02.01	CHAIN-LINK FENCE (4') (VINYL COATED)	11,100.000	L.F.
707-02.43	ROCK ANCHOR, TYPE I	1,210.000	L.F.
707-03.01	STOCK FENCE	1,900.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY(STOCK FENCE)	13.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,000.000	L.F.
707-10.06	ROCKFALL DRAPE (TYPE II)	8,000.000	S.Y.
707-10.30	ROCKFALL FENCE (PORTABLE-TEMPORARY)	4,200.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	71.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	1,000.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	10,000.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	14,000.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	17,000.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	29,428.000	L.F.
710-05	LATERAL UNDERDRAIN	1,300.000	L.F.
710-06.11	LATERAL UNDERDRAIN ENDWALL (2:1)	13.000	EACH
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	13.000	EACH
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	13.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	52.000	EACH
711-05.70	32IN SINGLE SLOPE CONCRETE BARRIER WALL	196.000	L.F.
711-05.71	51IN SINGLE SLOPE CONCRETE BARRIER WALL	10,138.000	L.F.
711-05.72	SINGLE SLOPE HALF CONCRETE BARRIER WALL	522.000	L.F.
711-05.78	GRADE SEPARATED SINGE SLOPE MEDIAN WALL	1,333.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	20,460.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	500.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
712-05.01	WARNING LIGHTS (TYPE A)	134.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	140.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,318.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	670.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	8.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	1,300.000	DAY
712-09.01	REMOVABLE PAVEMENT MARKING LINE	10,000.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	10,000.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	100.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	10,000.000	L.F.
712-09.31	REMOVABLE BLACK-OUT TAPE (8IN)	10,000.000	L.F.
712-12.10	TEMPORARY CURB W/FLEXIBLE DELINEATOR	20,000.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	10.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	2,500.000	LB.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	225.000	EACH
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	450.000	EACH
713-05	STEEL HOLLOW SQUARE POST (BREAKAWAY) SIGN SUPPORTS	385.000	LB.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	7,000.000	LB.
713-09.01	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 70.69')	1.000	EACH
713-09.02	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 66.11')	1.000	EACH
713-09.03	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 81.25')	1.000	EACH
713-09.04	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 69.29')	1.000	EACH
713-09.05	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 72'-0")	1.000	EACH
713-09.06	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 60'-0")	1.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
713-09.07	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 80'-0")	1.000	EACH
713-09.08	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 78'-0")	1.000	EACH
713-09.09	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 114'-0")	1.000	EACH
713-09.10	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 95'-0")	1.000	EACH
713-09.11	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 57'-0")	1.000	EACH
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	4,200.000	LB.
713-11.21	P POST SLIP BASE	6.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	345.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	650.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	4,600.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	128.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	12.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	8.000	EACH
713-16.20	SIGNS (DESCRIPTION) (HANDICAP, R7-8)	1.000	EACH
713-16.41	RELOCATE SIGN	(1)	LS
713-17.02	INSTALL AUXILIARY SUPPORT FOR EXIT NUMBER PANEL	12.000	EACH
713-30.09	BARRIER MOUNTED SIGN SUPPORT (DESCRIPTION) (MOUNTED ON BARRIER WALL)	6.000	EACH
713-30.10	BARRIER MOUNTED SIGN SUPPORT (PERF/KNOCKOUT) (PERF/KNOCKOUT)	5.000	EACH
716-01.06	TEMPORARY RAISED PAVEMENT MARKER,WHITE	200.000	EACH
716-01.07	TEMPORARY RAISED PAVEMENT MARKER,YELLOW	1,006.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	100.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	600.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS	120.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
716-02.04	(BI-DIR)(2 COLOR) PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	100.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	400.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	81.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,200.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	70.000	L.F.
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	6.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	3.000	EACH
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	1.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	240.000	S.F.
716-04.24	PLASTIC PAVEMENT MARKING (FISH-HOOKS WITH 2 ARROWS)	10.000	EACH
716-04.25	PLASTIC PAVEMENT MARKING (FISH-HOOKS WITH 3 ARROWS)	5.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	44.000	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	400.000	L.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	70.000	EACH
716-05.09	PAINTED PAVEMENT MARKING(STRAIGHT-TURN ARROW)	10.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	8.000	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	20,000.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	13.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	2,000.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	2,000.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	900.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	2,640.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	1.000	L.M.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	6.000	L.M.
716-13.03	SPRAY THERMO PVMT MRKNG (60 mil) (8IN BARRIER LINE)	1,700.000	L.F.
717-01	MOBILIZATION	(1)	LS
722-01.02	FIELD OFFICE (TYPE 2)	(1)	LS
725-20.02	CCTV POLE & FOUNDATION (80FT POLE W/LWRNG DVICE)	3.000	EACH
725-20.05	CCTV POLE REMOVAL	2.000	EACH
725-20.09	MAINTENANCE WORK PAD (CONCRETE PAD)	1.000	EACH
725-20.10	MAINTENANCE WORK PAD (WOOD PLATFORM)	2.000	EACH
725-20.22	STEEL OVERHEAD SIGN STRUCTURE (SPANS 51FT TO 70FT) (SPANS 51 FT TO 70 FT)	1.000	EACH
725-20.23	STEEL OVERHEAD SIGN STRUCTURE (SPANS 71FT TO 90FT) (SPANS 71 FT TO 90 FT)	1.000	EACH
725-20.43	PULL BOX (TYPE C)	12.000	EACH
725-20.44	PULL BOX (TYPE D)	19.000	EACH
725-20.45	PULL BOX (TYPE E)	5.000	EACH
725-20.55	CABLE (1/C #6 AWG.)	2,325.000	L.F.
725-20.57	CABLE (1/C #2 AWG.)	1,380.000	L.F.
725-20.71	ELECTRICAL CONNECTION	(1)	LS
725-20.91	CCTV CAMERA SYSTEM (PAN TILT & ZOOM)	3.000	EACH
725-21.02	DYNAMIC MESSAGE SIGN (MULTI-COLOR) (MULTI-COLOR)	2.000	EACH
725-21.04	DYNAMIC MESSAGE SIGN REMOVAL	1.000	EACH
725-21.07	PORTABLE SMART WORK ZONE SYSTEM	1,095.000	DAY
725-21.11	NETWORK SWITCH (TYPE A)	5.000	EACH
725-21.48	DEMARICATION POINT RISER ASSEMBLY	5.000	EACH
725-21.73	TRANSFORMER (DESCRIPTION) (TYPE C)	4.000	EACH
725-21.85	UNINTERRUPTIBLE POWER SUPPLY	5.000	EACH
725-21.91	RADAR DETECTION SYSTEM	4.000	EACH
725-21.95	RADAR DETECTION SYSTEM REMOVAL	3.000	EACH
725-21.96	RDS COMM CABLE	250.000	L.F.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
725-22.22	CONDUIT BANK (TYPE 2)	175.000	L.F.
725-22.24	CONDUIT BANK (TYPE 4)	5,980.000	L.F.
725-22.32	CONDUIT BANK BORED (TYPE 2)	370.000	L.F.
725-22.34	CONDUIT BANK BORED (TYPE 4)	2,855.000	L.F.
725-22.50	DMS CONDUIT BANK	150.000	L.F.
725-22.71	2IN CONDUIT	140.000	L.F.
725-22.72	2IN CONDUIT BORED	255.000	L.F.
725-22.74	2IN CONDUIT W/BANK	175.000	L.F.
725-22.75	2IN CONDUIT BORED W/BANK	400.000	L.F.
725-23.01	ITS CABLE MARKER	29.000	EACH
725-23.16	FIBER OPTIC CABLE (144F)	10,785.000	L.F.
725-23.21	FIBER OPTIC DROP CABLE (12 F)	1,240.000	L.F.
725-23.26	FIBER OPTIC CLOSURE (12 F)	4.000	EACH
725-23.27	FIBER OPTIC CLOSURE (DESCRIPTION) (144 F)	2.000	EACH
725-23.28	FIBER OPTIC SPLICE FUSION	164.000	EACH
725-23.30	FIBER OPTIC TERMINATION CABINET (DESCRIPTION) (144 F)	24.000	EACH
725-23.31	FIBER OPTIC DROP PANEL (12 F)	29.000	EACH
725-24.02	CABINET (TYPE B)	3.000	EACH
725-24.03	CABINET (TYPE C)	2.000	EACH
725-24.21	PREVENTIVE MAINTENANCE FOR SYSTEM	(1)	LS
725-24.32	EQUIPMENT REPLACEMENT	25,000.000	DOLL
725-24.41	BURN-IN PERIOD	(1)	LS
725-24.51	SYSTEM INTEGRATION	(1)	LS
725-24.55	AS-BUILT PLANS	(1)	LS
725-24.61	TRAINING	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	5.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	18.000	EACH
730-02.11	SIGNAL HEAD ASSEMBLY (130 A2 WITH BACKPLATE)	7.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	2.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	13.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	4.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	1,058.000	L.F.
730-08.05	SIGNAL CABLE - 12 CONDUCTOR	1,493.000	L.F.
730-12.26	CONDUIT 2" DIAMETER (PVC SCHEDULE 80)	2,845.000	L.F.
730-13.07	VEHICLE DETECTOR (SIREN ACTIVATED PRIORITY CONTROL)	12.000	EACH
730-13.12	VEHICLE DETECTOR (DESCRIPTION) (RADAR - STOP LINE)	12.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	9.000	EACH
730-15.07	CABINET (DESCRIPTION) (BATTERY BACKUP)	4.000	EACH
730-15.08	CABINET (DESCRIPTION) (SIXTEEN PHASE BASE MOUNTED)	4.000	EACH
730-16.04	CONTROLLER (ATC)	4.000	EACH
730-23.80	CANTILEVER SIGNAL SUPPORT (1 ARM @ 40')	4.000	EACH
730-25.01	CANTILEVER SIGNAL SUPPORT (1 ARM @ 50')	1.000	EACH
730-25.09	CANTILEVER SIGNAL SUPPORT (2 @ 55' & 60')	1.000	EACH
730-25.11	CANTILEVER SIGNAL SUPPORT (1 ARM @ 60')	1.000	EACH
730-25.14	CANTILEVER SIGNAL SUPPORT (1 ARM @ 70')	2.000	EACH
730-25.15	CANTILEVER SIGNAL SUPPORT (1 ARM @ 75')	1.000	EACH
730-25.16	CANTILEVER SIGNAL SUPPORT (1 ARM @ 80')	1.000	EACH
730-35.01	RF DATA SYSTEM (DESCRIPTION) (SPREAD SPECTRUM RADIO)	4.000	EACH
730-35.05	DATA SYSTEM POWER SUPPLY	4.000	EACH
730-35.06	BATTERY BACK-UP AND POWER CONDITIONER	4.000	EACH
730-35.10	ANTENNA (OMNI)	2.000	EACH
730-35.11	ANTENNA (YAGI)	2.000	EACH
730-35.21	RF DATA SYSTEM CABLE(DESCRIPTION) (RGA COAXIAL)	202.000	L.F.
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	12,000.000	S.Y.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	6,760.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	47,000.000	L.F.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	50,000.000	L.F.
801-01	SEEDING (WITH MULCH)	325.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	325.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	1,329.000	UNIT
801-02.15	FERTILIZER	18.000	TON
801-03	WATER (SEEDING & SODDING)	155.000	M.G.
803-01	SODDING (NEW SOD)	31,330.000	S.Y.
805-05.05	SOIL NAIL (#6 THREADED BAR)	31,931.000	L.F.
805-05.06	SOIL NAIL (#8 THREADED BAR)	20,198.000	L.F.
805-05.07	SOIL NAIL (#10 THREADED BAR)	30,814.000	L.F.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	116,830.000	S.Y.
806-02.03	PROJECT MOWING	25.000	CYCL
940-01.01	LIGHTWEIGHT FILL (DESCRIPTION) (EPS 22 GEOFOAM VOLUME)	8,850.000	C.Y.
940-01.02	LIGHTWEIGHT FILL (DESCRIPTION) (EPS 29 GEOFOAM VOLUME)	1,800.000	C.Y.
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (Bridge No.47-A163-02.25)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	723.000	C.Y.
204-14	CORE DRILLING FOR PILES(ROCK)	145.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	362.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	94.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	395,209.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	721.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	107,643.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	1,011.000	S.Y.
604-03.32	CLASS DS CONCRETE	1,066.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	8,707.000	S.Y.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
604-04.41	THREE STAR STATE EMBLEM	6.000	EACH
606-02.03	STEEL PILES (10 INCH)	6,822.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	172.000	EACH
606-19.03	STEEL PIPE PILES (16-INCH)	687.000	L.F.
615-01.11	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-63)	772.000	L.F.
615-01.12	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-72)	2,946.000	L.F.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	4,991.000	L.F.
709-04	REINFORCED CONCRETE SLOPE PAVEMENT	153.000	C.Y.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	304.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	208.000	L.F.
714-01.01	STRUCTURAL LIGHTING (BRIDGE NO.) (Bridge No.1)	(1)	LS
714-01.02	STRUCTURAL LIGHTING (BRIDGE NO.) (Bridge No.2)	(1)	LS
204-06.01	FLOWABLE FILL (GENERAL)	50.000	C.Y.
707-01.50	CHAIN-LINK FENCE (___ FOOT) (8 FOOT)	80.000	L.F.
708-03.11	CONCRETE PAD	416.000	S.F.
790-01.04	POLE 30FT CLASS 5 WOOD	2.000	EACH
790-03.03	POLE 40FT CLASS 4 WOOD	2.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	1.000	EACH
790-04.06	POLE 45FT CLASS 1 METAL	1.000	EACH
790-05.01	POLE 50FT CLASS 1 WOOD	1.000	EACH
790-05.03	POLE 50FT CLASS 3 WOOD	1.000	EACH
790-05.05	POLE 50FT CLASS 1 METAL	2.000	EACH
790-06.01	POLE 55FT CLASS 1 WOOD	3.000	EACH
790-06.05	POLE 55 FT CLASS 1 METAL	2.000	EACH
790-06.07	POLE 55FT CLASS H1 METAL	5.000	EACH
790-06.08	POLE 55FT CLASS H2 METAL	1.000	EACH
790-06.09	POLE 55FT CLASS H3 METAL	2.000	EACH
790-07.01	POLE 60FT CLASS 1 WOOD	2.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
790-07.05	POLE 60FT CLASS 1 METAL	3.000	EACH
790-07.07	POLE 60FT CLASS H1 METAL	5.000	EACH
790-07.08	POLE 60FT CLASS H2 METAL	1.000	EACH
790-07.09	POLE 60FT CLASS H3 METAL	5.000	EACH
790-08.04	POLE 65FT CLASS H2 METAL	2.000	EACH
790-08.06	POLE 65FT CLASS H4 METAL	1.000	EACH
790-08.14	POLE 65FT CLASS H1 METAL	2.000	EACH
790-08.30	POLE 65FT CLASS 1 WOOD	1.000	EACH
790-08.32	POLE 65FT CLASS 1 METAL	13.000	EACH
790-09.01	POLE 70FT CLASS 1 WOOD	1.000	EACH
790-09.05	POLE 70FT CLASS H2 METAL	1.000	EACH
790-09.06	POLE 70FT CLASS H3 METAL	1.000	EACH
790-09.07	POLE 70FT CLASS H4 METAL	1.000	EACH
790-09.08	POLE 70FT CLASS H5 METAL	1.000	EACH
790-09.13	POLE 70FT CLASS 1 METAL	1.000	EACH
790-11.17	POLE 80FT CLASS H1 METAL	1.000	EACH
790-20.01	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (60FT CLASS H4 METAL)	3.000	EACH
790-21.06	1PH PRIMARY MED ANGLE 15KV	1.000	EACH
790-21.07	1PH PRIMARY LG ANGLE 15KV	2.000	EACH
790-21.08	1PH DEADEND 15KV	6.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	28.000	EACH
790-25.11	3PH CROSSARM DBL PRIM SUP LRG COND 15KV	30.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	17.000	EACH
790-25.24	3PH CROSSARM DDE LRG COND 15KV	18.000	EACH
790-25.27	3PH CROSSARM DDE 10FT ARMS LRG COND 15KV	19.000	EACH
790-26.10	3PH VERTICAL TANGENT 25KV	4.000	EACH
790-26.24	3PH VERTICAL DEAD END LRG COND 25KV	2.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	12.000	EACH
790-30.06	SECONDARY CONDUCTOR 6 AL DUPLEX	310.000	L.F.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
790-30.08	SECONDARY CONDUCTOR 2 AL DUPLEX	100.000	L.F.
790-30.42	SECONDARY CONDUCTOR___ SGL COND (#2ACSR)	224.000	L.F.
790-32.04	DOWN GUY - WRAP TYPE	23.000	EACH
790-32.09	OH GUY - WRAP TYPE	2.000	EACH
790-32.23	GUY GUARD	23.000	EACH
790-32.26	DOWN GUY LIGHT CONSTRUCTION - PREFORM	3.000	EACH
790-32.29	DOWN GUY HEAVY CONSTRUCTION - PREFORM	122.000	EACH
790-32.30	OVERHEAD GUY HEAVY CONSTRUCTION - PREFORM	10.000	EACH
790-33.03	SCREW TYPE ANCHOR 6,000LB-8,000LB	26.000	EACH
790-33.17	ROCK ANCHOR EXPANDING TYPE	2.000	EACH
790-33.27	SCREW TYPE ANCHOR 32,000LB	72.000	EACH
790-36.02	TRANSFER CAPACITOR BANK	1.000	EACH
790-36.03	TRANSFER PCR SWITCH	3.000	EACH
790-36.05	TRANSFER SECONDARY	3.000	EACH
790-36.08	TRANSFER SECONDARY/SERVICE ASSEMBLY	1.000	EACH
790-36.10	TRANSFER - LIGHT ASSEMBLY	1.000	EACH
790-36.12	TRANSFER EXISTING 3PH TRANSFORMER/RECLOSER	2.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	486.000	L.F.
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	2,726.000	L.F.
790-40.39	OH COND 4/0 7 AAC OXLIP	9,806.000	L.F.
790-40.49	OH COND 795 37 AAC ARBUTUS	38,562.000	L.F.
790-41.03	UG PRI COND 1/0 AL 15KV	3,120.000	L.F.
790-41.10	UG PRI COND 750MCM AL 15KV	507.000	L.F.
790-42.16	1 DUCT @ 36IN-48IN DEPTH	162.000	L.F.
790-42.17	2 DUCT BANK @ 36IN-48IN DEPTH	709.000	L.F.
790-42.19	4 DUCT BANK @ 36IN-48IN DEPTH	169.000	L.F.
790-42.20	6 DUCT BANK @ 36IN-48IN DEPTH	169.000	L.F.
790-43.01	LOADBREAK ELBOW 200A 15KV	6.000	EACH
790-43.15	DEADBREAK ELBOW 900A 15KV	3.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
790-43.16	SPLICE 900A 15KV	3.000	EACH
790-43.47	PRIMARY PULLBOX	1.000	EACH
790-43.51	SECONDARY RISER W/ 3IN CONDUIT	1.000	EACH
790-43.52	SECONDARY RISER W/ 4IN CONDUIT	1.000	EACH
790-43.58	3PH PRIMARY RISER W/ 6IN CONDUIT	1.000	EACH
790-43.59	SECONDARY RISER (DESCRIPTION) (1" CONDUIT TO FEED MARKER LT)	1.000	EACH
790-43.62	3PH PRIMARY RISER W/ 4IN CONDUIT	7.000	EACH
790-46.03	1PH TRANSFORMER CONV W/XARM MTD FUSE & LA	12.000	EACH
790-51.06	3PH TRANSFORMER PAD - CONCRETE	1.000	EACH
790-56.05	225KVA 3PH PAD MT XFMR 15KV 208/120	1.000	EACH
790-59.05	GOLB SWITCH 25KV	15.000	EACH
790-60.01	1PH FUSE CUTOFF XARM MOUNT 15KV	6.000	EACH
790-64.08	SEC MTG 3PH PADMOUNT TRANSFORMER	1.000	EACH
790-64.14	PRI MTG 3PH CLUSTER MOUNT	1.000	EACH
790-68.01	POLE GROUND ROD TYPE	51.000	EACH
790-68.02	POLE GROUND PLATE TYPE	8.000	EACH
790-68.08	POLE GROUND W/ PLTFM FOR AIR BREAK SWCH	14.000	EACH
790-69.08	GROUND-GROUND ROD	3.000	EACH
790-69.24	EPOXY DEAD END	6.000	EACH
790-69.31	STICK PIN	3.000	EACH
790-69.33	DEADEND ASSEMBLY	8.000	EACH
790-74.31	FIBER TANGENT ASSEMBLY	10.000	EACH
790-98.01	REMOVE WIRE	62,482.000	L.F.
790-98.02	REMOVE POLES	62.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	510.000	EACH
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
791-01.05	6IN STEEL GAS MAIN	65.000	L.F.
791-01.09	()IN STEEL GAS MAIN (16IN)	1,005.000	L.F.
791-02.02	2IN MDPE GAS MAIN	1,120.000	L.F.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
791-02.04	4IN MDPE GAS MAIN	45.000	L.F.
791-02.05	6IN MDPE GAS MAIN	644.000	L.F.
791-02.06	8IN MDPE GAS MAIN	11,300.000	L.F.
791-04.26	HDD 16IN STEEL PIPE - UNCONSOLIDATED	875.000	L.F.
791-05.04	BORE/JACK 12IN - STEEL CASING PIPE - UNCON.	475.000	L.F.
791-05.55	12IN STEEL CASING OPEN CUT	275.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	4.000	EACH
791-06.03	CONNECT TO 4IN EX. PE MAIN	2.000	EACH
791-06.04	CONNECT TO 6IN EX. PE MAIN	3.000	EACH
791-06.05	CONNECT TO 8IN EX. PE MAIN	2.000	EACH
791-06.15	CONNECT TO 16IN EX. STL MAIN	2.000	EACH
791-07.01	2IN PE GAS VALVE ASSEMBLY	3.000	EACH
791-07.02	4IN PE GAS VALVE ASSEMBLY	1.000	EACH
791-07.03	6IN PE GAS VALVE ASSEMBLY	1.000	EACH
791-07.04	8IN PE GAS VALVE ASSEMBLY	15.000	EACH
791-07.11	6IN STEEL GAS VALVE ASSEMBLY	3.000	EACH
791-07.14	16IN STEEL GAS VALVE ASSEMBLY	1.000	EACH
791-08.06	1/2IN PE SERVICE PIPE	300.000	L.F.
791-08.09	1-1/4IN PE SERVICE PIPE	10.000	L.F.
791-08.10	2IN PE SERVICE PIPE	47.000	L.F.
791-08.17	HDD 3/4IN PE SERVICE PIPE	500.000	L.F.
791-08.18	HDD 1IN PE SERVICE PIPE	500.000	L.F.
791-08.41	GAS MAIN REMOVAL	2,500.000	L.F.
791-09.02	3-WIRE CATHODIC PROTECTION STATION	10.000	EACH
791-10.04	RETIRE IN PLACE 2IN SERV CUT & PLUG	2.000	EACH
791-10.10	RETIRE GAS MAIN	(1)	LS
791-12.35	16IN ANSI 300 WELD-IN INSULATOR	2.000	EACH
793-01.12	POLE 40FT CLASS 4 WOOD	1.000	EACH
793-01.23	POLE 55FT CLASS 1 WOOD	4.000	EACH
793-01.27	POLE 60FT CLASS 1 WOOD	1.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
793-01.42	ANCHOR 1 1/4IN	44.000	EACH
793-03.03	10M STRAND	6,050.000	L.F.
793-11.17	COMPOSITE HANDHOLE 5FTX3FTX3FT	3.000	EACH
793-11.20	HANDHOLE 30INX48IN	2.000	EACH
793-11.25	CONCRETE HANDHOLE 4FT X 4FT X 4FT	4.000	EACH
793-11.32	ENTER EXISTING HANDHOLE	1.000	EACH
793-12.01	DIG SPLICE PIT 80 C.F.	2.000	EACH
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	100.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	1,829.000	L.F.
793-13.22	3 DUCT FORMATION @ 36IN DEPTH	400.000	L.F.
793-14.02	CONCRETE ENCASEMENT PER DUCT	3,000.000	L.F.
793-14.14	MULTI DUCT	1,650.000	L.F.
793-14.20	PLACE MANHOLE OVER EXISTING CABLE	1.000	EACH
793-14.21	ROD DUCTS	315.000	L.F.
793-16.08	BORE/JACK 12IN CASING - UNCONSOLIDATED	230.000	L.F.
793-80.03	PLACE 4IN SPLIT DUCT AROUND CABLE/INNER DUCTS	315.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	25.000	EACH
795-01.01	4IN DIP RESTRAINED JOINT WATER LINE	585.000	L.F.
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	610.000	L.F.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	1,050.000	L.F.
795-01.07	10IN DIP RESTRAINED JOINT WATER LINE	450.000	L.F.
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	802.000	L.F.
795-01.13	16IN DIP RESTRAINED JOINT WATER LINE	9,500.000	L.F.
795-02.07	12IN HDPE WATER LINE	1,658.000	L.F.
795-05.68	BORE/JACK 24IN STEEL CASING PIPE-UNCON.	232.000	L.F.
795-05.69	BORE/JACK 30IN STEEL CASING PIPE-UNCON.	520.000	L.F.
795-06.03	CONNECT TO 4IN WATER LINE	1.000	EACH
795-06.04	CONNECT TO 6IN WATER LINE	6.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	8.000	EACH

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
795-06.06	CONNECT TO 10IN WATER LINE	2.000	EACH
795-06.07	CONNECT TO 12IN WATER LINE	7.000	EACH
795-06.09	CONNECT TO 16IN WATER LINE	5.000	EACH
795-06.32	CUT AND CAP 4IN WATER LINE	1.000	EACH
795-06.35	CUT AND CAP SERVICE LINE	3.000	EACH
795-08.03	4IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	4.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	6.000	EACH
795-08.06	10IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.09	12IN GATE VALVE ASSEMBLY	8.000	EACH
795-08.13	16IN BUTTERFLY VALVE ASSEMBLY	19.000	EACH
795-09.01	3/4IN WATER SERVICE METER ASSEMBLY	5.000	EACH
795-09.28	3/4IN COPPER SERVICE PIPE	150.000	L.F.
795-09.29	1IN COPPER SERVICE PIPE	150.000	L.F.
795-09.39	2N SERVICE PIPE	80.000	L.F.
795-10.03	1IN AUTO AIR RELEASE VALVE ASSEMBLY	1.000	EACH
795-10.05	2IN AUTO AIR RELEASE VALVE ASSEMBLY	12.000	EACH
795-11.01	BLOW-OFF ASSEMBLY	2.000	EACH
795-11.02	FIRE HYDRANT ASSEMBLY	4.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	10,000.000	L.F.
795-12.01	REMOVE FIRE HYDRANT	7.000	EACH
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-13.01	DI FITTINGS	15,000.000	LB.
795-14.07	CONCRETE VAULT	2.000	EACH
795-15.10	30IN STEEL CASING PIPE OPEN CUT METHOD	650.000	L.F.
798-05.29	COMMUNICATION ASSEMBLY (CSC)	4.000	EACH
798-05.32	COMMUNICATION ASSEMBLY (DDE)	22.000	EACH
798-05.33	COMMUNICATION ASSEMBLY (DE)	7.000	EACH
798-06.32	12-96 FIBER OPTIC CABLE (INSTALL ONLY)	11,000.000	L.F.
798-06.35	288-432 FIBER OPTIC CABLE (INSTALL ONLY)	3,000.000	L.F.

Contract ID CNX074 - KNOX

Item No.	Description	Quantity	Units
798-08.01	RISER	3.000	EACH

() Item will be bid as lump sum.

Contract ID CNX158 - KNOX

Contract ID: CNX158

Letting Date: May 12, 2023 10:00 AM

Projects: 47S001-M3-004

NA

Counties: KNOX

District:

DBE Goal Percent:

Description: The tunnel cleaning on the Henley Street Connector Tunnel on S.R. 1 and the SMARTFIX tunnel on S.R. 158 (James White Parkway).

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
712-01.56	MAINTENANCE OF TRAFFIC () (SMARTFIX I-40 RAMP)	12.000	EACH
712-01.60	MAINTENANCE OF TRAFFIC (HENLEY STREET TUNNELS)	12.000	EACH
713-20.40	GRAFFITI REMOVAL	250.000	S.F.
717-01	MOBILIZATION	(1)	LS
760-01.04	TUNNEL CLEANING (HENLEY STREET TUNNELS)	12.000	EACH
760-01.07	TUNNEL CLEANING (SMARTFIX I-40 RAMP)	12.000	EACH

() Item will be bid as lump sum.

Contract ID CNX213 - LAUDERDALE

Contract ID: CNX213

Letting Date: May 12, 2023 10:00 AM

Projects: 49S003-F3-003
49S003-F3-004
49S003-F8-004

HSIP-3(163)
NH/HSIP-3(169)
NH/HSIP-3(169)

Counties: LAUDERDALE

District:

DBE Goal Percent: 7.00

Description: From Wilson Road to Near SR-88

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	17.840	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	250.000	TON
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	17.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	57,600.000	S.Y.
411-04	CRACK SEALANT	7,136.000	LB.
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	270.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	2,250.000	TON
414-04.03	ASPHALT EMULSION (SCRUB SEAL)	175.000	TON
414-04.04	MINERAL AGGREGATE (SCRUB SEAL)	1,450.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	315.000	TON
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	1,880.000	L.F.
705-80.01	LONGITUDINAL CABLE BARRIER	3,115.000	L.F.
705-80.03	LONGITUDINAL CABLE BARRIER (END TERMINAL) TL-3	12.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,048.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-02.04	DELINEATOR (MILE MARKER) & STEEL POST	4.000	EACH

Contract ID CNX213 - LAUDERDALE

Item No.	Description	Quantity	Units
713-02.21	SIGN POST DELINEATION ENHANCEMENT	318.000	L.F.
713-02.22	BARRIER WALL DELINEATION ENHANCEMENT	640.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	780.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	8,738.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	63.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	845.170	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	106.000	EACH
713-16.20	SIGNS (DESCRIPTION) (BIKE ROUTE (D11-1)	20.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	582.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	582.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	298.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	150.000	L.F.
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	4.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	22.150	L.M.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-08.10	REMOVAL OF PAVEMENT MARKING (TRANSVERSE SHOULDER)	150.000	L.F.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	22.150	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	25.980	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	5,135.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	2.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	20.000	L.F.
730-14.02	SAW SLOT	500.000	L.F.
730-14.03	LOOP WIRE	1,500.000	L.F.

Contract ID CNX213 - LAUDERDALE

() Item will be bid as lump sum.

Contract ID CNX204 - LEWIS

Contract ID: CNX204

Letting Date: May 12, 2023 10:00 AM

Projects: 51945-3453-94

HSIP-5100(34)

Counties: LEWIS

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	780.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	2,248.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	3,650.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	365.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	934.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	52.000	EACH
713-16.05	RAILROAD CROSS-BUCK SIGN & SUPPORT	4.000	EACH
713-16.09	RAILROAD ADVANCE WARNING SIGN AND SUPPORT	3.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,431.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	152.000	L.F.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	2.000	EACH
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	69.400	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	7,524.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX145 - LOUDON

Contract ID: CNX145

Letting Date: May 12, 2023 10:00 AM

Projects: 53945-3488-94

HSIP-5300(32)

Counties: LOUDON

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	10.900	L.M.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	15.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	14.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	2,200.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	925.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	14.000	EACH
706-01	GUARDRAIL REMOVED	38.000	L.F.
706-10.26	ROUNDED END ELEMENT	5.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
713-02.20	ROADSIDE OBSTACLE DELINEATION	5.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	1,710.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	3,549.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	8,979.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	1,404.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	1,439.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	92.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	440.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	33.000	S.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	80.000	L.F.

Contract ID CNX145 - LOUDON

Item No.	Description	Quantity	Units
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	15.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	111.800	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	3,125.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX149 - MACON

Contract ID: CNX149

Letting Date: May 12, 2023 10:00 AM

Projects: 56946-3432-94

BRZE-5600(39)

Counties: MACON

District:

DBE Goal Percent: 9.00

Description: The construction of a concrete box bridge on Purtle Road over Puncheon Creek (L.M. 0.10), including grading, drainage and paving.

Contract Time: DT - 5/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	127.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	4,590.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	44.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	16.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	39.000	C.Y.
209-05	SEDIMENT REMOVAL	11.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	720.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	5.000	EACH
209-08.09	FILTER SOCK CHECK DAM	3.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	3.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	176.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	246.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	579.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,204.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	53.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	1.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	3.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.200	TON

Contract ID CNX149 - MACON

Item No.	Description	Quantity	Units
411-01.10	ACS MIX(PG64-22) GRADING D	36.000	TON
705-01.04	METAL BEAM GUARD FENCE	50.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	250.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	3.000	EACH
706-06.03	RADIUS RAIL	7.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	640.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	232.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	25.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	216.500	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	44.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.200	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	587.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	2,749.000	S.Y.
801-01	SEEDING (WITH MULCH)	18.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	44.000	UNIT
801-03	WATER (SEEDING & SODDING)	4.300	M.G.
202-04.50	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (PURTLE ROAD, STA. 25+98.00)	(1)	LS
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	113.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	21,828.000	LB.

() Item will be bid as lump sum.

Contract ID CNX212 - MARION

Contract ID: CNX212

Letting Date: May 12, 2023 10:00 AM

Projects: 58999-3606-04

NA

Counties: MARION

District:

DBE Goal Percent:

Description: The construction of a new 40' x 125' salt bin at 520 TVA Road in Jasper.

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
680-01.11	SALT BIN (DESCRIPTION) (SEE PLANS)	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX179 - MARION

Contract ID: CNX179

Letting Date: May 12, 2023 10:00 AM

Projects: 58S027-F3-004
58S027-M8-004
58S156-F8-004

HSIP-27(57)
N/A
STP-156(18)

Counties: MARION

District:

DBE Goal Percent: 6.00

Description: The resurfacing on U.S. 72 (S.R. 27) from near Lock and Dam Road (L.M. 6.42) to near Ketner Mill Lane (L.M. 12.47) and on S.R. 156 over the CSXT railroad crossing (L.M. 18.60 to L.M. 18.80).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	12.500	L.M.
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	500.000	TON
403-02.01	TRACKLESS TACK COAT	40.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	5,891.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	6.100	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	9.700	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	5,836.000	TON
705-04.22	GUARDRAIL DELINEATION ENHANCEMENT (BI-DIRECTIONAL)	4,787.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	10.000	EACH
712-06	SIGNS (CONSTRUCTION)	850.500	S.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.09	RAILROAD ADVANCE WARNING SIGN AND SUPPORT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	444.000	EACH

Contract ID CNX179 - MARION

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	14.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	213.000	L.F.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	37.500	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	25.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	475.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX168 - MAURY

Contract ID: CNX168

Letting Date: May 12, 2023 10:00 AM

Projects: 60003-3223-94
60003-4223-04

HSIP-7(46)
HSIP-7(46)

Counties: MAURY

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 7 from the Giles County line (L.M. 0.00) to near Rankin Drive (L.M. 11.11).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	22.300	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	5,881.000	TON
307-01.07	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M	500.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	407.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	83.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	8,103.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	15.500	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,407.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,510.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	733.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	375.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	103.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	40.400	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	40.400	L.M.

Contract ID CNX168 - MAURY

Item No.	Description	Quantity	Units
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX069 - MCMINN

Contract ID: CNX069

Letting Date: May 12, 2023 10:00 AM

Projects: 54010-3218-94

BR-STP-39(14)

Counties: MCMINN

District:

DBE Goal Percent: 10.00

Description: The construction of a concrete I-beam bridge on S.R. 39 over Middle Creek (L.M. 13.35), including grading, drainage, and paving.

Contract Time: DT - 10/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (15" RCP, COUNTY RD. 432 STA. 11+78.52)	93.000	L.F.
202-01.14	REMOVAL OF PIPE (SIZE, STA.) (18" CMP, COUNTY RD. 567 STA. 20+27.41)	35.000	L.F.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	570.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,491.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	4,485.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	2,602.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	248.000	C.Y.
203-06	WATER	10.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.600	L.M.
209-05	SEDIMENT REMOVAL	107.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	2,800.000	L.F.
209-08.07	ROCK CHECK DAM	12.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	10.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	250.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,289.000	TON

Contract ID CNX069 - MCMINN

Item No.	Description	Quantity	Units
303-01.01	GRANULAR BACKFILL (ROADWAY)	8.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,372.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	340.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	294.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	4.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	13.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.300	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	1,183.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	265.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	0.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	94.000	TON
604-01.01	CLASS A CONCRETE (ROADWAY)	19.000	C.Y.
604-36	SCARIFYING	325.000	S.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	141.000	L.F.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	3.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	257.000	L.F.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	2.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	30.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	506.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	441.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
705-08.51	PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	999.000	L.F.

Contract ID CNX069 - MCMINN

Item No.	Description	Quantity	Units
706-06.03	RADIUS RAIL	41.000	L.F.
706-06.05	RADIUS RAIL LONG POST (6-9 FT)	80.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	575.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	5.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	351.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	77.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	330.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	550.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	30.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	12.000	EACH
712-06	SIGNS (CONSTRUCTION)	565.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	36.000	L.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	7,350.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	60.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	485.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	43.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	39.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	12.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	35.000	L.F.
716-09.03	WET REFLECTIVE PAVEMENT MARKING(6" LINE)	0.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.550	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-06.01	GEOMEMBRANE	56.000	S.Y.
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,846.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	807.000	S.Y.

Contract ID CNX069 - MCMINN

Item No.	Description	Quantity	Units
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	625.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	400.000	L.F.
801-01.02	CROWN VETCH MIXTURE (WITH MULCH)	28.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	40.000	UNIT
801-03	WATER (SEEDING & SODDING)	23.000	M.G.
803-01	SODDING (NEW SOD)	1,935.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	266.000	S.Y.
805-01.03	TURF REINFORCEMENT MAT (CLASS III)	134.000	S.Y.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	3,900.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXISTING BR. NO. 54-SR039-13.35)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	64.000	C.Y.
204-05.01	CORE DRILLING AND SAMPLING	90.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	104.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	59,724.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	239.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	33,972.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	208.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	228.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	292.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,048.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	438.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	18.000	EACH
610-10.45	DECK DRAINS (DESCRIPTION) (TYPE I, GRATE DRAIN)	4.000	EACH
615-01.03	PRESTRESSED CONCRETE I-BEAM (TYPE III)	1,352.000	L.F.
617-02	BRIDGE DECK CRACK SEALING	200.000	L.F.
617-05	SEALANT (DESCRIPTION) (PHASE CONSTRUCTION JOINT)	1.000	GAL.
620-03.10	CONCRETE PARAPET (DESCRIPTION) (STD-1-1SS)	457.000	L.F.

Contract ID CNX069 - MCMINN

Item No.	Description	Quantity	Units
625-01.11	CAMERA INSPECTION - DRILLED SHAFT (UNDERWATER)	6.000	EACH
625-02.01	DRILLED SHAFT-SOIL (DIA.) (5'-6" DIAMETER)	137.000	V.F.
625-02.13	DRILLED SHAFT-ROCK (DIA.) (5'-0" DIAMETER)	60.000	V.F.
625-02.25	DRILLED SHAFT CASING-PERMANENT (DIA.) (5'-6" INSIDE DIAMETER)	138.000	V.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	166.000	C.Y.
625-02.44	DRILLED SHAFT REINFORCING STEEL	36,974.000	LB.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	126.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	33.000	L.F.
790-04.03	POLE 45FT CLASS 3 WOOD	2.000	EACH
790-05.03	POLE 50FT CLASS 3 WOOD	2.000	EACH
790-21.07	1PH PRIMARY LG ANGLE 15KV	1.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	1.000	EACH
790-25.07	3PH CROSSARM DBL LRG COND 15KV	1.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	1.000	EACH
790-25.24	3PH CROSSARM DDE LRG COND 15KV	2.000	EACH
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	7.000	EACH
790-32.23	GUY GUARD	7.000	EACH
790-33.02	EXPANDING TYPE ANCHOR 10,000LB-12,000LB	7.000	EACH
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	500.000	L.F.
790-40.09	OH COND 336.4 18/1 ACSR MERLIN	900.000	L.F.
790-40.46	OH COND 556.5 19 AAC DAHLIA	2,700.000	L.F.
790-60.02	1PH FUSE CUTOFF BRKT MOUNT 15KV	1.000	EACH
790-60.03	1PH SECTIONALIZER OR RECLOSER 15KV	1.000	EACH
790-65.03	LIGHTNING ARRESTER ARM MTD 9 KV	1.000	EACH
790-68.01	POLE GROUND ROD TYPE	1.000	EACH
790-68.13	SGL PHASE MOUNTING BRACKET - FIBERGLASS	1.000	EACH
793-04.08	TRANSFER AERIAL CABLE	5.000	EACH
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	250.000	L.F.

Contract ID CNX069 - MCMINN

Item No.	Description	Quantity	Units
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	85.000	L.F.
795-06.03	CONNECT TO 4IN WATER LINE	1.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	2.000	EACH
795-06.32	CUT AND CAP 4IN WATER LINE	1.000	EACH
795-06.34	CUT AND CAP 8IN WATER LINE	2.000	EACH
795-07.06	8IN X 8IN TAPPING SLEEVE AND VALVE	2.000	EACH
795-07.32	INSERTION VALVE (8IN)	2.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	3.000	EACH
795-10.01	3/4IN AUTO AIR RELEASE VALVE ASSEMBLY	1.000	EACH
795-11.01	BLOW-OFF ASSEMBLY	3.000	EACH
795-11.02	FIRE HYDRANT ASSEMBLY	1.000	EACH
795-13.01	DI FITTINGS	1,250.000	LB.
795-13.04	BRIDGE HANGER SYSTEM	(1)	LS
795-20.01	RECONNECT SERVICE ASSEMBLY	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNX178 - MCNAIRY

Contract ID: CNX178

Letting Date: May 12, 2023 10:00 AM

Projects: 55008-3245-94
55008-8245-14

STP/HSIP-57(80)
STP/HSIP-57(80)

Counties: MCNAIRY

District:

DBE Goal Percent: 7.00

Description: The resurfacing on S.R. 57 from the Hardeman County line (L.M. 0.00) to west of Luther Ingle Road (L.M. 12.00).

Contract Time: DT - 11/15/2023

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	200.000	S.Y.
203-06	WATER	13.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	23.880	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (D)	1,723.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	92.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	19,340.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	132.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	8,048.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	19.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	18,018.000	TON
701-02.01	CONCRETE CURB RAMP (RETROFIT)	170.000	S.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	31.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	26.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	5.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	26.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	5.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS

Contract ID CNX178 - MCNAIRY

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	1,290.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	40.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	123.000	LB.
713-11.22	U POST SLIP BASE	6.000	EACH
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.09	RAILROAD ADVANCE WARNING SIGN AND SUPPORT	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (ADVANCED WARNING, W10-2L)	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (ADVANCED WARNING, W10-2R)	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (ADVANCED WARNING, W10-4R)	1.000	EACH
713-16.23	SIGNS (DESCRIPTION) (STOP, R1-1)	3.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	792.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	321.000	L.F.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	96.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	48.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX157 - MEIGS

Contract ID: CNX157

Letting Date: May 12, 2023 10:00 AM

Projects: 61S058-F3-003
61S058-F8-003

STP/HSIP-58(61)
STP/HSIP-58(61)

Counties: MEIGS

District:

DBE Goal Percent: 9.00

Description: The resurfacing on S.R. 58 from south of Polymer Drive (L.M. 15.34) to north of Z Street (L.M. 18.35).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	6.100	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	368.000	TON
403-02.01	TRACKLESS TACK COAT	26.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	3,999.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	3.900	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	4.500	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	3,938.000	TON
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	21.000	EACH
701-02.01	CONCRETE CURB RAMP (RETROFIT)	2,069.000	S.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	2.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	4.000	EACH
705-04.22	GUARDRAIL DELINEATION ENHANCEMENT (BI-DIRECTIONAL)	151.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	188.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	684.000	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	90.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH

Contract ID CNX157 - MEIGS

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	400.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	97.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	400.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	105.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	800.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	17.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	200.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	700.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.400	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	395.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	1.000	EACH
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	1.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	24.000	S.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	18.100	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	800.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	12.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	1,210.000	L.F.
730-14.03	LOOP WIRE	3,680.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX150 - MONROE

Contract ID: CNX150

Letting Date: May 12, 2023 10:00 AM

Projects: 62S033-F3-002
62S033-F8-002

STP/HSIP-33(152)
STP/HSIP-33(152)

Counties: MONROE

District:

DBE Goal Percent: 4.00

Description: The microsurfacing on U.S. 411 (S.R. 33) from the McMinn County line (L.M. 0.00) to near S.R. 68 (L.M. 5.60).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	18.200	L.M.
403-01.01	BITUMINOUS MATERIAL FOR TACK COAT (MICRO-SURFACING)	23.000	TON
414-03.01	EMULSIFIED ASPHALT FOR MICRO-SURFACING	233.000	TON
414-03.02	AGGREGATE FOR MICRO SURFACING	1,943.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	2.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	236.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	118.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,321.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	276.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	276.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	621.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE	1,173.000	EACH

Contract ID CNX150 - MONROE

Item No.	Description	Quantity	Units
716-02.04	MARKER PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	710.000	S.Y.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	45.000	EACH
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	600.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	320.000	S.F.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	26.800	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	600.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX202 - MONROE

Contract ID: CNX202

Letting Date: May 12, 2023 10:00 AM

Projects: 62999-3607-04

n/a

Counties: MONROE

District:

DBE Goal Percent:

Description: The construction of a new 40' X 120' salt bin located at 119 Unicoi Church Road in Tellico Plains.

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
680-01.11	SALT BIN (DESCRIPTION) (40 x 120)	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX154 - MONTGOMERY

Contract ID: CNX154

Letting Date: May 12, 2023 10:00 AM

Projects: 63S149-F3-004
63S149-F8-004

STP/HSIP-149(17)
STP/HSIP-149(17)

Counties: MONTGOMERY

District:

DBE Goal Percent: 5.00

Description: The resurfacing on S.R. 149 from the Stewart County line (L.M. 0.00) to east of Jarman Hollow Road (L.M. 7.33).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	14.700	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,118.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	250.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	250.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	81.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	12,248.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	14.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	12,133.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	96.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,491.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	469.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	240.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	25.800	L.M.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	25.800	L.M.
717-01	MOBILIZATION	(1)	LS

Contract ID CNX154 - MONTGOMERY

() Item will be bid as lump sum.

Contract ID CNX143 - MORGAN

Contract ID: CNX143

Letting Date: May 12, 2023 10:00 AM

Projects: 65006-3220-94
65006-3221-94

BR-STP/HIP-116(24)
BR-STP/HIP-116(25)

Counties: MORGAN

District:

DBE Goal Percent: 9.00

Description: The construction of concrete box bridges on S.R. 116 (Petros Highway) over Stockstill Creek (L.M. 2.26 and L.M. 2.60), including grading, drainage, and paving.

Contract Time: DT - 9/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (24" CMP, STA. 17+28.77)	82.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (36" CMP, STA. 16+03.00, 29.92'LT)	183.000	L.F.
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (6'X7' CATCH BASIN, STA. 17+01.21, 21.25' LT)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,495.000	C.Y.
203-01.07	RD & DRNG EXCV (ACID PRODUCING- OFF SITE DISPOSAL)	1,265.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	605.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	264.000	C.Y.
203-06	WATER	2.900	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	82.000	C.Y.
203-08	CHANNEL EXCAVATION (UNCLASSIFIED)	284.000	C.Y.
203-20.01	CHANNEL SUBSTRATE	176.000	C.Y.
204-01	CULVERT EXCAVATION (UNCLASSIFIED)	107.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	74.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.400	L.M.
209-02.06	15" TEMPORARY SLOPE DRAIN	21.000	L.F.

Contract ID CNX143 - MORGAN

Item No.	Description	Quantity	Units
209-05	SEDIMENT REMOVAL	44.000	C.Y.
209-06.02	12" DIA COIR LOG (DESCRIPTION) (LOW FLOW CHANNEL)	98.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,302.000	L.F.
209-08.07	ROCK CHECK DAM	4.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	7.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	6.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	138.000	S.Y.
209-40.30	CATCH BASIN PROTECTION (TYPE A)	1.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	294.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,735.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	729.000	TON
303-01.03	GRANULAR BACKFILL (RETAINING WALLS)	275.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	72.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	228.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	150.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	4.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	3.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	227.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	0.300	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	0.100	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	220.000	TON
607-10.02	54" CONCRETE PIPE CULVERT (CLASS III)	264.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	45.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	15.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	210.000	LB.
611-39.02	CATCH BASINS, TYPE 39, > 4' - 8' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	16.000	L.F.

Contract ID CNX143 - MORGAN

Item No.	Description	Quantity	Units
705-01.04	METAL BEAM GUARD FENCE	143.000	L.F.
705-04.50	PORTABLE BARRIER RAIL DELINEATOR	34.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	384.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	435.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	6.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	5.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
706-01	GUARDRAIL REMOVED	248.000	L.F.
706-10.26	ROUNDED END ELEMENT	5.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	150.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	336.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	217.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,390.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	72.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	37.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,056.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	58.000	L.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	4,243.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	66.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.20	SIGNS (DESCRIPTION) (R1-1, STOP SIGN, 36"X36")	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) TN-18, DRIVEWAY CONNECTIONS BY PERMIT ONLY	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	15.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	15.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	11.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.

Contract ID CNX143 - MORGAN

Item No.	Description	Quantity	Units
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	0.800	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,034.000	S.Y.
801-01	SEEDING (WITH MULCH)	1.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	10.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	20.000	UNIT
801-03	WATER (SEEDING & SODDING)	3.100	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	610.000	S.Y.
805-12.03	EROSION CONTROL BLANKET (TYPE III)	1,564.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (27' SINGLE-SPAN CONCRETE SLAB BRIDGE, STA. 14+30)	(1)	LS
202-04.03	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (29' SINGLE SPAN SLAB BRIDGE, STA. 103+65.66)	(1)	LS
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	376.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	75,566.000	LB.
795-01.04	6IN DIP SLIP JOINT WATER LINE	105.000	L.F.
795-06.03	CONNECT TO 4IN WATER LINE	1.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	4.000	EACH
795-06.32	CUT AND CAP 4IN WATER LINE	2.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	1.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	4.000	EACH
795-09.28	3/4IN COPPER SERVICE PIPE	60.000	L.F.
795-10.31	2IN BLOW-OFF ASSEMBLY	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNX146 - MORGAN

Contract ID: CNX146

Letting Date: May 12, 2023 10:00 AM

Projects: 65945-3467-94

HSIP-6500(42)

Counties: MORGAN

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on various local roads.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	8.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	4,163.000	L.F.
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	16.000	S.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,300.000	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	8.000	EACH
706-10.26	ROUNDED END ELEMENT	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
713-02.14	FLEXIBLE DELINEATOR (WHITE)	42.000	EACH
713-02.20	ROADSIDE OBSTACLE DELINEATION	15.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	2,268.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	1,528.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	11,287.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	1,983.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	1,139.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	64.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	190.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	165.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	64.700	L.M.
716-13.04	SPRAY THERMO PVMT MRKNG (60 mil) (4IN DOTTED LINE)	660.000	L.F.

Contract ID CNX146 - MORGAN

Item No.	Description	Quantity	Units
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX147 - MORGAN

Contract ID: CNX147

Letting Date: May 12, 2023 10:00 AM

Projects: 65005-3239-94
65008-3267-94

PHSIP-62(56)
PHSIP-62(57)

Counties: MORGAN

District:

DBE Goal Percent:

Description: The miscellaneous safety improvements on S.R. 62 from near Chestnut Ridge Community Chapel Missionary Baptist Church (L.M. 5.10) to near Bart Woolum Road (L.M. 11.10).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
713-02.21	SIGN POST DELINEATION ENHANCEMENT	1,602.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	520.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	7,210.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	1,391.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	576.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	135.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	27.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	30.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	245.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-13.07	SPRAY THERMO PVMT MRKNG (40 mil) (6IN LINE)	44.000	L.M.
716-13.10	SPRAY THERMO PVMT MRKNG (40 mil) (6IN DOTTED LINE)	470.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX180 - OVERTON

Contract ID: CNX180

Letting Date: May 12, 2023 10:00 AM

Projects: 67S052-F3-003 STP/HSIP-52(99)
 67S052-F8-003 STP/HSIP-52(99)
 67S111-M8-002 N/A
 67S294-F8-002 STP-294(7)

Counties: OVERTON

District: **DBE Goal Percent:** 6.00

Description: The resurfacing on S.R. 111 from S.R. 294 to south of Twin Oaks Road, on S.R. 52 from Roberts Street to east of S.R. 294 and on S.R. 294 from S.R. 52 to S.R. 111.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	8.200	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	23.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	294.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	23,789.000	S.Y.
403-02.01	TRACKLESS TACK COAT	50.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	7,310.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	4.500	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	3.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	7,370.000	TON
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	2.000	EACH
701-02.01	CONCRETE CURB RAMP (RETROFIT)	446.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	20.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,196.000	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	70.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH

Contract ID CNX180 - OVERTON

Item No.	Description	Quantity	Units
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	342.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	92.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	319.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	169.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	436.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	13.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	54.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.200	L.M.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	17.500	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	436.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	15.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	898.000	L.F.
730-14.03	LOOP WIRE	2,512.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX199 - ROANE

Contract ID: CNX199

Letting Date: May 12, 2023 10:00 AM

Projects: 73S061-F3-002
73S061-F8-002

STP/HSIP-61(50)
STP/HSIP-61(50)

Counties: ROANE

District:

DBE Goal Percent: 7.00

Description: The resurfacing on U.S. 27 (S.R. 61) from near U.S. 70 (S.R. 1) (L.M. 0.00) to near I-40 (L.M. 5.29).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	10.600	L.M.
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	1,860.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	149.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	8.500	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	1,010.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	314.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	157.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,481.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	659.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	698.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,357.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	65.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	300.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	26.000	EACH

Contract ID CNX199 - ROANE

Item No.	Description	Quantity	Units
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	300.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	10.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	25.000	L.M.
717-01	MOBILIZATION	(1)	LS
411-03.08	ACS MIX(PG70-22) THIN LIFT ASPHALT	9,323.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	9,323.000	TON

() Item will be bid as lump sum.

Contract ID CNX161 - ROBERTSON

Contract ID: CNX161

Letting Date: May 12, 2023 10:00 AM

Projects: 74S257-F8-002

STP-257(12)

Counties: ROBERTSON

District:

DBE Goal Percent: 6.00

Description: The resurfacing on S.R. 257 from S.R. 49 (L.M. 0.00) to New Cut Road (L.M. 5.80).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	11.000	L.M.
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	250.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	250.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	41.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	4,023.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	8.800	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	4,273.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	2.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,276.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	365.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	365.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	24.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	302.000	L.F.
716-03.03	PLASTIC WORD PAVEMENT MARKING (STOP AHEAD)	1.000	EACH
716-04.17	PLASTIC PAVEMENT MARKING (YIELD SYMBOL)	5.000	EACH

Contract ID CNX161 - ROBERTSON

Item No.	Description	Quantity	Units
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	20.400	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	20.400	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	100.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	802.000	L.F.
730-14.03	LOOP WIRE	1,804.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX156 - SEQUATCHIE

Contract ID: CNX156

Letting Date: May 12, 2023 10:00 AM

Projects: 77S008-F8-003

STP-8(66)

Counties: SEQUATCHIE

District:

DBE Goal Percent: 4.50

Description: The resurfacing on S.R. 8 from near S.R. 111 (L.M. 30.11) to the Van Buren County line (L.M. 33.45).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	6.700	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	449.000	TON
308-01.10	COLD IN PLACE RECYCLED BITUMINOUS PAVEMENT	86,217.000	S.Y.
308-01.15	ENGINEERED ASPHALT EMULSION	449.000	TON
309-10.01	PORTLAND CEMENT	150.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	40.000	TON
403-05	BITUMINOUS MATERIAL(TC/FOG SEAL)(UNDILUTED)	24.000	TON
403-05.05	MINERAL AGGREGATE (SAND FOR FOG SEAL)	87.000	TON
411-03.12	ACS MIX(PG64-22) THIN LIFT D ASPHALT	6,161.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	5.300	L.M.
705-04.22	GUARDRAIL DELINEATION ENHANCEMENT (BI-DIRECTIONAL)	307.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	25.000	EACH
712-06	SIGNS (CONSTRUCTION)	594.000	S.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	225.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	25.000	EACH

Contract ID CNX156 - SEQUATCHIE

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	250.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	270.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	80.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	210.000	L.F.
716-04.16	PLASTIC PAVEMENT MARKING (NOISE STRIP)	216.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	8.800	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	80.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	8.800	L.M.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	695.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX206 - SEVIER

Contract ID: CNX206

Letting Date: May 12, 2023 10:00 AM

Projects: 78946-3418-94

BRZ-7800(64)

Counties: SEVIER

District:

DBE Goal Percent: 10.00

Description: The construction of a concrete box beam bridge on Grassy Branch Road over the Middle Prong of Little Pigeon River (L.M. .020), including grading, drainage, and paving.

Contract Time: DT - 7/31/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	396.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	103.000	C.Y.
203-06	WATER	2.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
209-02.05	12" TEMPORARY SLOPE DRAIN	205.000	L.F.
209-05	SEDIMENT REMOVAL	34.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	722.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	1.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	1.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	270.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	49.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	78.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	3.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	80.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	80.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	32.000	L.F.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH

Contract ID CNX206 - SEVIER

Item No.	Description	Quantity	Units
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	2.000	EACH
705-11.22	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST) (POWDER COATED)	372.000	L.F.
705-11.42	GR TERMINAL (ENERGY ABSORBING) MASH TL-2 (POWDER COATED)	2.000	EACH
705-11.46	THRIE BEAM BRIDGE TRANSITION MASH TL-2 (POWDER COATED)	4.000	EACH
706-10.26	ROUNDED END ELEMENT	2.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	59.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	55.000	TON
709-05.10	MACHINED RIP-RAP (DESCRIPTION) (GROUTED CLASS-C)	121.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	12.000	EACH
712-06	SIGNS (CONSTRUCTION)	908.688	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	52.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R1-1, STOP SIGN)	1.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	17.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	312.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	358.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	154.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	23.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	23.000	UNIT
801-03	WATER (SEEDING & SODDING)	6.000	M.G.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	657.000	S.Y.

Contract ID CNX206 - SEVIER

Item No.	Description	Quantity	Units
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BRIDGE NO. 78-0A359-00.01)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	122.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	44.000	C.Y.
204-04.01	ROCK EXCAVATION (BRIDGES)	43.000	C.Y.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO. 1, STA. 92+99.00)	(1)	LS
204-10.02	FOUNDATION PREPARATION(PR NO. ,STA) (PIER NO. 2, STA. 93+75.00)	(1)	LS
204-14	CORE DRILLING FOR PILES(ROCK)	174.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	180.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	18.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	36,494.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	133.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	29,734.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	111.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	695.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	377.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	386.000	L.F.
615-02.19	PRESTRESSED CONCRETE BOX BEAM (24" X 36")	584.000	L.F.
620-06	CONCRETE RAILING	357.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	84.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	21.000	L.F.
791-03.02	2IN HDPE GAS MAIN	248.000	L.F.
791-05.51	4IN STEEL CASING OPEN CUT	160.000	L.F.
791-09.01	BRIDGE HANGER SYSTEM AND PIPE	(1)	LS
791-09.05	RESTORE ASPHALT	15.000	S.Y.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	234.000	L.F.
795-06.34	CUT AND CAP 8IN WATER LINE	2.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	2.000	EACH

Contract ID CNX206 - SEVIER

Item No.	Description	Quantity	Units
795-13.04	BRIDGE HANGER SYSTEM	(1)	LS
795-13.22	BRIDGE HANGER SYSTEM SUPPORTS	(1)	LS
795-14.08	RESTORE ASPHALT	15.000	S.Y.
795-15.25	16IN STEEL CASING PIPE OPEN CUT METHOD	16.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX197 - SULLIVAN

Contract ID: CNX197

Letting Date: May 12, 2023 10:00 AM

Projects: 82085-3239-94
82085-4239-04

HSIP-126(23)
HSIP-126(23)

Counties: SULLIVAN

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 126 from near the Blountville By-pass (L.M. 16.48) to U.S. 11W (S.R. 1) (L.M. 23.36).

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	13.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	150.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	1,199.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	96.000	TON
411-12.05	SCORING FOR CENTERLINE RUMBLE (4IN WIDTH-24IN SPACING)	0.500	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	5,181.000	S.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	8.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	5.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	8.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	25.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,020.500	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (OM3-L)	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	454.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	48.000	EACH

Contract ID CNX197 - SULLIVAN

Item No.	Description	Quantity	Units
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	910.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	660.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	3.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	11.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	28.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	4,500.000	L.F.
730-14.03	LOOP WIRE	9,000.000	L.F.
411-03.08	ACS MIX(PG70-22) THIN LIFT ASPHALT	5,996.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	5,996.000	TON

() Item will be bid as lump sum.

Contract ID CNX200 - WASHINGTON

Contract ID: CNX200

Letting Date: May 12, 2023 10:00 AM

Projects: 90023-3225-94

BR-STP/HIP-353(12)

Counties: WASHINGTON

District:

DBE Goal Percent: 9.00

Description: The construction of a concrete box bridge on S.R. 353 (Old S.R. 34) over Little Limestone Creek (L.M. 11.72), including grading, drainage, and paving.

Contract Time: DT - 6/30/2024

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.21	REMOVAL OF PIPE (DESCRIPTION) (EXISTING SIDE DRAIN ON TRACT 4B)	25.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,104.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	246.000	C.Y.
203-06	WATER	10.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	224.000	C.Y.
203-20.01	CHANNEL SUBSTRATE	47.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.200	L.M.
209-05	SEDIMENT REMOVAL	47.000	C.Y.
209-06.02	12" DIA COIR LOG (DESCRIPTION) (DESCRIPTION)	100.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	87.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	1,160.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	3.000	EACH
209-09.04	SEDIMENT FILTER BAG(15' X 10')	2.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	2.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	322.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,642.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	15.000	TON

Contract ID CNX200 - WASHINGTON

Item No.	Description	Quantity	Units
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	310.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	503.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	3.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	76.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	319.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	275.000	S.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	140.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	35.000	L.F.
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	1.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	1.000	EACH
621-03.10	66" TEMPORARY DRAINAGE PIPE	90.000	L.F.
705-01.04	METAL BEAM GUARD FENCE	60.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	169.000	L.F.
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
705-20.25	TEMPORARY CRASH CUSHION (MASH TL-3)	4.000	EACH
706-01	GUARDRAIL REMOVED	236.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	290.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	12.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	315.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	169.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,050.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	53.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	25.000	EACH
712-06	SIGNS (CONSTRUCTION)	256.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	30.000	L.F.

Contract ID CNX200 - WASHINGTON

Item No.	Description	Quantity	Units
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	500.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	20.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	20.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	35.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.600	L.M.
717-01	MOBILIZATION	(1)	LS
740-06.01	GEOMEMBRANE	418.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,570.000	S.Y.
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	135.000	L.F.
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	10.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	41.000	UNIT
801-03	WATER (SEEDING & SODDING)	3.000	M.G.
802-11.01	ACER NEGUNDO (BOX ELDER 2-5FT CNTNR GRWN)	4.000	EACH
802-11.02	ACER RUBRUM (RED MAPLE 2-5FT CNTNR GRWN)	3.000	EACH
802-11.07	BETULA NIGRA (RIVER BIRCH 2-5FT CNTNR GRWN)	3.000	EACH
802-11.12	CORNUS FLORIDA (FLOWERING DOGWOOD 2-5FT CNTNR GRWN)	3.000	EACH
802-11.18	LIQUIDAMBER STYRACIFLUA (SWEETGUM 2-5FT CNTNR GRWN)	3.000	EACH
802-11.26	PLATANUS OCCIDENTALIS (SYCAMORE 2-5FT CNTNR GRWN)	3.000	EACH
802-11.40	SALIX NIGRA (BLACK WILLOW 2-5FT CNTNR GRWN)	3.000	EACH
802-11.44	ULMUS AMERICANA (AMERICAN ELM 2-5FT CNTNR GRWN)	3.000	EACH
802-11.62	CORNUS ALTERNIFOLIA (ALTERNATE LEAF DGWOOD 2-5FT CNTNR GRWN)	3.000	EACH
803-01	SODDING (NEW SOD)	70.000	S.Y.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	3,759.000	S.Y.

Contract ID CNX200 - WASHINGTON

Item No.	Description	Quantity	Units
805-12.03	EROSION CONTROL BLANKET (TYPE III)	95.000	S.Y.
202-04.50	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE, STA. 106+45)	(1)	LS
204-08	FOUNDATION FILL MATERIAL	35.000	C.Y.
303-01.01	GRANULAR BACKFILL (ROADWAY)	216.000	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	171.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	41,117.000	LB.
790-03.03	POLE 40FT CLASS 4 WOOD	2.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	3.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	2.000	EACH
790-25.01	3PH CROSSARM SGL 15KV	2.000	EACH
790-25.10	3PH CROSSARM DBL PRIM SUPPORT 15KV	2.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	1.000	EACH
790-25.23	3PH CROSSARM DDE 15KV	1.000	EACH
790-30.04	SECONDARY ASSEMBLIES MISC	2.000	EACH
790-30.13	SECONDARY CONDUCTOR 2 AL TRIPLEX	20.000	L.F.
790-32.01	DOWN GUY - THROUGH BOLT TYPE	10.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	3.000	EACH
790-33.11	SERVICE ANCHOR SCREW TYPE	5.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	956.000	L.F.
790-40.05	OH COND 3/0 6/1 ACSR PIGEON	559.000	L.F.
790-40.46	OH COND 556.5 19 AAC DAHLIA	1,677.000	L.F.
790-46.01	1PH TRANSFORMER	1.000	EACH
790-60.01	1PH FUSE CUTOFF XARM MOUNT 15KV	3.000	EACH
790-65.03	LIGHTNING ARRESTER ARM MTD 9 KV	3.000	EACH
790-98.01	REMOVE WIRE	3,211.000	L.F.
790-98.02	REMOVE POLES	4.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	1.000	EACH
791-03.04	4IN HDPE GAS MAIN	530.000	L.F.
791-04.13	HDD 4IN PE PIPE - ROCK	470.000	L.F.

Contract ID CNX200 - WASHINGTON

Item No.	Description	Quantity	Units
791-06.03	CONNECT TO 4IN EX. PE MAIN	2.000	EACH
791-08.41	GAS MAIN REMOVAL	25.000	L.F.
791-10.01	RETIRE IN PLACE 3/4IN SERV CUT & PLUG	1.000	EACH
791-10.05	RETIRE IN PLACE 4IN SERV CUT & PLUG	1.000	EACH
793-01.08	POLE 35FT CLASS 5 WOOD	4.000	EACH
793-01.12	POLE 40FT CLASS 4 WOOD	1.000	EACH
793-01.40	ANCHOR 3/4IN	11.000	EACH
793-02.07	GUY WIRE 6.6M OR 1/4IN	7.000	EACH
793-02.08	GUY WIRE 10M OR 3/8IN	7.000	EACH
793-03.01	25 PAIR GROUP AERIAL SPLICE	96.000	EACH
793-03.02	6M STRAND	2,870.000	L.F.
793-03.03	10M STRAND	1,435.000	L.F.
793-03.14	100 PAIR CABLE	1,370.000	L.F.
793-03.16	200 PAIRCABLE	220.000	L.F.
793-03.17	300 PAIR CABLE	1,515.000	L.F.
793-04.01	RELASH/DELASH CABLE	1,990.000	L.F.
793-04.07	AERIAL SPLICE CLOSURE	7.000	EACH
793-04.08	TRANSFER AERIAL CABLE	13.000	EACH
793-09.06	200 PAIR BURIED CABLE	70.000	L.F.
793-09.07	300 PAIR BURIED CABLE	120.000	L.F.
793-11.01	25 GROUP BURIED SPLICE	68.000	EACH
793-11.06	8IN PEDESTAL	1.000	EACH
793-11.10	12IN PEDESTAL	1.000	EACH
793-11.13	BURIED RISER GUARD	6.000	EACH
793-12.02	REARRANGEMENT EXISTING CABLE	2.000	EACH
793-12.05	200 PAIR UG CABLE	175.000	L.F.
793-12.06	300 PAIR UG CABLE	65.000	L.F.
793-12.08	600 PAIR UG CABLE	150.000	L.F.
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	330.000	L.F.
793-98.01	REMOVE AERIAL CABLE AND WIRE	2,090.000	L.F.

Contract ID CNX200 - WASHINGTON

Item No.	Description	Quantity	Units
793-98.04	REMOVE POLES ALL SIZES	7.000	EACH
793-98.05	RETIRE BURIED FACILITIES IN PLACE	815.000	L.F.
793-98.06	REMOVE PEDESTALS	1.000	EACH
793-98.07	REMOVE UNDERGROUND TO OVERHEAD RISER	1.000	EACH
793-98.08	REMOVE ANCHOR (ANY SIZE)	7.000	EACH
795-01.01	4IN DIP RESTRAINED JOINT WATER LINE	481.000	L.F.
795-01.04	6IN DIP SLIP JOINT WATER LINE	962.000	L.F.
795-05.14	HDD __IN HDPE CASING PIPE-UNCON (6 IN)	40.000	L.F.
795-05.63	BORE/JACK 12IN STEEL CASING PIPE-UNCON.	34.000	L.F.
795-05.90	HDD 6IN HDPE CARRIER PIPE-UNCON	200.000	L.F.
795-06.04	CONNECT TO 6IN WATER LINE	3.000	EACH
795-06.33	CUT AND CAP 6IN WATER LINE	3.000	EACH
795-07.03	6IN X 6IN TAPPING SLEEVE AND VALVE	2.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	1.000	EACH
795-09.14	3/4IN HDPE SERVICE PIPE	110.000	L.F.
795-11.02	FIRE HYDRANT ASSEMBLY	2.000	EACH
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-12.03	PIPE GROUTING	(1)	LS
795-13.01	DI FITTINGS	500.000	LB.
795-16.16	RELOCATE/RECONNECT 3/4IN WATER METER ASSEMBLY	1.000	EACH
797-06.02	HDD 4IN HDPE CARRIER PIPE-UNCON	200.000	L.F.
797-08.01	DI FITTINGS	500.000	LB.
797-09.06	4IN PLUG VALVE ASSEMBLY	2.000	EACH
797-09.43	CUT AND CAP 4IN FORCE MAIN	2.000	EACH
797-10.16	CONNECT TO 4IN FORCE MAIN	2.000	EACH
797-11.34	REMOVE EXISTING SEWER <8IN	81.000	L.F.
797-40.02	PIPE GROUTING	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX192 - WAYNE

Contract ID: CNX192

Letting Date: May 12, 2023 10:00 AM

Projects: 91NMSC-S3-002

NA

Counties: WAYNE

District:

DBE Goal Percent:

Description: The construction of a 40' by 60' brine shed at 855 Savannah Highway in Waynesboro.

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
607-65.20	SITE PREPARATION	1.000	EACH
680-02.01	BUILDING (DESCRIPTION) (FOUNDATION AND STRUCTURE)	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX182 - WHITE

Contract ID: CNX182

Letting Date: May 12, 2023 10:00 AM

Projects: 93S111-M3-002

N/A

Counties: WHITE

District:

DBE Goal Percent:

Description: The construction of a small drainage structure on S.R. 111 at L.M. 15.76.

Contract Time: DT - 9/30/2023

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	4,203.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	1,165.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	451.000	C.Y.
203-07	FURNISHING & SPREADING TOPSOIL	225.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	103.000	C.Y.
209-03.21	FILTER SOCK (12 INCH)	550.000	L.F.
209-05	SEDIMENT REMOVAL	14.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	230.000	L.F.
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	5.000	EACH
209-40.44	CATCH BASIN FILTER ASSEMBLY(TYPE 4)	2.000	EACH
209-40.45	CATCH BASIN FILTER ASSEMBLY(TYPE 5)	2.000	EACH
209-65.01	TEMPORARY STREAM DIVERSION (DESCRIPTION) (INSTREAM DIVERSION)	(1)	LS
303-10.01	MINERAL AGGREGATE (SIZE 57)	80.000	TON
606-24.13	TEMPORARY SHEET PILES	(1)	LS
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	20.000	L.F.
607-08.02	42" CONCRETE PIPE CULVERT (CLASS III)	72.000	L.F.

Contract ID CNX182 - WHITE

Item No.	Description	Quantity	Units
607-08.05	42" CONCRETE PIPE CULVERT(CLASS IV)JACKED-IN-PLACE	592.000	L.F.
611-01.04	MANHOLES, > 12' - 16' DEPTH	2.000	EACH
611-02.01	SPRING DRAIN BOX, TYPE 1	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	11.200	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	474.000	LB.
611-39.03	CATCH BASINS, TYPE 39, > 8' - 12' DEPTH	2.000	EACH
707-03.01	STOCK FENCE	342.000	L.F.
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (PAGE WIRE)	342.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,900.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	500.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,700.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	8.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	75.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	85.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	8.000	EACH
712-06	SIGNS (CONSTRUCTION)	432.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	4,190.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.500	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,150.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	1,080.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	80.000	UNIT
801-03	WATER (SEEDING & SODDING)	53.000	M.G.
803-01	SODDING (NEW SOD)	4,500.000	S.Y.
806-02.03	PROJECT MOWING	1.000	CYCL

Contract ID CNX182 - WHITE

() Item will be bid as lump sum.

Contract ID CNX201 - WILLIAMSON

Contract ID: CNX201

Letting Date: May 12, 2023 10:00 AM

Projects: 94S046-F3-002
94S046-M8-002

HSIP-46(42)
HSIP-46(42)

Counties: WILLIAMSON

District:

DBE Goal Percent:

Description: The resurfacing on S.R. 46 from the Natchez Trace Parkway (L.M. 12.00) to Green Chapel Road (L.M. 19.32).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	14.600	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,440.000	TON
307-01.10	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING C-W	500.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	48.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	7,224.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	1.200	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (4IN WIDTH)	9.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	7,156.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	4.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	2.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
706-01	GUARDRAIL REMOVED	150.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,190.000	S.F.

Contract ID CNX201 - WILLIAMSON

Item No.	Description	Quantity	Units
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	455.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	36.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	455.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	795.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	12.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	300.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	100.000	L.F.
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	84.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	30.400	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,830.000	L.F.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.300	L.M.
716-09.95	CONTRAST PAVEMENT SHADOW MARKING 8"	0.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	30.400	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,195.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNX167 - WILLIAMSON

Contract ID: CNX167

Letting Date: May 12, 2023 10:00 AM

Projects: 94028-3222-94
94028-8222-14

STP/HSIP-252(16)
STP/HSIP-252(16)

Counties: WILLIAMSON

District:

DBE Goal Percent: 9.00

Description: The resurfacing on S.R. 252 from north of Raintree Parkway (L.M. 7.77) to near U.S. 31 (S.R. 6, Franklin Road) (L.M. 13.33).

Contract Time: DT - 10/31/2023

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	10.500	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	687.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	500.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	57.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	8,656.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	7.700	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	8,575.000	TON
611-01.20	ADJUSTMENT OF EXISTING MANHOLE	17.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	5.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	5.000	EACH
706-01	GUARDRAIL REMOVED	125.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	88.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	20.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,447.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	367.000	EACH

Contract ID CNX167 - WILLIAMSON

Item No.	Description	Quantity	Units
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	123.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	425.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	410.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	208.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	540.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	46.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	1,624.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	243.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.670	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	3.000	EACH
716-04.02	PLASTIC PAVEMENT MARKING(DOUBLE TURNING ARROW)	4.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	9.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	29.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	29.200	L.M.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	7,819.000	L.F.
730-14.03	LOOP WIRE	17,938.000	L.F.

() Item will be bid as lump sum.

Contract ID CNX264 - BENTON , CARROLL, ETC.

Contract ID: CNX264

Letting Date: May 12, 2023 10:00 AM

Projects: R4BVAR-M3-039

N/A

Counties: BENTON, CARROLL, CHESTER, CROCKETT,
 DECATUR, DYER, FAYETTE, GIBSON,
 HARDEMAN, HARDIN, HAYWOOD,
 HENDERSON, HENRY, LAKE, LAUDERDALE,
 MADISON, MCNAIRY, OBION, SHELBY,
 TIPTON, WEAKLEY

District:

DBE Goal Percent:

Description: The on-call guardrail repair on various Interstate and State Routes.

Contract Time: DT - 6/30/2026

Item No.	Description	Quantity	Units
705-01.01	GUARDRAIL AT BRIDGE ENDS	750.000	L.F.
705-01.02	GUARDRAIL AT BRIDGE PIERS	60.000	L.F.
705-01.04	METAL BEAM GUARD FENCE	300.000	L.F.
705-02.01	SINGLE GUARDRAIL, WITH RUB-RAIL (TYPE 2)	175.000	L.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	750.000	EACH
705-02.20	SINGLE GUARDRAIL (TYPE 2) LONG POST (6 FT-9 FT)	750.000	L.F.
705-02.25	SINGLE GUARDRAIL (TYPE 2) LONG POST (9 FT-12 FT)	750.000	L.F.
705-02.31	SINGLE GUARDRAIL (TYPE 2) (YEAR 1)	6,000.000	L.F.
705-02.32	SINGLE GUARDRAIL (TYPE 2) (YEAR 2)	6,250.000	L.F.
705-02.33	SINGLE GUARDRAIL (TYPE 2) (YEAR 3)	6,500.000	L.F.
705-03.01	MEDIAN DIVIDER GUARDRAIL, WITH RUB-RAIL (TYPE 2)	60.000	L.F.
705-03.02	MEDIAN DIVIDER GUARDRAIL (TYPE 2)	450.000	L.F.
705-03.03	MEDIAN DIVIDER GUARDRAIL (TYPE 2) (27" MT HT)	75.000	L.F.
705-03.04	MEDIAN DIVIDER GUARDRAIL AT CONCRETE BARRIER	75.000	L.F.
705-04.02	GUARDRAIL TERMINAL (TYPE 12)	6.000	EACH

Contract ID CNX264 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
705-04.03	GUARDRAIL TERMINAL (TYPE 13)	9.000	EACH
705-04.05	GUARDRAIL TERMINAL (TYPE-IN-LINE)	6.000	EACH
705-04.11	STONE FOR GUARDRAIL END TERMINAL PAD	120.000	TON
705-04.24	GUARDRAIL END TERMINAL DELINEATION SHEETING	100.000	S.F.
705-04.29	C-A-T CRASH CUSHION ATTENUATING TERMINAL	4.000	EACH
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	100.000	L.F.
705-06.09	WEAK-POST GUARDRAIL ATTACHMENT TO CULVERT(MASH TL-3)(TYPE _) (MASH TL-3)	100.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	90.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	25.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	5.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	5.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	30.000	EACH
705-06.71	W BEAM GR (TYPE 2) MASH TL-3 (YEAR 1)	16,000.000	L.F.
705-06.72	W BEAM GR (TYPE 2) MASH TL-3 (YEAR 2)	16,250.000	L.F.
705-06.73	W BEAM GR (TYPE 2) MASH TL-3 (YEAR 3)	16,500.000	L.F.
705-06.81	TANGENT ENERGY ABSORBING TERM MASH TL-3 (YEAR 1)	300.000	EACH
705-06.82	TANGENT ENERGY ABSORBING TERM MASH TL-3 (YEAR 2)	325.000	EACH
705-06.83	TANGENT ENERGY ABSORBING TERM MASH TL-3 (YEAR 3)	350.000	EACH
705-10.30	GUARDRAIL ATTACHMENT TO SLOPE FACE ENDPOST	110.000	L.F.
705-10.31	GUARDRAIL ATTACHMENT TO VERTICAL FACE ENDPOST	30.000	L.F.
705-10.32	GUARDRAIL ATTACHMENT TO EXISTING BRIDGE PIER PROTECTION	4.000	EACH
705-10.99	GUARDRAIL END TERMINAL ANCHOR CABLE ASSEMBLY	15.000	EACH
705-16.01	MEDIAN ATTENUATING TREND TERMINAL (MATT)	3.000	EACH
706-01	GUARDRAIL REMOVED	100.000	L.F.
706-02.21	RESET SINGLE GUARDRAIL (TYPE 2)	450.000	L.F.

Contract ID CNX264 - BENTON , CARROLL, ETC.

Item No.	Description	Quantity	Units
706-03.01	POSTS FURNISHED	60.000	EACH
706-06.01	SINGLE THRIE RAIL (TYPE 2)	50.000	L.F.
706-06.02	MEDIAN DIVIDER THRIE RAIL (TYPE 2)	50.000	L.F.
706-06.03	RADIUS RAIL	2,400.000	L.F.
706-06.05	RADIUS RAIL LONG POST (6-9 FT)	30.000	L.F.
706-06.06	RADIUS RAIL LONG POST (9-12 FT)	30.000	L.F.
706-10.26	ROUNDED END ELEMENT	36.000	EACH
706-10.54	RE-ALIGN GUARDRAIL	1,200.000	L.F.
706-10.71	HAZARD MARKERS	20.000	EACH
706-10.72	PULL AND REINSTALL GUARDARAIL POST FOR VERIFICATION	15.000	EACH
706-10.74	CONCRETE BARRIER WALL REPAIR	40.000	C.Y.
706-10.80	MICHIGAN AND MODIFIED MICHIGAN END SHOE	12.000	EACH
706-10.81	GUARDRAIL REFLECTORS	50.000	EACH
706-10.82	CONCRETE BRIDGE END OR PIER PROTECTION REPAIR	12.000	C.Y.
706-10.83	DRILL BR. PAR. WALL FOR MICHIGAN END SHOE	5.000	EACH
712-01.02	LANE CLOSURE	1,500.000	EACH
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	450.000	DAY
717-01	MOBILIZATION	(1)	LS
717-01.04	MOBILIZATION (DESCRIPTION) (EMERGENCY CALL- OUT)	240.000	EACH

() Item will be bid as lump sum.