

Estimated Quantities -- Letting October 04, 2024

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNY256 - BEDFORD , GILES, ETC.

Contract ID: CNY256

Letting Date: October 04, 2024 10:00 AM

Projects: R3SVAR-F3-065

HSIP-REG3(232)

Counties: BEDFORD, GILES, LAWRENCE, LEWIS,
LINCOLN, MARSHALL, PERRY,
RUTHERFORD, WAYNE

District:

DBE Goal Percent: 8.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
202-01.03	REMOVAL OF TRASH AND DEBRIS	(1)	LS
701-02.01	CONCRETE CURB RAMP (RETROFIT)	9,743.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	305.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.100	L.M.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	50.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	3.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	24.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY257 - BENTON , CARROLL, ETC.

Contract ID: CNY257

Letting Date: October 04, 2024 10:00 AM

Projects: R4SVAR-F3-035

HSIP-REG4(233)

Counties: BENTON, CARROLL, DYER, GIBSON, HENRY,
LAKE, OBION, WEAKLEY

District:

DBE Goal Percent: 7.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
202-01.03	REMOVAL OF TRASH AND DEBRIS	(1)	LS
701-02.01	CONCRETE CURB RAMP (RETROFIT)	2,868.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	134.000	S.F.
702-01	CONCRETE CURB	8.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.010	L.M.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	100.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	3.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	36.000	L.F.
716-05.08	PAINTED PAVEMENT MARKING (PARKING LINE)	40.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY237 - BLOUNT

Contract ID: CNY237

Letting Date: October 04, 2024 10:00 AM

Projects: 05S073-F3-005
 05S073-F8-005
 05S337-F3-002
 05S337-F8-002

STP-NH/HSIP-73(83)
 STP-NH/HSIP-73(83)
 STP/HSIP-337(3)
 STP/HSIP-337(3)

Counties: BLOUNT

District:

DBE Goal Percent: 8.00

Description: The resurfacing on S.R. 337 from near U.S. 321 (S.R. 73) to near the Great Smoky Mountains National Park and on U.S. 321 (S.R. 73) from near Kinzel Springs Baptist Church to Wears Valley Road.

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	10.700	L.M.
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	1,540.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	123.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	7,703.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	1.700	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	2.300	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	1.300	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	170.000	S.Y.
705-06.32	GR TERMINAL (GATING) (TYPE 21) MASH TL2	4.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	120.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	60.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,555.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	6.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS	532.000	EACH

Contract ID CNY237 - BLOUNT

Item No.	Description	Quantity	Units
716-01.22	(BI-DIR) (1 COLOR) SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	391.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	91.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	430.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,200.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	51.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	1,510.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	9.600	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	22.500	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	580.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	3,000.000	L.F.
730-14.03	LOOP WIRE	6,000.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY249 - BLOUNT , CAMPBELL, ETC.

Contract ID: CNY249

Letting Date: October 04, 2024 10:00 AM

Projects: R1SVAR-F3-042

HSIP-REG1(224)

Counties: BLOUNT, CAMPBELL, ROANE

District:

DBE Goal Percent: 9.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	516.000	S.Y.
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (SEE PLANS)	1,571.000	L.F.
203-07	FURNISHING & SPREADING TOPSOIL	96.000	C.Y.
701-01.01	CONCRETE SIDEWALK (4 ")	4,637.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	13,099.000	S.F.
701-02.03	CONCRETE CURB RAMP	53.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	1,444.000	S.F.
702-01	CONCRETE CURB	37.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	13.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	310.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	667.000	L.F.
717-01	MOBILIZATION	(1)	LS
801-01	SEEDING (WITH MULCH)	10.000	UNIT

() Item will be bid as lump sum.

Contract ID CNY261 - BRADLEY & MCMINN

Contract ID: CNY261

Letting Date: October 04, 2024 10:00 AM

Projects: 06I075-F8-006
54I075-F8-004

NH-I-75-1(158)
NH-I-75-1(158)

Counties: BRADLEY, MCMINN

District:

DBE Goal Percent: 8.50

Description: The resurfacing on I-75 from north of Hooper Gap Road NW (L.M. 15.35) in Bradley County to south of County Road 28 (L.M. 2.06) in McMinn County.

Contract Time: DT - 7/31/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	18.800	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,364.000	TON
307-01.18	ASPHALT CONCRETE MIX (PG64-22) GRADING CM	4,430.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	10,251.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	28.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	22,148.000	S.Y.
411-03.10	ACS MIX(PG76-22) GRADING D	1,695.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	10,070.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	18.800	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	18,118.000	TON
502-01	CLEANING AND SEALING JOINTS	14,650.000	L.F.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	14,650.000	L.F.
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	2,410.000	L.F.
503-01	GRINDING CONCRETE PAVEMENT	11,200.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	290.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,207.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH

Contract ID CNY261 - BRADLEY & MCMINN

Item No.	Description	Quantity	Units
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	552.000	HOUR
713-02.14	FLEXIBLE DELINEATOR (WHITE)	624.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	11,314.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	4,988.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	120.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	3.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	873.000	L.F.
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	25.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	50.200	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	26.600	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	2,939.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	631.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	18,696.000	L.F.
717-01	MOBILIZATION	(1)	LS
403-02.01	TRACKLESS TACK COAT	272.000	TON
403-02.02	HOT APPLIED TACK COAT	128.000	TON

() Item will be bid as lump sum.

Contract ID CNY223 - CAMPBELL

Contract ID: CNY223

Letting Date: October 04, 2024 10:00 AM

Projects: 07I075-F3-015

ER-NH-I-75-3(199)

Counties: CAMPBELL

District:

DBE Goal Percent: 3.00

Description: The slide repair on I-75 northbound near M.M. 156.6 (L.M. 26.79).

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	2,948.000	C.Y.
203-06	WATER	1.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
209-05	SEDIMENT REMOVAL	13.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	114.000	L.F.
209-08.07	ROCK CHECK DAM	5.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	1.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	78.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	1.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	25.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	25.000	TON
604-07.02	RETAINING WALL (DESCRIPTION) (#2 REPAIR FROM STA. 1581+80 TO STA. 1584+82)	3,926.000	S.F.
621-03.04	30" TEMPORARY DRAINAGE PIPE	20.000	L.F.
707-10.01	ROCKFALL FENCE (TYPE I)	486.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	1,008.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	520.000	L.F.

Contract ID CNY223 - CAMPBELL

Item No.	Description	Quantity	Units
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	1.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	27.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	19.000	EACH
712-06	SIGNS (CONSTRUCTION)	478.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	1,227.000	L.F.
716-01.05	TEMPORARY RAISED PAVEMENT MARKER	30.000	EACH
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	345.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	559.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-06.01	GEOMEMBRANE	1,151.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	86.000	S.Y.
930-08.28	LOADING TEST (GROUTED ANCHOR)	39.000	EACH

() Item will be bid as lump sum.

Contract ID CNY243 - CAMPBELL

Contract ID: CNY243

Letting Date: October 04, 2024 10:00 AM

Projects: 07I075-M3-011

N/A

Counties: CAMPBELL

District:

DBE Goal Percent:

Description: The repair of the bridges on I-75 over Better Chanee Road and the RJ Corman Railroad (L.M. 2.68).

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
201-05.31	VEGETATION REMOVAL	(1)	LS
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	712.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	6.900	TON
411-03.10	ACS MIX(PG76-22) GRADING D	877.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	2.300	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	8,400.000	S.Y.
603-02.15	REPAINT EXISTING BEARINGS	(1)	LS
604-04.02	APPLIED TEXTURE FINISH (EXISTING STRUCTURES)	3,938.000	S.Y.
604-10.05	CONCRETE	163.000	S.F.
604-10.14	REMOVE EXISTING WEARING SURFACE	(1)	LS
604-10.21	CONTAINMENT & DISPOSAL OF WASTE	(1)	LS
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	195.000	S.Y.
604-10.42	CONCRETE REPAIRS	2.000	C.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	380.000	S.Y.
604-10.54	CONCRETE REPAIRS	163.000	S.F.
604-10.55	CONCRETE (FOUNDATION REPAIRS)	7.000	C.Y.
604-10.58	EPOXY INJECTION (INJECTION)	86.000	GAL.
604-10.62	EPOXY INJECTION REPAIR (COMPLETE AND IN PLACE)	860.000	L.F.

Contract ID CNY243 - CAMPBELL

Item No.	Description	Quantity	Units
617-01	BRIDGE DECK SEALANT	3,144.000	S.Y.
707-07.01	CHAIN-LINK FENCE (BRIDGES)	2,450.000	S.F.
709-04	REINFORCED CONCRETE SLOPE PAVEMENT	2.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	360.000	L.F.
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	920.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	281.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	47.000	EACH
712-06	SIGNS (CONSTRUCTION)	811.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	224.000	DAY
712-08.14	PORTABLE QUEUE WARNING SYSTEM	28.000	DAY
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	39,320.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	24.000	L.F.
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	144.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	5.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNY220 - CAMPBELL

Contract ID: CNY220

Letting Date: October 04, 2024 10:00 AM

Projects: 07S063-S3-002

N/A

Counties: CAMPBELL

District:

DBE Goal Percent:

Description: The construction of a small drainage structure on S.R. 63 near I-75 Exit 141 (L.M. 6.43).

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	747.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	769.000	C.Y.
203-06	WATER	2.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	47.370	C.Y.
204-06.01	FLOWABLE FILL (GENERAL)	90.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.100	L.M.
209-03.21	FILTER SOCK (12 INCH)	225.000	L.F.
209-03.99	PROTECTED AREA MARKER (WHITE WITH DECAL)	2.000	EACH
209-05	SEDIMENT REMOVAL	3.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	133.000	L.F.
209-65.14	TEMPORARY STREAM DIVERSION	(1)	LS
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	33.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	7.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	2.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	1.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	100.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	99.000	TON

Contract ID CNY220 - CAMPBELL

Item No.	Description	Quantity	Units
607-07.30	36" PIPE CULVERT	100.000	L.F.
607-10.03	54" CONCRETE PIPE CULVERT (CLASS IV)	63.000	L.F.
607-10.05	54" CONCRETE PIPE CULVERT(CLASS IV)JACKED- IN-PLACE	130.000	L.F.
611-01.06	MANHOLES, > 20' - 24' DEPTH	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	11.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	451.000	LB.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	300.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	200.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	310.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	20.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	15.000	EACH
712-06	SIGNS (CONSTRUCTION)	328.000	S.F.
713-16.20	SIGNS (DESCRIPTION) (R-1)	1.000	EACH
713-16.50	REMOVE AND REPLACE SIGN (DESCRIPTION) (GUIDE SIGN STA. 14+15 RT.)	1.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	34.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.250	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.250	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	186.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	281.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	9.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	9.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	10.000	UNIT
801-03	WATER (SEEDING & SODDING)	6.000	M.G.
802-11.01	ACER NEGUNDO (BOX ELDER 2-5FT CNTNR GRWN)	4.000	EACH
802-11.02	ACER RUBRUM (RED MAPLE 2-5FT CNTNR GRWN)	4.000	EACH

Contract ID CNY220 - CAMPBELL

Item No.	Description	Quantity	Units
802-11.07	BETULA NIGRA (RIVER BIRCH 2-5FT CNTNR GRWN)	4.000	EACH
802-11.11	CERCIS CANADENSIS (REDBUD 2-5FT CNTNR GRWN)	4.000	EACH
802-11.12	CORNUS FLORIDA (FLOWERING DOGWOOD 2-5FT CNTNR GRWN)	4.000	EACH
802-11.15	FAGUS GRANDIFOLIA (BEECH 2-5FT CNTNR GRWN)	4.000	EACH
802-11.26	PLATANUS OCCIDENTALIS (SYCAMORE 2-5FT CNTNR GRWN)	4.000	EACH
803-01	SODDING (NEW SOD)	341.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	740.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY255 - CHEATHAM , DICKSON, ETC.

Contract ID: CNY255

Letting Date: October 04, 2024 10:00 AM

Projects: R3SVAR-F3-064

HSIP-REG3(231)

Counties: CHEATHAM, DICKSON, HICKMAN,
HUMPHREYS, MAURY, MONTGOMERY,
ROBERTSON, STEWART

District:

DBE Goal Percent: 9.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
202-01.03	REMOVAL OF TRASH AND DEBRIS	(1)	LS
701-01.01	CONCRETE SIDEWALK (4 ")	31.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	16,657.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	139.000	S.F.
702-01	CONCRETE CURB	6.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	1.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.100	L.M.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	40.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	3.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	24.000	L.F.
716-05.22	PAINTED PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	30.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY188 - CHESTER

Contract ID: CNY188

Letting Date: October 04, 2024 10:00 AM

Projects: 12006-3219-94
12007-3220-94

BR-STP/HIP-100(80)
BR-STP/HIP-100(81)

Counties: CHESTER

District:

DBE Goal Percent: 8.00

Description: The construction of a concrete Bulb-Tee beam bridge on S.R. 100 over the South Fork Forked Deer River (L.M. 14.16), and a concrete I-beam bridge over Dry Branch (L.M. 16.03), including grading, drainage, and paving.

Contract Time: DT - 11/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	2,720.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	10,281.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	25,971.000	C.Y.
203-03.10	SELECT GRANULAR MATERIAL	3,630.000	TON
203-04	PLACING AND SPREADING TOPSOIL	401.000	C.Y.
203-06	WATER	208.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	2,869.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-02.07	18" TEMPORARY SLOPE DRAIN	33.000	L.F.
209-03.21	FILTER SOCK (12 INCH)	100.000	L.F.
209-05	SEDIMENT REMOVAL	477.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	8,576.000	L.F.
209-08.07	ROCK CHECK DAM	1.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	6.000	EACH

Contract ID CNY188 - CHESTER

Item No.	Description	Quantity	Units
209-09.04	SEDIMENT FILTER BAG(15' X 10')	4.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	2.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	280.000	L.F.
209-65.04	TEMPORARY IN STREAM DIVERSION	400.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	17,461.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	870.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	2,025.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	2,438.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	32.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	109.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	15.150	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	448.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	1,068.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	1.100	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.260	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (8IN WIDTH)	0.200	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	361.000	TON
604-10.51	SCARIFYING	578.000	S.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	148.000	L.F.
607-39.07	48" PIPE CULVERT (SIDE DRAIN)	54.000	L.F.
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	50.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	438.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	9.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	8.000	EACH
706-01	GUARDRAIL REMOVED	288.000	L.F.

Contract ID CNY188 - CHESTER

Item No.	Description	Quantity	Units
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,235.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	7.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	450.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	780.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	4,620.000	L.F.
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	280.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	10.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	188.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	63.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	32.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,304.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	132.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	56.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	6,200.000	L.F.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	2,492.000	LB.
713-11.01	"U" SECTION STEEL POSTS	2,310.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	458.000	LB.
713-11.21	P POST SLIP BASE	2.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	445.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	224.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.21	SIGNS (DESCRIPTION) (TN-17B)	1.000	EACH
713-16.22	SIGNS (DESCRIPTION) (W2-2R)	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	41.000	EACH

Contract ID CNY188 - CHESTER

Item No.	Description	Quantity	Units
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	18.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	76.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	12.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.020	L.M.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	2.000	EACH
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	6.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	5.895	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	3.044	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.000	EACH
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,447.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,963.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	9,872.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	1,710.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	491.000	UNIT
801-03	WATER (SEEDING & SODDING)	251.000	M.G.
803-01	SODDING (NEW SOD)	19,929.000	S.Y.
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO.BR-STP/HIP-100(81)	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 12SR1000013)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	348.000	C.Y.
303-01.02	GRANULAR BACKFILL (BRIDGES)	84.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	502,508.000	LB.

Contract ID CNY188 - CHESTER

Item No.	Description	Quantity	Units
604-03.01	CLASS A CONCRETE (BRIDGES)	595.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	95,849.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	429.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	1,980.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	7,006.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	7,175.000	S.Y.
604-11.01	EXPANSION DEVICE (DESCRIPTION) (STRIPSEAL, 4" TOTAL MOVEMENT)	46.000	L.F.
606-18.01	TEST PILES (STEEL PIPE PILES, 14-INCH)	1,570.000	L.F.
606-18.02	LOADING TEST (STEEL PIPE PILES, 14-INCH)	3.000	EACH
606-18.03	STEEL PIPE PILES (14-INCH)	15,060.000	L.F.
615-01.02	PRESTRESSED CONCRETE I-BEAM (TYPE II)	920.000	L.F.
615-01.10	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-54)	6,387.000	L.F.
615-05	POST-TENSIONING (DESCRIPTION) (SEE PLANS)	(1)	LS
617-02	BRIDGE DECK CRACK SEALING	162.000	L.F.
617-05	SEALANT (DESCRIPTION) (HMWM)	1.000	GAL.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	3,042.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	290.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	84.000	L.F.
790-04.03	POLE 45FT CLASS 3 WOOD	3.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	2.000	EACH
790-05.06	POLE 50FT CLASS 2 METAL	1.000	EACH
790-06.06	POLE 55 FT CLASS 2 METAL	2.000	EACH
790-21.08	1PH DEADEND 15KV	1.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	1.000	EACH
790-25.01	3PH CROSSARM SGL 15KV	1.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	1.000	EACH
790-25.29	3PH CROSSARM SGL 10FT LRG COND 15KV	3.000	EACH
790-25.37	3PH 8FT FIBERGLASS CROSSARM DEADEND 15kv	4.000	EACH

Contract ID CNY188 - CHESTER

Item No.	Description	Quantity	Units
790-25.38	3PH 10FT FIBERGLASS CROSSARM DEADEND 15kV	2.000	EACH
790-25.39	3PH 8FT FIBERGLASS DOUBLE DEADEND 15kV	1.000	EACH
790-30.13	SECONDARY CONDUCTOR 2 AL TRIPLEX	158.000	L.F.
790-31.02	SERVICE ASSEMBLY-POLE TYPE	2.000	EACH
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	13.000	EACH
790-32.06	DOWN GUY - INSULATED	12.000	EACH
790-32.23	GUY GUARD	9.000	EACH
790-33.04	SCREW TYPE ANCHOR 10,000LB-12,000LB	22.000	EACH
790-36.11	TRANSFER EXISTING 1PH TRANSFORMER/RECLOSER	1.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	1,000.000	L.F.
790-40.42	OH COND 336.4 19 AAC TULIP	1,576.000	L.F.
790-40.49	OH COND 795 37 AAC ARBUTUS	4,328.000	L.F.
790-60.01	1PH FUSE CUTOFF XARM MOUNT 15KV	1.000	EACH
790-65.03	LIGHTNING ARRESTER ARM MTD 9 KV	1.000	EACH
790-68.01	POLE GROUND ROD TYPE	5.000	EACH
790-68.02	POLE GROUND PLATE TYPE	3.000	EACH
790-69.22	POLE TOP PIN	1.000	EACH
790-69.31	STICK PIN	2.000	EACH
790-74.07	48 FIBER(MATERIAL ONLY)	1,143.000	L.F.
790-74.19	12-96 FIBER(INSTALLATION ONLY)	1,941.000	L.F.
790-74.20	108-144 FIBER(INSTALLATION ONLY)	986.000	L.F.
790-74.31	FIBER TANGENT ASSEMBLY	13.000	EACH
790-74.32	FIBER DEADEND ASSEMBLY	4.000	EACH
790-74.33	FIBER DOUBLE DEADEND ASSEMBLY	9.000	EACH
790-98.01	REMOVE WIRE	6,178.000	L.F.
790-98.02	REMOVE POLES	4.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	36.000	EACH
790-98.04	REMOVE FIBER OPTIC CABLE	1,803.000	L.F.
791-03.02	2IN HDPE GAS MAIN	673.000	L.F.

Contract ID CNY188 - CHESTER

Item No.	Description	Quantity	Units
791-04.02	HDD 2IN PE PIPE - UNCONSOLIDATED	160.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	2.000	EACH
791-07.01	2IN PE GAS VALVE ASSEMBLY	2.000	EACH
791-07.40	PE GAS FITTINGS	10.000	LB.
793-01.08	POLE 35FT CLASS 5 WOOD	2.000	EACH
793-01.41	ANCHOR 1IN	2.000	EACH
793-04.08	TRANSFER AERIAL CABLE	6.000	EACH
793-04.09	TRANSFER AERIAL DROP	2.000	EACH
793-07.01	12 FIBER (MATERIAL ONLY)	1,340.000	L.F.
793-07.16	12-96 FIBER(INSTALLATION ONLY)	1,340.000	L.F.
793-07.25	SINGLE FIBER OPTIC CABLE SPLICE	120.000	EACH
793-07.74	FIBER(144) AERIAL PRESSURIZED SPLICE CLOSURE	1.000	EACH
793-07.91	REARRANGE EXISTING FIBER STORAGE BRACKET	3.000	EACH
793-11.19	MARKER POST	2.000	EACH
793-11.58	REMOVE HANDHOLE	1.000	EACH
793-13.07	4IN SCHEDULE 40 PVC	59.000	L.F.
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	212.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	364.000	L.F.
793-14.18	LOWER CONDUIT PER 12ININCREMENTS	110.000	L.F.
793-14.19	4IN SCH 80 ORANGE FLEXPipe	2,108.000	L.F.
793-14.26	UNDERGROUND TO OVERHEAD RISER	4.000	EACH
793-16.04	DIRECTIONAL BORE 4IN/FLEX SLEEVE	1,227.000	L.F.
793-16.22	GROUND BED	2.000	EACH
793-98.04	REMOVE POLES ALL SIZES	5.000	EACH
793-98.06	REMOVE PEDESTALS	1.000	EACH
795-01.08	10IN DIP SLIP JOINT WATER LINE	2,612.000	L.F.
795-02.35	10IN HDPE WATER LINE (HDD)	600.000	L.F.
795-06.06	CONNECT TO 10IN WATER LINE	2.000	EACH
795-06.36	CUT & CAP 10IN WATER LINE	2.000	EACH

Contract ID CNY188 - CHESTER

Item No.	Description	Quantity	Units
795-11.01	BLOW-OFF ASSEMBLY	1.000	EACH
795-12.03	PIPE GROUTING	(1)	LS
795-13.01	DI FITTINGS	1,500.000	LB.

() Item will be bid as lump sum.

Contract ID CNY233 - CHESTER

Contract ID: CNY233

Letting Date: October 04, 2024 10:00 AM

Projects: 12LCOU-F3-003

BRZ-1200(30)

Counties: CHESTER

District:

DBE Goal Percent: 8.00

Description: The construction of bridges on Talley Store Road over Jacks Creek (L.M. 2.51, L.M. 2.59, and L.M. 2.64), including grading, drainage, and paving.

Contract Time: DT - 11/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,680.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,391.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	6,863.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	1,733.000	C.Y.
203-03.10	SELECT GRANULAR MATERIAL	3,834.000	TON
203-06	WATER	52.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	1,528.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-02.03	8" TEMPORARY SLOPE DRAIN	25.000	L.F.
209-02.05	12" TEMPORARY SLOPE DRAIN	150.000	L.F.
209-05	SEDIMENT REMOVAL	30.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	3,650.000	L.F.
209-08.07	ROCK CHECK DAM	16.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	4.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	18.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	1,050.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	6,762.000	TON

Contract ID CNY233 - CHESTER

Item No.	Description	Quantity	Units
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,704.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	1,117.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	14.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	430.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	3.300	TON
411-01.10	ACS MIX(PG64-22) GRADING D	663.000	TON
607-03.30	18" PIPE CULVERT	90.000	L.F.
607-05.30	24" PIPE CULVERT	42.000	L.F.
607-06.30	30" PIPE CULVERT	153.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	153.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	6.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	279.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	6.000	EACH
611-07.55	18IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	2.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	50.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	850.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	3.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	6.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	5.000	EACH
706-10.80	MICHIGAN AND MODIFIED MICHIGAN END SHOE	8.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	3,750.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	751.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	584.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	2,181.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	1,130.000	L.F.
712-02.47	BRIDGE MOUNTED INTERCONNECTED PORTABLE BARRIER RAIL	250.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH	14.000	EACH

Contract ID CNY233 - CHESTER

Item No.	Description	Quantity	Units
	TL-3)		
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	90.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	30.000	EACH
712-06	SIGNS (CONSTRUCTION)	927.000	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	8.000	L.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	192.000	L.F.
712-09.01	REMOVABLE PAVEMENT MARKING LINE	6,705.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	40.000	L.F.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	1,272.000	LB.
713-11.01	"U" SECTION STEEL POSTS	584.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	55.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	112.000	S.F.
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	17.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	50.000	L.F.
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	6.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	2.000	L.M.
717-01	MOBILIZATION	(1)	LS
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
740-07.04	GEOGRID REINFORCEMENT TYPE 2	2,705.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,435.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	9,237.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	83.000	UNIT
801-01.36	SPECIAL WETLAND SEED MIXTURE	22.000	UNIT
801-03	WATER (SEEDING & SODDING)	100.000	M.G.
802-12.61	ALNUS SERRULATA (HAZEL ALDER SEEDLING B.R.)	71.000	EACH
802-13.09	LINDERA BENZOIN (SPICEBUSH 2-5FT CNTNR GRWN)	71.000	EACH
802-13.53	CEPHALANTHUS OCCIDENTALIS (BUTTONBUSH SDLNG BARE ROOT)	71.000	EACH

Contract ID CNY233 - CHESTER

Item No.	Description	Quantity	Units
802-13.54	CORNUS AMOMUM (SILKY DOGWOOD SDLNG BARE ROOT)	71.000	EACH
803-01	SODDING (NEW SOD)	9,168.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 12-1679-2.51)	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 12-1679-2.59)	(1)	LS
202-04.03	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 12-1679-2.64)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	500.000	C.Y.
303-01.02	GRANULAR BACKFILL (BRIDGES)	62.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	81,745.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	195.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	28,749.000	LB.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	275.000	C.Y.
604-03.74	CLASS X CONCRETE	26.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	1,364.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	1,340.000	S.Y.
606-09.01	TEST PILES (PRECAST CONCRETE, SIZE 1)	420.000	L.F.
606-09.02	LOADING TEST (PRECAST CONCRETE, SIZE 1)	2.000	EACH
606-09.03	PRECAST CONCRETE PILES (SIZE 1)	2,520.000	L.F.
606-12.01	PILE ANCHORAGE SYSTEM (SEISMIC)	36.000	EACH
606-18.01	TEST PILES (STEEL PIPE PILES, 14-INCH)	160.000	L.F.
606-18.02	LOADING TEST (STEEL PIPE PILES, 14-INCH)	2.000	EACH
606-18.03	STEEL PIPE PILES (14-INCH)	700.000	L.F.
615-01.02	PRESTRESSED CONCRETE I-BEAM (TYPE II)	884.000	L.F.
615-01.10	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-54)	348.000	L.F.
617-02	BRIDGE DECK CRACK SEALING	168.000	L.F.
617-05	SEALANT (DESCRIPTION) (HMWM)	1.000	GAL.
620-06	CONCRETE RAILING	814.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	312.000	L.F.

Contract ID CNY233 - CHESTER

Item No.	Description	Quantity	Units
710-09.02	6" PIPE UNDERDRAIN	158.000	L.F.
790-04.03	POLE 45FT CLASS 3 WOOD	8.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	2.000	EACH
790-06.01	POLE 55FT CLASS 1 WOOD	1.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	1.000	EACH
790-25.01	3PH CROSSARM SGL 15KV	4.000	EACH
790-25.06	3PH CROSSARM DBL 15KV	5.000	EACH
790-25.23	3PH CROSSARM DDE 15KV	2.000	EACH
790-32.01	DOWN GUY - THROUGH BOLT TYPE	6.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	1.000	EACH
790-33.04	SCREW TYPE ANCHOR 10,000LB-12,000LB	6.000	EACH
790-36.02	TRANSFER CAPACITOR BANK	1.000	EACH
790-40.02	OH COND 2 7/1 ACSR SPARATE	11,500.000	L.F.
790-60.01	1PH FUSE CUTOFF XARM MOUNT 15KV	1.000	EACH
790-65.03	LIGHTNING ARRESTER ARM MTD 9 KV	1.000	EACH
790-65.15	3PH CAPACITOR ASSEMBLY 15KV	1.000	EACH
790-68.01	POLE GROUND ROD TYPE	6.000	EACH
790-69.31	STICK PIN	6.000	EACH
790-74.19	12-96 FIBER(INSTALLATION ONLY)	1,650.000	L.F.
790-74.20	108-144 FIBER(INSTALLATION ONLY)	2,600.000	L.F.
790-74.31	FIBER TANGENT ASSEMBLY	3.000	EACH
790-74.32	FIBER DEADEND ASSEMBLY	5.000	EACH
790-74.33	FIBER DOUBLE DEADEND ASSEMBLY	9.000	EACH
790-74.35	FIBER STORAGE DOUBLE LOOP	2.000	EACH
790-74.37	FIBER SERVICE ATTACHMENT	3.000	EACH
790-74.50	FIBER TANGENT ASSEMBLY (DESCRIPTION) (24F)	2.000	EACH
790-74.55	FIBER DOUBLE DEADEND ASSEMBLY (DESCRIPTION) (24F)	3.000	EACH
790-98.01	REMOVE WIRE	11,184.000	L.F.
790-98.02	REMOVE POLES	10.000	EACH

Contract ID CNY233 - CHESTER

Item No.	Description	Quantity	Units
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	47.000	EACH
793-06.01	POLE MOUNTED FIBER BOX	1.000	EACH
793-07.74	FIBER(144) AERIAL PRESSURIZED SPLICE CLOSURE	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNY252 - CLAY , CUMBERLAND, ETC.

Contract ID: CNY252

Letting Date: October 04, 2024 10:00 AM

Projects: R2SVAR-F3-051

HSIP-REG2(227)

Counties: CLAY, CUMBERLAND, DEKALB, PICKETT,
PUTNAM, WHITE

District:

DBE Goal Percent: 7.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 7/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	1,117.000	S.Y.
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (SEE PLANS)	6,255.000	L.F.
203-07	FURNISHING & SPREADING TOPSOIL	227.000	C.Y.
701-01.01	CONCRETE SIDEWALK (4 ")	10,050.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	25,118.000	S.F.
701-02.03	CONCRETE CURB RAMP	372.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	498.000	S.F.
702-01	CONCRETE CURB	64.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	157.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	295.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	768.000	L.F.
717-01	MOBILIZATION	(1)	LS
801-01	SEEDING (WITH MULCH)	23.000	UNIT

() Item will be bid as lump sum.

Contract ID CNY251 - COFFEE

Contract ID: CNY251

Letting Date: October 04, 2024 10:00 AM

Projects: 16945-3681-94

BRZ-1600(22)

Counties: COFFEE

District:

DBE Goal Percent: 8.50

Description: The construction of a steel bridge on Campground Lane over the Duck River in Old Stone Fort State Park, including grading, drainage, relocation of a truss bridge, and paving.

Contract Time: DT - 9/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,680.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	879.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	24.000	C.Y.
203-07	FURNISHING & SPREADING TOPSOIL	35.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-03.23	FILTER SOCK (24 INCH)	1,176.000	L.F.
209-03.99	PROTECTED AREA MARKER (WHITE WITH DECAL)	3.000	EACH
209-05	SEDIMENT REMOVAL	59.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	3,457.000	L.F.
209-09.04	SEDIMENT FILTER BAG(15' X 10')	4.000	EACH
209-13.04	TURBIDITY CURTAIN(DESCRIPTION) (WITHOUT LIGHTED BUOYS)	528.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	534.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	57.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE 57)	518.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	120.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	2.000	TON

Contract ID CNY251 - COFFEE

Item No.	Description	Quantity	Units
402-02	AGGREGATE FOR COVER MATERIAL (PC)	6.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	3.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	62.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	390.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	284.000	TON
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	49.000	L.F.
611-07.60	30IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.61	30IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
620-05.10	CONCRETE PARAPET CURVED WALL (<=TO 40MPH)	96.000	L.F.
621-03.02	18" TEMPORARY DRAINAGE PIPE	555.000	L.F.
701-01.02	CONCRETE SIDEWALK (6 ")	240.000	S.F.
701-02.03	CONCRETE CURB RAMP	120.000	S.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	25.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
706-06.03	RADIUS RAIL	51.000	L.F.
707-06.03	REMOVAL AND RESET FENCE (DESCRIPTION) (CAMPGROUND LANE SPLIT RAIL)	80.000	L.F.
707-08.02	GATE (DESCRIPTION) (SEE PLANS)	3.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	5,058.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	150.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	69.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	701.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	35.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	95.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	40.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	1.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR	200.000	LB.

Contract ID CNY251 - COFFEE

Item No.	Description	Quantity	Units
	SIGN SUPPORTS)		
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	235.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	130.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	38.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	182.000	S.F.
713-15.36	REMOVE SIGN, SUPPORT & FOOTING	22.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
714-03.03	DIRECT BURIAL CONDUIT (DESCRIPTION) (2.5" PVC, SCHEDULE 40)	260.000	L.F.
714-03.04	DIRECT BURIAL CONDUIT (DESCRIPTION) (2.5" PVC, SCHEDULE 80)	52.000	L.F.
714-04.03	CONDUIT (DESCRIPTION) (STRUCTURES - 6" RGS)	285.000	L.F.
714-06.08	CABLE (DESCRIPTION) (1/C #1 AWG)	2,588.000	L.F.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	41.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.200	L.M.
717-01	MOBILIZATION	(1)	LS
725-20.46	PULL BOX (STRUCTURE MOUNTED)	2.000	EACH
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	2.000	EACH
740-07.04	GEOGRID REINFORCEMENT TYPE 2	800.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	642.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	200.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	3,774.000	L.F.
795-51.01	BOLLARD	4.000	EACH
797-02.04	2IN HDPE FORCE MAIN	155.000	L.F.
797-05.01	8IN DIP GRAVITY SEWER 0FT-6FT DEPTH	618.000	L.F.
797-05.51	8IN PVC GRAVITY SEWER 0FT-6FT DEPTH	280.000	L.F.
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	2.000	EACH
797-07.03	48IN MANHOLE 6FT-8FT DEPTH	1.000	EACH
797-07.80	REMOVE SEWER MANHOLE	1.000	EACH
797-10.09	CONNECT EX. 8IN SEWER TO NEW MANHOLE	1.000	EACH

Contract ID CNY251 - COFFEE

Item No.	Description	Quantity	Units
797-10.14	CONNECT TO 2IN FORCE MAIN	1.000	EACH
797-10.24	REMOVE & REPLACE SEWER PUMP STATION	(1)	LS
797-11.34	REMOVE EXISTING SEWER <8IN	790.000	L.F.
797-11.92	TEMPORARY SEWER OPERATION PUMPING	1.000	LS
798-01.06	2IN INNERDUCT	855.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	299.000	UNIT
801-01.36	SPECIAL WETLAND SEED MIXTURE	4.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	8.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	7.000	UNIT
801-03	WATER (SEEDING & SODDING)	114.000	M.G.
802-11.02	ACER RUBRUM (RED MAPLE 2-5FT CNTNR GRWN)	155.000	EACH
802-11.26	PLATANUS OCCIDENTALIS (SYCAMORE 2-5FT CNTNR GRWN)	155.000	EACH
802-11.29	QUERCUS ALBA (WHITE OAK 2-5FT CNTNR GRWN)	155.000	EACH
802-11.44	ULMUS AMERICANA (AMERICAN ELM 2-5FT CNTNR GRWN)	154.000	EACH
802-12.01	ACER NEGUNDO (BOX ELDER SEEDLNG B.R.)	6.000	EACH
802-12.02	ACER RUBRUM (RED MAPLE SEEDLNG B.R.)	5.000	EACH
802-12.16	FRAXINUS PENNSYLVANICA (GREEN ASH SEEDLNG B.R.)	5.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	5.000	EACH
802-12.29	QUERCUS ALBA (WHITE OAK SEEDLNG B.R.)	5.000	EACH
802-12.45	CARPINUS CAROLINIANA (AMERICAN HORNBEAM SEEDLING B.R.)	5.000	EACH
802-16.01	SALIX NIGRA (BLACK WILLOW 3FT LIVE STAKES)	1,796.000	EACH
803-01	SODDING (NEW SOD)	7,359.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	100.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	446.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 16-B188-00.03)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	469.000	C.Y.
204-03.01	WET EXCAVATION (BRIDGES)	15.000	C.Y.

Contract ID CNY251 - COFFEE

Item No.	Description	Quantity	Units
204-04.01	ROCK EXCAVATION (BRIDGES)	52.000	C.Y.
204-05	ROCK DRILLING (BRIDGES)	54.000	L.F.
204-09.01	COFFERDAM (PIER NO. ,STA.) (PIER NO. 1, STA. 63+52.78)	(1)	LS
204-09.02	COFFERDAM (PIER NO. ,STA.) (PIER NO. 2, STA. 64+59.78)	(1)	LS
204-14	CORE DRILLING FOR PILES(ROCK)	31.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	30.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	30.000	TON
601-02	TREATED TIMBER	7.000	MBFM
602-03	STEEL STRUCTURES	(1)	LS
602-03.01	STEEL STRUCTURES	(1)	LS
602-10.01	STRUCTURAL STEEL REPAIRS	(1)	LS
602-10.51	STRUCTURAL STEEL REPAIR(DESCRIPTION)	6.000	EACH
602-10.82	TRUSS RELOCATION	(1)	LS
602-10.83	PIN INSPECTION	(1)	LS
604-02.03	EPOXY COATED REINFORCING STEEL	68,052.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	229.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	38,114.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	122.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	193.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	920.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
604-10.07	CONCRETE REMOVAL	(1)	LS
604-11.01	EXPANSION DEVICE (DESCRIPTION) (ABUTMENT NO. 1)	26.000	L.F.
606-02.03	STEEL PILES (10 INCH)	24.000	L.F.
606-03.03	STEEL PILES (12 INCH)	60.000	L.F.
610-10.45	DECK DRAINS (DESCRIPTION) (GRATE TYPE 2)	3.000	EACH
620-02	STEEL RAILING (DESCRIPTION) (CUSTOM)	267.000	L.F.
620-05.02	STANDARD CONCRETE CLASSIC PARAPET RAIL	610.000	L.F.

Contract ID CNY251 - COFFEE

Item No.	Description	Quantity	Units
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	109.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	100.000	L.F.
790-42.38	CONDUIT (DESCRIPTION) (2 - 2" DIA.)	610.000	L.F.
790-42.39	CONDUIT (DESCRIPTION) (1 = 2 1/2" DIA.)	305.000	L.F.
793-14.09	BRIDGE CONDUIT HANGER SYSTEM	(1)	LS
797-11.43	BRIDGE HANGER SYSTEM	(1)	LS
908-21.01	BEARINGS (DESCRIPTION) (TYPE I)	3.000	EACH
908-21.02	BEARINGS (DESCRIPTION) (TYPE II)	3.000	EACH
908-21.03	BEARINGS (DESCRIPTION) (TYPE III)	7.000	EACH
908-21.04	BEARINGS (DESCRIPTION) (TYPE IV)	7.000	EACH

() Item will be bid as lump sum.

Contract ID CNY262 - COFFEE

Contract ID: CNY262

Letting Date: October 04, 2024 10:00 AM

Projects: 16I024-F8-003
16I024-M3-005

NH-I-24-2(190)
NH-I-24-2(190)

Counties: COFFEE

District:

DBE Goal Percent: 8.50

Description: The resurfacing on I-24 from east of U.S. 41 (S.R. 2) (L.M. 8.86) to near S.R. 55 (L.M. 14.77), including bridge expansion joint repairs and thin epoxy overlay.

Contract Time: DT - 10/31/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	23.600	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,500.000	TON
307-01.18	ASPHALT CONCRETE MIX (PG64-22) GRADING CM	6,772.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	1,500.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	17,219.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	33.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	27,850.000	S.Y.
411-03.10	ACS MIX(PG76-22) GRADING D	868.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	15,852.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	23.600	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	24,667.000	TON
502-01	CLEANING AND SEALING JOINTS	14,660.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	920.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,496.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	11.000	EACH

Contract ID CNY262 - COFFEE

Item No.	Description	Quantity	Units
712-08.12	QUEUE PROTECTION TRUCK	150.000	DAY
713-02.14	FLEXIBLE DELINEATOR (WHITE)	150.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	990.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	990.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	170.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	6.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,742.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	4.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	4.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	45.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	78.000	L.M.
716-08.30	HYDROBLAST REMOVAL OF PAVEMENT MARKING (LINE)	5.000	L.M.
716-08.32	HYDROBLAST REMOVAL OF PAVEMENT MARKING (DESCRIPTION) (STOP LINE)	170.000	L.F.
716-08.33	HYDROBLAST REMOVAL OF PAVEMENT MARKING (DESCRIPTION) (ARROWS)	12.000	EACH
716-08.34	HYDROBLAST REMOVAL OF PAVEMENT MARKING (DESCRIPTION) (YIELD LINE)	5.100	S.Y.
716-09.86	CONTRAST PAVEMENT MARKING 6"	5.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	34.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	5,512.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,442.000	L.F.
717-01	MOBILIZATION	(1)	LS
604-10.44	EXPANSION JOINT REPAIRS	138.000	L.F.
604-10.53	CONCRETE REPAIRS	76.000	S.Y.

Contract ID CNY262 - COFFEE

Item No.	Description	Quantity	Units
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	2,809.000	S.Y.
403-02.01	TRACKLESS TACK COAT	356.000	TON
403-02.02	HOT APPLIED TACK COAT	185.000	TON

() Item will be bid as lump sum.

Contract ID CNY241 - CUMBERLAND

Contract ID: CNY241

Letting Date: October 04, 2024 10:00 AM

Projects: 18I040-F8-007
18I040-M3-006

NH-I-40-6(186)
NH-I-40-6(186)

Counties: CUMBERLAND

District:

DBE Goal Percent: 8.00

Description: The resurfacing on I-40 from near the Obed River (L.M. 13.53) to near S.R. 101 (L.M. 18.04), including bridge expansion joint repair and thin epoxy overlay.

Contract Time: DT - 10/31/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	18.300	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,932.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	23.000	TON
403-01.10	HIGH PERFORMANCE FOG SEALS	20,885.000	S.Y.
403-02.01	TRACKLESS TACK COAT	99.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	3,460.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	12,109.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	17.800	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	15,397.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	536.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,232.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	6.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	63.000	DAY
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	16.000	L.F.
713-02.14	FLEXIBLE DELINEATOR (WHITE)	122.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	7.000	EACH

Contract ID CNY241 - CUMBERLAND

Item No.	Description	Quantity	Units
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	825.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	825.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	220.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	23.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,875.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	193.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	44.600	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	22.300	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	4,610.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,304.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	3.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	40.000	L.F.
730-14.02	SAW SLOT	1,000.000	L.F.
730-14.03	LOOP WIRE	3,000.000	L.F.
604-10.44	EXPANSION JOINT REPAIRS	86.000	L.F.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	13.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY254 - DAVIDSON , MACON, ETC.

Contract ID: CNY254

Letting Date: October 04, 2024 10:00 AM

Projects: R3SVAR-F3-063

HSIP-REG3(230)

Counties: DAVIDSON, MACON, SMITH, SUMNER,
TROUSDALE, WILLIAMSON

District:

DBE Goal Percent: 8.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 6/30/2025

Item No.	Description	Quantity	Units
202-01.03	REMOVAL OF TRASH AND DEBRIS	(1)	LS
202-01.50	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	4.000	EACH
701-01.01	CONCRETE SIDEWALK (4 ")	190.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	32,989.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	1,652.000	S.F.
702-01	CONCRETE CURB	2.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	2.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.020	L.M.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	50.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	5.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	60.000	L.F.
716-05.22	PAINTED PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	150.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY206 - DAVIDSON , MONTGOMERY, ETC.

Contract ID: CNY206

Letting Date: October 04, 2024 10:00 AM

Projects: R3SVAR-M3-069

N/A

Counties: DAVIDSON, MONTGOMERY, ROBERTSON,
RUTHERFORD, SUMNER, WILLIAMSON,
WILSON

District:

DBE Goal Percent:

Description: The random on-call asphalt pothole patching on various State Routes.

Contract Time: DT - 12/31/2025

Item No.	Description	Quantity	Units
411-51.01	POTHOLE TEMPORARY REPAIR (ASPHALT)	50.000	TON
411-51.02	POTHOLE PERMANENT REPAIR (ASPHALT)	500.000	TON
411-51.10	INFRARED POTHOLE REPAIR (ASPHALT)	5,000.000	S.F.
712-01.08	LANE CLOSURE (INTERSTATE AND CONTROLLED ACCESS)	5.000	EACH
712-01.09	LANE CLOSURE (STATE ROUTES)	95.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	5.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01.20	MOBILIZATION (INTERSTATE AND CONTROLLED ACCESS) (INTERSTATE AND CONTROLLED ACCESS)	5.000	EACH
717-01.21	MOBILIZATION (STATE ROUTES) (STATE ROUTES)	35.000	EACH
717-01.22	MOBILIZATION (INFRARED REPAIRS) (INFRARED REPAIRS)	60.000	EACH

() Item will be bid as lump sum.

Contract ID CNY218 - DAVIDSON , ROBERTSON, ETC.

Contract ID: CNY218

Letting Date: October 04, 2024 10:00 AM

Projects: 19NMSC-S3-011

N/A

74NMSC-S3-002

N/A

95NMSC-S3-002

N/A

Counties: DAVIDSON, ROBERTSON, WILSON

District:

DBE Goal Percent:

Description: The construction of salt brine sheds at three (3) locations.

Contract Time: DT - 4/30/2025

Item No.	Description	Quantity	Units
680-02.01	BUILDING (DESCRIPTION) (40' X 100')	1.000	EACH
680-02.01	BUILDING (DESCRIPTION) (40' X 60')	2.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY258 - DECATUR , HARDEMAN, ETC.

Contract ID: CNY258

Letting Date: October 04, 2024 10:00 AM

Projects: R4SVAR-F3-036

HSIP-REG4(234)

Counties: DECATUR, HARDEMAN, HARDIN,
HENDERSON, MADISON, MCNAIRY

District:

DBE Goal Percent: 7.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
202-01.03	REMOVAL OF TRASH AND DEBRIS	(1)	LS
701-01.01	CONCRETE SIDEWALK (4 ")	407.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	4,646.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	143.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.010	L.M.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	50.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	3.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	36.000	L.F.
716-05.22	PAINTED PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	50.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY260 - DICKSON

Contract ID: CNY260

Letting Date: October 04, 2024 10:00 AM

Projects: 22I040-F8-004

NH-I-40-3(178)

Counties: DICKSON

District:

DBE Goal Percent: 8.50

Description: The resurfacing on I-40 from the Hickman County line (L.M. 0.00) to near East Piney Road (L.M. 5.33).

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	21.300	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,567.000	TON
307-01.18	ASPHALT CONCRETE MIX (PG64-22) GRADING CM	5,262.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	400.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	14,285.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	109.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	788.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	13,272.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	21.300	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	19,532.000	TON
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	9.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	13.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	17.000	EACH
706-01	GUARDRAIL REMOVED	1,075.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,486.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	35.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	1.000	EACH

Contract ID CNY260 - DICKSON

Item No.	Description	Quantity	Units
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	806.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	806.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	70.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	509.000	L.F.
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	1.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	51.400	L.M.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	0.130	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	25.700	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	990.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	1,319.000	L.F.
717-01	MOBILIZATION	(1)	LS
403-02.01	TRACKLESS TACK COAT	216.000	TON
403-02.02	HOT APPLIED TACK COAT	165.000	TON

() Item will be bid as lump sum.

Contract ID CNY232 - DICKSON

Contract ID: CNY232

Letting Date: October 04, 2024 10:00 AM

Projects: 22S046-S3-006

N/A

Counties: DICKSON

District:

DBE Goal Percent:

Description: The culvert replacement adjacent to S.R. 46 and Barbecue Road in Dickson, including grading, drainage, and paving.

Contract Time: DT - 11/15/2025

Item No.	Description	Quantity	Units
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-01.13	REMOVAL OF PIPE (SIZE ,STA.) (60" ,STA. 1+00)	4.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	19,386.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	91.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	431.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	2.000	EACH
209-09.04	SEDIMENT FILTER BAG(15' X 10')	2.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,720.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	10.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	526.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	11.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	7.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	310.000	TON
606-24.12	TEMPORARY SHEET PILES	8,700.000	S.F.
607-11.05	60" CONCRETE PIPE CULVERT (CLASS V)	659.000	L.F.
611-01.04	MANHOLES, > 12' - 16' DEPTH	1.000	EACH
611-01.05	MANHOLES, > 16' - 20' DEPTH	1.000	EACH
611-01.07	MANHOLES, > 24' - 28' DEPTH	1.000	EACH
611-01.08	MANHOLES, > 28' - 32' DEPTH	1.000	EACH
611-02.14	JUNCTION BOX, TYPE 5	1.000	EACH

Contract ID CNY232 - DICKSON

Item No.	Description	Quantity	Units
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	12.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	605.000	LB.
621-03.02	18" TEMPORARY DRAINAGE PIPE	30.000	L.F.
621-03.09	60" TEMPORARY DRAINAGE PIPE	140.000	L.F.
701-02.02	CONCRETE DRIVEWAY (8")	1,331.000	S.F.
702-01.01	EXTRUDED SLOPING CURB	281.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	62.500	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	812.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	310.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
714-08.30	REMOVE & RELOCATE LIGHT STANDARD	2.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.030	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	462.000	S.Y.
740-11.04	TEMPORARY SEDIMENT TUBE 20IN	2,737.000	L.F.
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	1.000	EACH
795-09.28	3/4IN COPPER SERVICE PIPE	125.000	L.F.
795-09.37	3/4IN SERVICE PIPE	125.000	L.F.
795-09.51	RECONNECT SERVICE ASSEMBLY	1.000	EACH
795-09.60	3/4IN PEXa SERVICE PIPE	125.000	L.F.
797-08.04	4IN PVC PIPE FOR SERVICE LATERAL	86.000	L.F.
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	86.000	L.F.
797-08.07	4IN CLEAN OUT ASSEMBLY	1.000	EACH
797-08.08	6IN CLEAN OUT ASSEMBLY	1.000	EACH
797-08.20	CONNECT SERVICE LINES (ALL SIZES)	1.000	EACH
797-10.05	CONNECT 4IN LATERAL TO SEWER LINE	1.000	EACH

Contract ID CNY232 - DICKSON

Item No.	Description	Quantity	Units
797-10.06	CONNECT 6IN LATERAL TO SEWER LINE	1.000	EACH
801-01	SEEDING (WITH MULCH)	9.000	UNIT
801-03	WATER (SEEDING & SODDING)	1.000	M.G.

() Item will be bid as lump sum.

Contract ID CNY259 - FAYETTE , LAUDERDALE, ETC.

Contract ID: CNY259

Letting Date: October 04, 2024 10:00 AM

Projects: R4SVAR-F3-037

HSIP-REG4(235)

Counties: FAYETTE, LAUDERDALE, SHELBY, TIPTON

District:

DBE Goal Percent: 7.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
202-01.03	REMOVAL OF TRASH AND DEBRIS	(1)	LS
701-01.01	CONCRETE SIDEWALK (4 ")	378.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	6,107.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	209.000	S.F.
712-01	TRAFFIC CONTROL	(1)	LS
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.010	L.M.
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	50.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	3.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	24.000	L.F.
716-05.22	PAINTED PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	30.000	L.F.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY207 - FAYETTE & SHELBY

Contract ID: CNY207

Letting Date: October 04, 2024 10:00 AM

Projects: R4IVAR-M3-015

N/A

Counties: FAYETTE, SHELBY

District:

DBE Goal Percent:

Description: The random on-call asphalt pothole patching on various Interstate Routes.

Contract Time: DT - 12/31/2025

Item No.	Description	Quantity	Units
411-51.01	POTHOLE TEMPORARY REPAIR (ASPHALT)	50.000	TON
411-51.02	POTHOLE PERMANENT REPAIR (ASPHALT)	500.000	TON
411-51.10	INFRARED POTHOLE REPAIR (ASPHALT)	5,000.000	S.F.
712-01.08	LANE CLOSURE (INTERSTATE AND CONTROLLED ACCESS)	100.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	20.000	DAY
712-08.20	TRUCK MOUNTED ATTENUATOR W/MSSAGE BOARD	5.000	DAY
717-01.20	MOBILIZATION (INTERSTATE AND CONTROLLED ACCESS) (INTERSTATE AND CONTROLLED ACCESS)	25.000	EACH
717-01.22	MOBILIZATION (INFRARED REPAIRS) (INFRARED REPAIRS)	75.000	EACH

() Item will be bid as lump sum.

Contract ID CNY224 - FRANKLIN

Contract ID: CNY224

Letting Date: October 04, 2024 10:00 AM

Projects: 26071-3403-94

BRZ-2600(47)

Counties: FRANKLIN

District:

DBE Goal Percent: 9.00

Description: The construction of a concrete I-beam bridge on Crownover Road over Crow Creek (L.M. 0.19), including grading, drainage, and paving.

Contract Time: DT - 5/31/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,160.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BOX CULVERT 11' X 5', STA. 14+93.64)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	6,434.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	128.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	3,296.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	346.000	C.Y.
203-06	WATER	12.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	488.000	C.Y.
204-06.01	FLOWABLE FILL (GENERAL)	73.000	C.Y.
209-05	SEDIMENT REMOVAL	36.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,599.000	L.F.
209-08.08	ENHANCED ROCK CHECK DAM	2.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	16.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	293.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	969.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	466.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	174.000	TON

Contract ID CNY224 - FRANKLIN

Item No.	Description	Quantity	Units
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	11.600	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	31.400	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	5.900	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	55.000	L.F.
411-01.10	ACS MIX(PG64-22) GRADING D	141.000	TON
604-10.51	SCARIFYING	187.000	S.Y.
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	4.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	50.000	L.F.
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (FENCES IN TRACTS 1 AND 4)	950.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	378.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	698.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-05.01	WARNING LIGHTS (TYPE A)	8.000	EACH
712-06	SIGNS (CONSTRUCTION)	650.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	90.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	112.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	21.000	S.F.
713-15.41	SIGN REMOVAL (DESCRIPTION) (STOP SIGN AT STA. 10+45.00)	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	11.000	L.F.
716-13.01	SPRAY THERMO PVMT MRKNG (60 mil) (4IN LINE)	0.600	L.M.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	490.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	365.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,195.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	236.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	45.000	UNIT

Contract ID CNY224 - FRANKLIN

Item No.	Description	Quantity	Units
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	1.000	UNIT
801-03	WATER (SEEDING & SODDING)	55.000	M.G.
802-12.02	ACER RUBRUM (RED MAPLE SEEDLNG B.R.)	2.000	EACH
802-12.03	ACER SACCHARINUM (SILVER MAPLE SEEDLNG B.R.)	2.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	2.000	EACH
803-01	SODDING (NEW SOD)	5,339.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	111.000	S.Y.
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXISTING BR. ID 26-A591-017)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	84.000	C.Y.
204-05.01	CORE DRILLING AND SAMPLING	172.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	20.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	29,103.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	89.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	13,843.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	122.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	111.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	735.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	4.000	EACH
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	459.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	394.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	14.000	EACH
615-01.02	PRESTRESSED CONCRETE I-BEAM (TYPE II)	576.000	L.F.
620-03.10	CONCRETE PARAPET (DESCRIPTION) (STD-7-1)	357.000	L.F.
625-01.11	CAMERA INSPECTION - DRILLED SHAFT (UNDERWATER)	4.000	EACH
625-02.01	DRILLED SHAFT-SOIL (DIA.) (3'-6" DIAMETER)	84.000	V.F.
625-02.13	DRILLED SHAFT-ROCK (DIA.) (3'-0" DIAMETER)	40.000	V.F.
625-02.25	DRILLED SHAFT CASING-PERMANENT (DIA.) (3'-6"	94.000	V.F.

Contract ID CNY224 - FRANKLIN

Item No.	Description	Quantity	Units
625-02.40	INSIDE DIAMETER) DRILLED SHAFT (SH-SCC) CONCRETE	45.000	C.Y.
625-02.44	DRILLED SHAFT REINFORCING STEEL	14,854.000	LB.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	94.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	38.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY246 - GRAINGER

Contract ID: CNY246

Letting Date: October 04, 2024 10:00 AM

Projects: 29007-3221-94

BR-STP-131(50)

Counties: GRAINGER

District:

DBE Goal Percent: 9.50

Description: The construction of a concrete box bridge on S.R. 131 over Williams Creek (L.M. 7.73), including grading, drainage, and paving.

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-02.21	REMOVAL OF PIPE (DESCRIPTION) (EXISTING SIDE DRAIN AT STA. 102+85.79)	53.000	L.F.
202-04.50	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXISTING 2-48" CMP PIPES, STA. 104+64)	(1)	LS
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 3)	(1)	LS
202-06.02	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 4 / 8004)	(1)	LS
202-06.03	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 6)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	6,544.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	741.000	C.Y.
203-06	WATER	30.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	196.000	C.Y.
209-03.31	STREAM MITIGATION-COCONUT FIBER ROLLS	307.000	L.F.
209-05	SEDIMENT REMOVAL	114.000	C.Y.
209-06.02	12" DIA COIR LOG (DESCRIPTION) (LOW FLOW CHANNEL)	163.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	990.000	L.F.
209-08.07	ROCK CHECK DAM	4.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	12.000	EACH

Contract ID CNY246 - GRAINGER

Item No.	Description	Quantity	Units
209-09.01	SANDBAGS	820.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	1.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	32.000	S.Y.
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	1.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	85.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,187.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	219.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	55.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	720.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	596.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	8.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	3.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	390.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	13.000	TON
604-01.01	CLASS A CONCRETE (ROADWAY)	45.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	7,917.000	LB.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	70.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	136.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	1.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	45.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	5.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	1.000	EACH
621-03.07	48" TEMPORARY DRAINAGE PIPE	62.000	L.F.
701-02	CONCRETE DRIVEWAY	36.000	S.F.
702-01	CONCRETE CURB	3.000	C.Y.
705-01.04	METAL BEAM GUARD FENCE	125.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	412.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH

Contract ID CNY246 - GRAINGER

Item No.	Description	Quantity	Units
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	7.000	EACH
706-01	GUARDRAIL REMOVED	407.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	302.000	L.F.
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	20.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	434.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	480.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	3,253.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	54.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	214.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	30.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	50.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	6,656.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	3,957.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.20	SIGNS (DESCRIPTION) (STOP, R1-1, 36"X36")	1.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	18.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	18.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	16.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	0.100	L.M.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.500	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.100	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,657.000	S.Y.

Contract ID CNY246 - GRAINGER

Item No.	Description	Quantity	Units
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	2,544.000	L.F.
801-01	SEEDING (WITH MULCH)	3.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	67.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	44.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	31.000	UNIT
801-03	WATER (SEEDING & SODDING)	20.000	M.G.
803-01	SODDING (NEW SOD)	1,258.000	S.Y.
805-12.01	EROSION CONTROL BLANKET (TYPE I)	3,379.000	S.Y.
202-04.51	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXISTING BOX BRIDGE, STA. 109+88.84)	(1)	LS
303-01.02	GRANULAR BACKFILL (BRIDGES)	440.000	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	157.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	33,737.000	LB.
790-02.04	POLE 35FT CLASS 5 WOOD	2.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	2.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	2.000	EACH
790-06.02	POLE 55FT CLASS 2 WOOD	2.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	2.000	EACH
790-25.07	3PH CROSSARM DBL LRG COND 15KV	2.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	3.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	2.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	10.000	EACH
790-30.13	SECONDARY CONDUCTOR 2 AL TRIPLEX	97.000	L.F.
790-30.14	SECONDARY CONDUCTOR 1/0 AL TRIPLEX	166.000	L.F.
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	10.000	EACH
790-33.20	ANCHOR TRIPLE EYE POWER INSTALLED	7.000	EACH
790-36.11	TRANSFER EXISTING 1PH TRANSFORMER/RECLOSER	1.000	EACH
790-36.13	TRANSFER STREET LIGHT	1.000	EACH
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	2,324.000	L.F.
790-46.02	1PH TRANSFORMER CONV W/POLE MTD FUSE & LA	2.000	EACH

Contract ID CNY246 - GRAINGER

Item No.	Description	Quantity	Units
790-60.02	1PH FUSE CUTOFF BRKT MOUNT 15KV	2.000	EACH
790-68.01	POLE GROUND ROD TYPE	3.000	EACH
790-98.01	REMOVE WIRE	3,256.000	L.F.
790-98.02	REMOVE POLES	4.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	31.000	EACH
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
793-01.18	POLE 45FT CLASS 4 WOOD	4.000	EACH
793-01.40	ANCHOR 3/4IN	71.000	EACH
793-02.08	GUY WIRE 10M OR 3/8IN	350.000	EACH
793-03.01	25 PAIR GROUP AERIAL SPLICE	1,200.000	EACH
793-03.03	10M STRAND	2,500.000	L.F.
793-03.12	50 PAIR CABLE	2,500.000	L.F.
793-03.14	100 PAIR CABLE	2,500.000	L.F.
793-03.18	400 PAIR CABLE	2,500.000	L.F.
793-03.41	AERIAL CABLE (DESCRIPTION) (1100 PAIR COPPER 22 GAUGE)	296.000	L.F.
793-04.01	RELASH/DELASH CABLE	500.000	L.F.
793-04.02	2 PAIR AERIAL DROP	30.000	L.F.
793-04.06	READY ACCESS CLOSURE	20.000	EACH
793-04.07	AERIAL SPLICE CLOSURE	10.000	EACH
793-04.25	HOT SPLICE EXISTING CABLES	1,200.000	EACH
793-07.05	96 FIBER(MATERIAL ONLY)	2,500.000	L.F.
793-07.16	12-96 FIBER(INSTALLATION ONLY)	192.000	L.F.
793-07.23	FIBER OPTIC MAINTENANCE LOOP	4.000	EACH
793-07.25	SINGLE FIBER OPTIC CABLE SPLICE	192.000	EACH
793-07.41	HOT SPLICE EXISTING FIBER CABLES	48.000	EACH
793-11.13	BURIED RISER GUARD	6.000	EACH
793-12.02	REARRANGEMENT EXISTING CABLE	3.000	EACH
793-14.24	LOAD COIL	2.000	EACH
793-15.01	TRANSFER CABLE ATTACHMENT	8.000	EACH

Contract ID CNY246 - GRAINGER

Item No.	Description	Quantity	Units
793-98.01	REMOVE AERIAL CABLE AND WIRE	8,500.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	6.000	EACH
793-98.08	REMOVE ANCHOR (ANY SIZE)	16.000	EACH
795-03.35	8IN C900 PVC WATER LINE	400.000	L.F.
795-06.05	CONNECT TO 8IN WATER LINE	1.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	1.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	2.000	EACH
795-09.60	3/4IN PEXa SERVICE PIPE	30.000	L.F.
795-10.31	2IN BLOW-OFF ASSEMBLY	1.000	EACH

() Item will be bid as lump sum.

Contract ID CNY235 - GREENE , HAWKINS, ETC.

Contract ID: CNY235

Letting Date: October 04, 2024 10:00 AM

Projects: R1SVAR-F3-040

HSIP-REG1(222)

Counties: GREENE, HAWKINS, SULLIVAN,
WASHINGTON

District:

DBE Goal Percent: 9.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	251.000	S.Y.
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (DESCRIPTION)	732.000	L.F.
203-07	FURNISHING & SPREADING TOPSOIL	66.000	C.Y.
701-01.01	CONCRETE SIDEWALK (4 ")	2,255.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	5,347.000	S.F.
701-02.03	CONCRETE CURB RAMP	749.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	97.000	S.F.
701-99.91	RAISED CONCRETE MEDIAN	(1)	LS
702-01	CONCRETE CURB	10.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	22.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	528.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	72.000	L.F.
717-01	MOBILIZATION	(1)	LS
801-01	SEEDING (WITH MULCH)	7.000	UNIT

() Item will be bid as lump sum.

Contract ID CNY205 - HAMBLEN

Contract ID: CNY205

Letting Date: October 04, 2024 10:00 AM

Projects: 32S034-F3-002

NH-34(86)

Counties: HAMBLEN

District:

DBE Goal Percent: 10.00

Description: The grading, drainage, construction of a concrete box bridge, signals, and paving on U.S. 11E (S.R. 34) from U.S. 25E (S.R. 32) (L.M. 11.14) in Morristown to near Morris Boulevard (L.M. 14.94).

Contract Time: DT - 4/30/2029

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
108-03	CPM PROJECT SCHEDULE	(1)	LS
109-10.01	TRAINEE	5,240.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-06.02	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 12)	(1)	LS
202-06.03	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 13)	(1)	LS
202-06.04	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 13A)	(1)	LS
202-06.05	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 13B)	(1)	LS
202-06.06	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 20)	(1)	LS
202-06.07	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 25)	(1)	LS
202-06.08	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 27)	(1)	LS
202-06.09	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 36)	(1)	LS
202-06.10	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 37)	(1)	LS

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
202-06.11	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 41)	(1)	LS
202-06.12	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 42)	(1)	LS
202-06.13	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 44)	(1)	LS
202-06.14	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 46)	(1)	LS
202-06.15	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 48)	(1)	LS
202-06.16	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 50)	(1)	LS
202-06.17	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 68)	(1)	LS
202-06.18	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 70)	(1)	LS
202-06.19	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 72)	(1)	LS
202-06.20	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 76)	(1)	LS
202-06.21	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 78)	(1)	LS
202-06.22	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 78A)	(1)	LS
202-06.23	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 79)	(1)	LS
202-06.24	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 99)	(1)	LS
202-06.25	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 102)	(1)	LS
202-06.26	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 112)	(1)	LS
202-09.11	REMOVAL OF UNDERGROUND TANKS (TRACT NO.) (TRACT NO. 85)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	266,398.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	557.000	TON
203-04	PLACING AND SPREADING TOPSOIL	32,262.000	C.Y.

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
203-06	WATER	418.000	M.G.
203-15.03	COMPACTED CLAY	3.000	C.Y.
204-08	FOUNDATION FILL MATERIAL	29.000	C.Y.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	9.000	C.Y.
209-02.03	8" TEMPORARY SLOPE DRAIN	1,132.000	L.F.
209-02.05	12" TEMPORARY SLOPE DRAIN	1,020.000	L.F.
209-02.07	18" TEMPORARY SLOPE DRAIN	700.000	L.F.
209-05	SEDIMENT REMOVAL	1,544.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	29,300.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	32,843.000	L.F.
209-08.07	ROCK CHECK DAM	273.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	146.000	EACH
209-09.01	SANDBAGS	500.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	191.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	8.000	EACH
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	18.000	EACH
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	50.000	EACH
209-40.43	CATCH BASIN FILTER ASSEMBLY(TYPE 3)	15.000	EACH
209-40.44	CATCH BASIN FILTER ASSEMBLY(TYPE 4)	12.000	EACH
209-40.45	CATCH BASIN FILTER ASSEMBLY(TYPE 5)	77.000	EACH
209-40.46	CATCH BASIN FILTER ASSEMBLY(TYPE 6)	3.000	EACH
209-40.48	CATCH BASIN FILTER ASSEMBLY(TYPE 8)	17.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	200.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	125,670.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	97.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	764.600	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,062.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	3,539.000	TON

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	22,597.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	28,874.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	18,914.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	271.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	1,071.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	156.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	139.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	3,546.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	11,206.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	1,757.000	S.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	44.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	10,702.000	LB.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	8,034.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	3,567.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	2,750.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	2,137.000	L.F.
607-08.02	42" CONCRETE PIPE CULVERT (CLASS III)	3,134.000	L.F.
607-09.02	48" CONCRETE PIPE CULVERT (CLASS III)	1,399.000	L.F.
607-09.30	48" PIPE CULVERT	48.000	L.F.
607-10.02	54" CONCRETE PIPE CULVERT (CLASS III)	4,587.000	L.F.
607-37.02	18" CORRUGATED METAL PIPE CULVERT	66.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	269.000	L.F.
607-39.03	24" PIPE CULVERT (SIDE DRAIN)	78.000	L.F.
607-39.04	30" PIPE CULVERT (SIDE DRAIN)	48.000	L.F.
607-45	12" SLOTTED DRAIN PIPE	40.000	L.F.
607-45.02	18" SLOTTED DRAIN PIPE	55.000	L.F.
611-01.01	MANHOLES, 0' - 4' DEPTH	1.000	EACH
611-01.02	MANHOLES, > 4' - 8' DEPTH	2.000	EACH
611-01.03	MANHOLES, > 8' - 12' DEPTH	9.000	EACH

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	37.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	1,565.000	LB.
611-07.16	PIPE CLEANING (18IN TO 24IN)	70.000	L.F.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.63	36IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-09.02	REWORK CATCHBASIN	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	27.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	60.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	14.000	EACH
611-12.04	CATCH BASINS, TYPE 12, > 12' - 16' DEPTH	12.000	EACH
611-12.07	CATCH BASINS, TYPE 12, > 24' - 28' DEPTH	1.000	EACH
611-13.03	CATCH BASINS, TYPE 13, > 8' - 12' DEPTH	1.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	44.000	EACH
611-14.03	CATCH BASINS, TYPE 14, > 8' - 12' DEPTH	21.000	EACH
611-14.04	CATCH BASINS, TYPE 14, > 12' - 16' DEPTH	5.000	EACH
611-14.05	CATCH BASINS, TYPE 14, > 16' - 20' DEPTH	1.000	EACH
611-16.02	CATCH BASINS, TYPE 16, > 4' - 8' DEPTH	3.000	EACH
611-16.03	CATCH BASINS, TYPE 16, > 8' - 12' DEPTH	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	15.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	9.000	EACH
611-42.03	CATCH BASINS, TYPE 42, > 8' - 12' DEPTH	1.000	EACH
611-43.02	CATCH BASINS, TYPE 43, > 4' - 8' DEPTH	13.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	70.000	L.F.
621-03.03	24" TEMPORARY DRAINAGE PIPE	107.000	L.F.
621-03.04	30" TEMPORARY DRAINAGE PIPE	228.000	L.F.
621-03.06	42" TEMPORARY DRAINAGE PIPE	62.000	L.F.
621-05.10	TEMPORARY SHORING (DESCRIPTION) (AT POPE ROAD)	(1)	LS

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
621-05.11	TEMPORARY SHORING (DESCRIPTION) (AT NORFOLK STREET)	(1)	LS
621-05.12	TEMPORARY SHORING (DESCRIPTION) (AT JAYBIRD ROAD)	(1)	LS
701-02	CONCRETE DRIVEWAY	11,360.000	S.F.
702-01	CONCRETE CURB	127.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	3,573.000	C.Y.
705-02.02	SINGLE GUARDRAIL (TYPE 2)	3,066.000	L.F.
705-04.03	GUARDRAIL TERMINAL (TYPE 13)	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	5.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	1,539.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	1,000.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	2,034.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	946.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	351.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	40,511.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	4,061.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	9.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	1,700.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	51.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	44.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,422.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	627.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	2.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	401.000	LB.
713-02.04	DELINEATOR (MILE MARKER) & STEEL POST	6.000	EACH

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	1,070.000	LB.
713-11.01	"U" SECTION STEEL POSTS	312.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	4,138.000	LB.
713-11.21	P POST SLIP BASE	124.000	EACH
713-11.22	U POST SLIP BASE	10.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	701.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	284.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	112.000	S.F.
713-14.22	STREET NAME SIGN (SUSPENDED 0.100IN THICK)	192.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	5.000	EACH
713-15.35	METAL BARRICADE (TYPE III)	4.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.05	RAILROAD CROSS-BUCK SIGN & SUPPORT	10.000	EACH
713-16.06	DEAD END SIGN AND SUPPORT	2.000	EACH
713-16.07	END OF ROADWAY SIGN AND SUPPORT	4.000	EACH
713-16.09	RAILROAD ADVANCE WARNING SIGN AND SUPPORT	3.000	EACH
713-16.20	SIGNS (DESCRIPTION) (LED ELECTRONIC BLANK OUT R3-1)	2.000	EACH
713-16.21	SIGNS (DESCRIPTION) (LED ELECTRONIC BLANK OUT R3-2)	2.000	EACH
714-03	JACKED OR BORED CONDUIT	1,824.000	L.F.
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	21,156.000	L.F.
714-05.04	PULL BOXES (TYPE C)	57.000	EACH
714-06.04	CABLE (1/C # 8 AWG)	15,804.000	L.F.
714-06.05	CABLE (1/C # 6 AWG)	46,578.000	L.F.
714-06.06	CABLE (1/C # 4 AWG)	24,714.000	L.F.
714-06.07	CABLE (1/C # 2 AWG)	11,754.000	L.F.
714-08.09	LIGHT STANDARDS (DESCRIPTION) (30' M.H., 15' ARM)	82.000	EACH

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
714-08.28	FOUNDATION FOR LIGHT STANDARDS - ROADWAY (DESCRIPTION) (30' M.H.)	82.000	EACH
714-09.47	LED LUMINAIRES (DESCRIPTION) (211W)	116.000	EACH
714-10.01	OVERHEAD CONDUCTORS (GAUGE & TYPE) (1/C #4 AWG)	24,714.000	L.F.
714-14.01	MASTARM - 15'	22.000	EACH
714-14.03	MASTARM (DESCRIPTION) (8')	13.000	EACH
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (PSA, 2 PROPOSED CIRCUIT BREAKERS/DISCONNECTS)	(1)	LS
714-25.02	ELECTRICAL CONNECTION (DESCRIPTION) (PSB, 1 PROPOSED CIRCUIT BREAKER/DISCONNECT)	(1)	LS
714-25.03	ELECTRICAL CONNECTION (DESCRIPTION) (PSC, 1 PROPOSED CIRCUIT BREAKER/DISCONNECT)	(1)	LS
714-25.04	ELECTRICAL CONNECTION (DESCRIPTION) (PSD, 1 PROPOSED CIRCUIT BREAKER/DISCONNECT)	(1)	LS
714-25.05	ELECTRICAL CONNECTION (DESCRIPTION) (PSE, 2 PROPOSED CIRCUIT BREAKERS/DISCONNECTS)	(1)	LS
714-25.06	ELECTRICAL CONNECTION (APPALACHIAN ENERGY COOPERATIVE)	(1)	LS
714-25.07	ELECTRICAL CONNECTION (AMERICAN ELECTRIC POWER)	(1)	LS
714-25.08	ELECTRICAL CONNECTION (DESCRIPTION) (PSH, 1 PROPOSED CIRCUIT BREAKER/DISCONNECT)	(1)	LS
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	693.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	644.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	256.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	700.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	1,100.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	73.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	410.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.900	L.M.

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	2.000	EACH
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	6.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	3.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	775.000	L.F.
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.800	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	1,010.000	L.F.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	2,100.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	3,300.000	L.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	219.000	EACH
716-05.10	PAINTED PAVEMENT MARKING (RXR)	18.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	38.500	L.M.
716-05.49	PAINTED PAVEMENT MARKINGS(8" LINE)	2.700	L.M.
716-06.01	PAINTED WORD PVMT MARK ()	6.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	19.900	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	2.000	EACH
730-02.08	SIGNAL HEAD ASSEMBLY (130 POLE MOUNTED)	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	18.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	4.000	EACH
730-02.18	SIGNAL HEAD ASSEMBLY (150 A2 POLE MOUNTED)	1.000	EACH
730-02.59	SIGNAL HEAD ASSEMBLY (140 A4F WITH BACKPLATE)	7.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	3.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	3.000	EACH
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	3,940.000	L.F.
730-09.21	SPAN WIRE ASSEMBLY (LOCATION DESCRIPTION) (JAYBIRD RD)	465.000	L.F.

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
730-09.22	SPAN WIRE ASSEMBLY (LOCATION DESCRIPTION) (MAHLE DR)	400.000	L.F.
730-09.23	SPAN WIRE ASSEMBLY (LOCATION DESCRIPTION) (E MORRIS BLVD)	420.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	1,285.000	L.F.
730-11.01	STEEL CONDUIT RISER ASSEMBLY	5.000	EACH
730-12.01	CONDUIT 1" DIAMETER (PVC SCHEDULE 40)	75.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	75.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	11.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	6.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	3.000	EACH
730-16.04	CONTROLLER (ATC)	3.000	EACH
730-23.01	STEEL STRAIN POLE (SIGNAL SUPPORT)	4.000	EACH
730-23.02	STEEL STRAIN POLE (DESCRIPTION) (SIGNAL SUPPORT, MAHLE DR)	4.000	EACH
730-23.03	STEEL STRAIN POLE (DESCRIPTION) (SIGNAL SUPPORT, E MORRIS BLVD)	4.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	3.000	EACH
730-50.31	SCHOOL SPEED LIMIT FLASHING ASSEMBLY (HARD-WIRED)	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	9,132.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	356.000	S.Y.
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	3,418.000	L.F.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	3,459.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	3,911.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	7.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	3,967.000	UNIT
801-03	WATER (SEEDING & SODDING)	286.000	M.G.
803-01	SODDING (NEW SOD)	31,034.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	6,196.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	144,838.000	S.Y.
806-02.03	PROJECT MOWING	8.000	CYCL

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
204-08	FOUNDATION FILL MATERIAL	180.000	C.Y.
209-20.04	POLYETHYLENE SHEETING (10 MIL.)	30.000	S.Y.
303-01.01	GRANULAR BACKFILL (ROADWAY)	1,624.000	TON
303-10.03	MINERAL AGGREGATE (SIZE 68)	116.000	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	587.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	124,615.000	LB.
604-02.03	EPOXY COATED REINFORCING STEEL	542.000	LB.
710-10.02	6" PERFORATED PLASTIC PIPE	89.000	L.F.
204-06.01	FLOWABLE FILL (GENERAL)	125.000	C.Y.
790-03.02	POLE 40FT CLASS 3 WOOD	3.000	EACH
790-03.03	POLE 40FT CLASS 4 WOOD	7.000	EACH
790-04.01	POLE 45FT CLASS 1 WOOD	12.000	EACH
790-04.02	POLE 45FT CLASS 2 WOOD	10.000	EACH
790-04.03	POLE 45FT CLASS 3 WOOD	57.000	EACH
790-05.01	POLE 50FT CLASS 1 WOOD	13.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	17.000	EACH
790-05.03	POLE 50FT CLASS 3 WOOD	1.000	EACH
790-06.01	POLE 55FT CLASS 1 WOOD	13.000	EACH
790-06.02	POLE 55FT CLASS 2 WOOD	1.000	EACH
790-06.03	POLE 55FT CLASS 3 WOOD	1.000	EACH
790-06.19	POLE 55FT CLASS H1 WOOD	1.000	EACH
790-07.01	POLE 60FT CLASS 1 WOOD	1.000	EACH
790-20.01	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (45FT CLASS H1 WOOD)	1.000	EACH
790-20.02	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (45 CLASS H2 WOOD)	4.000	EACH
790-20.02	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (45FT CLASS H2 WOOD)	2.000	EACH
790-20.03	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (50FT CLASS H1 WOOD)	7.000	EACH
790-20.04	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (50FT CLASS H2 WOOD)	7.000	EACH

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
790-20.05	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (50FT CLASS H3 WOOD)	3.000	EACH
790-20.06	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (55FT CLASS H3 WOOD)	4.000	EACH
790-20.07	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (60FT CLASS H3 WOOD)	2.000	EACH
790-20.90	METAL TAG INSTALLATION	7.000	EACH
790-21.05	1PH DBL PRIMARY SUPPORT 15KV	2.000	EACH
790-21.06	1PH PRIMARY MED ANGLE 15KV	1.000	EACH
790-21.08	1PH DEADEND 15KV	5.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	11.000	EACH
790-21.10	1PH VERTICAL DDE 15KV	10.000	EACH
790-21.13	1PH CROSSARM DBL LINE ARM 15KV	9.000	EACH
790-21.18	1PH DDE FEED THROUGH 15KV	1.000	EACH
790-23.07	2PH CROSSARM CONST DEADEND (SGL) 15KV	2.000	EACH
790-25.01	3PH CROSSARM SGL 15KV	1.000	EACH
790-25.06	3PH CROSSARM DBL 15KV	1.000	EACH
790-25.07	3PH CROSSARM DBL LRG COND 15KV	15.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	99.000	EACH
790-25.11	3PH CROSSARM DBL PRIM SUP LRG COND 15KV	10.000	EACH
790-25.15	3PH VERTICAL 15KV	2.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	19.000	EACH
790-25.23	3PH CROSSARM DDE 15KV	7.000	EACH
790-25.24	3PH CROSSARM DDE LRG COND 15KV	7.000	EACH
790-25.37	3PH 8FT FIBERGLASS CROSSARM DEADEND 15kv	14.000	EACH
790-26.02	3PH CROSSARM DBL LRG COND 25KV	5.000	EACH
790-30.01	SECONDARY ASSEMBLIES SMALL ANGLE	2.000	EACH
790-30.02	SECONDARY ASSEMBLIES LRG ANGLE	20.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	8.000	EACH
790-30.05	SECONDARY RACKS	3.000	EACH
790-30.06	SECONDARY CONDUCTOR 6 AL DUPLEX	1,381.000	L.F.

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
790-30.14	SECONDARY CONDUCTOR 1/0 AL TRIPLEX	961.000	L.F.
790-32.01	DOWN GUY - THROUGH BOLT TYPE	144.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	25.000	EACH
790-32.23	GUY GUARD	129.000	EACH
790-33.26	SCREW TYPE ANCHOR 28,000LB	129.000	EACH
790-36.02	TRANSFER CAPACITOR BANK	2.000	EACH
790-36.06	TRANSFER LIGHT	6.000	EACH
790-36.08	TRANSFER SECONDARY/SERVICE ASSEMBLY	2.000	EACH
790-36.09	TRANSFER - 1TR XFMR ASSEMBLY	1.000	EACH
790-36.13	TRANSFER STREET LIGHT	2.000	EACH
790-36.14	TRANSFER CONDUCTOR	5.000	EACH
790-36.15	TRANSFER FRAMING/ASSOCIATED APPARATUS	1.000	EACH
790-40.01	OH COND 4 7/1 ACSR SWANATE	1,667.000	L.F.
790-40.02	OH COND 2 7/1 ACSR SPARATE	4,144.000	L.F.
790-40.42	OH COND 336.4 19 AAC TULIP	6,862.000	L.F.
790-40.46	OH COND 556.5 19 AAC DAHLIA	20,586.000	L.F.
790-40.73	OH PRI COND _____ (336 ACSR)	44,811.000	L.F.
790-40.74	OH PRI COND _____ (2/0 ACSR)	14,937.000	L.F.
790-41.46	UG SEC COND 1/0 AL TPLX	20.000	L.F.
790-42.16	1 DUCT @ 36IN-48IN DEPTH	20.000	L.F.
790-43.46	SECONDARY PULLBOX LARGE	1.000	EACH
790-43.50	SECONDARY RISER W/ 2IN CONDUIT	3.000	EACH
790-46.01	1PH TRANSFORMER	17.000	EACH
790-58.03	CUTOUT KNIFE SWITCH, SNGL LOADBREAK 15KV	6.000	EACH
790-58.05	GOLB SWITCH 15KV	1.000	EACH
790-58.06	GOAB SWITCH 15KV	1.000	EACH
790-65.09	LIGHTNING ARRESTER 3PH 18 KV	3.000	EACH
790-65.19	3PH FUSE CUTOUT BRKT MT	3.000	EACH
790-68.01	POLE GROUND ROD TYPE	34.000	EACH

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
790-68.02	POLE GROUND PLATE TYPE	13.000	EACH
790-68.07	POLE GROUND FOR AIR BREAK SWITCH	2.000	EACH
790-74.31	FIBER TANGENT ASSEMBLY	103.000	EACH
790-74.32	FIBER DEADEND ASSEMBLY	10.000	EACH
790-74.33	FIBER DOUBLE DEADEND ASSEMBLY	77.000	EACH
790-98.01	REMOVE WIRE	145,703.000	L.F.
790-98.02	REMOVE POLES	126.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	524.000	EACH
791-01.02	2IN STEEL GAS MAIN	4.000	L.F.
791-01.04	4IN STEEL GAS MAIN	206.000	L.F.
791-02.27	<=2 IN PE TEMP. BY-PASS FOR TIE-IN	(1)	LS
791-03.02	2IN HDPE GAS MAIN	5,131.000	L.F.
791-03.04	4IN HDPE GAS MAIN	5,155.000	L.F.
791-03.05	6IN HDPE GAS MAIN	708.000	L.F.
791-04.32	HDD 6IN STEEL PIPE - ROCK	295.000	L.F.
791-04.33	HDD 8IN STEEL PIPE - ROCK	296.000	L.F.
791-04.34	HDD 12IN STEEL PIPE - ROCK	475.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	9.000	EACH
791-06.03	CONNECT TO 4IN EX. PE MAIN	1.000	EACH
791-06.31	CONNECT TO 2IN EX. STL MAIN W/ STOPPLE	3.000	EACH
791-06.32	CONNECT TO 4IN EX. STL MAIN W/ STOPPLE	3.000	EACH
791-07.01	2IN PE GAS VALVE ASSEMBLY	1.000	EACH
791-07.02	4IN PE GAS VALVE ASSEMBLY	3.000	EACH
791-07.03	6IN PE GAS VALVE ASSEMBLY	1.000	EACH
791-07.10	4IN STEEL GAS VALVE ASSEMBLY	1.000	EACH
791-08.06	1/2IN PE SERVICE PIPE	21.000	L.F.
791-08.40	RECONNECT SERVICE ASSEMBLY	2.000	EACH
791-09.02	3-WIRE CATHODIC PROTECTION STATION	1.000	EACH
791-09.03	17LB MAGNESIUM ANODES	5.000	EACH
791-10.10	RETIRE GAS MAIN	(1)	LS

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
793-01.39	ANCHOR 5/8IN	27.000	EACH
793-01.41	ANCHOR 1IN	56.000	EACH
793-02.08	GUY WIRE 10M OR 3/8IN	27.000	EACH
793-02.92	OVERHEAD GUY WIRE (DESCRIPTION) (10M)	14.000	EACH
793-02.99	INSTALL GUY GUARD	27.000	EACH
793-07.01	12 FIBER (MATERIAL ONLY)	1,059.000	L.F.
793-07.02	24 FIBER(MATERIAL ONLY)	6,169.000	L.F.
793-07.04	48 FIBER(MATERIAL ONLY)	2,104.000	L.F.
793-07.05	96 FIBER(MATERIAL ONLY)	5,879.000	L.F.
793-07.07	144 FIBER(MATERIAL ONLY)	221.000	L.F.
793-07.16	12-96 FIBER(INSTALLATION ONLY)	15,211.000	L.F.
793-07.17	108-144 FIBER(INSTALLATION ONLY)	221.000	L.F.
793-07.23	FIBER OPTIC MAINTENANCE LOOP	30.000	EACH
793-07.25	SINGLE FIBER OPTIC CABLE SPLICE	1,680.000	EACH
793-07.31	SINGLE FIBER AERIAL DROP	3,267.000	L.F.
793-07.99	TEST BARE FIBER	1.000	EACH
793-12.01	DIG SPLICE PIT 80 C.F.	8.000	EACH
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	140.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	1,000.000	L.F.
793-13.22	3 DUCT FORMATION @ 36IN DEPTH	70.000	L.F.
793-14.02	CONCRETE ENCASEMENT PER DUCT	2,220.000	L.F.
793-14.14	MULTI DUCT	1,135.000	L.F.
793-14.25	APPARATUS CASE	7.000	EACH
793-16.04	DIRECTIONAL BORE 4IN/FLEX SLEEVE	50.000	L.F.
793-98.01	REMOVE AERIAL CABLE AND WIRE	12,716.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	122.000	EACH
793-98.08	REMOVE ANCHOR (ANY SIZE)	65.000	EACH
793-98.09	REMOVE DOWN GUY	69.000	EACH
793-98.10	REMOVE FIBER STORAGE BRACKET	7.000	EACH
795-01.02	4IN DIP SLIP JOINT WATER LINE	530.000	L.F.

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	1,275.000	L.F.
795-01.04	6IN DIP SLIP JOINT WATER LINE	2,386.000	L.F.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	1,590.000	L.F.
795-01.06	8IN DIP SLIP JOINT WATER LINE	4,920.000	L.F.
795-01.08	10IN DIP SLIP JOINT WATER LINE	495.000	L.F.
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	524.000	L.F.
795-01.10	12IN DIP SLIP JOINT WATER LINE	15,866.000	L.F.
795-02.01	2IN HDPE WATER LINE	4,000.000	L.F.
795-05.02	HDD 4IN HDPE CASING PIPE-UNCON	100.000	L.F.
795-06.01	CONNECT TO 2IN WATER LINE	2.000	EACH
795-06.03	CONNECT TO 4IN WATER LINE	3.000	EACH
795-06.04	CONNECT TO 6IN WATER LINE	13.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	7.000	EACH
795-06.06	CONNECT TO 10IN WATER LINE	1.000	EACH
795-06.07	CONNECT TO 12IN WATER LINE	5.000	EACH
795-07.61	__IN X __IN TAPPING SLEEVE AND VALVE (8INX2IN)	1.000	EACH
795-08.01	2IN GATE VALVE ASSEMBLY	5.000	EACH
795-08.03	4IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	15.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	32.000	EACH
795-08.06	10IN GATE VALVE ASSEMBLY	4.000	EACH
795-08.09	12IN GATE VALVE ASSEMBLY	25.000	EACH
795-09.01	3/4IN WATER SERVICE METER ASSEMBLY	10.000	EACH
795-09.07	6IN WATER SERVICE METER ASSEMBLY	1.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	10.000	EACH
795-09.14	3/4IN HDPE SERVICE PIPE	800.000	L.F.
795-09.17	2IN HDPE SERVICE PIPE	100.000	L.F.
795-09.24	TI OF 2IN HDPE CASING FOR SERVICE PIPE-UNCON	1,962.000	L.F.
795-09.60	3/4IN PEXa SERVICE PIPE	2,525.000	L.F.
795-09.62	1IN PEX SERVICE PIPE	680.000	L.F.

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
795-09.64	2IN PEXa SERVICE PIPE	135.000	L.F.
795-11.01	BLOW-OFF ASSEMBLY	2.000	EACH
795-11.02	FIRE HYDRANT ASSEMBLY	9.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	1.000	L.F.
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-12.03	PIPE GROUTING	(1)	LS
795-12.26	REMOVE 6IN METER ASSEMBLY	1.000	EACH
795-13.01	DI FITTINGS	9,500.000	LB.
795-13.06	CREEK CROSSING (DESCRIPTION) (12IN DIP)	(1)	LS
795-14.05	CONCRETE ENCASEMENT	300.000	L.F.
795-15.02	12IN STEEL CASING PIPE OPEN CUT METHOD	1,175.000	L.F.
795-15.04	18IN STEEL CASING PIPE OPEN CUT METHOD	90.000	L.F.
795-15.05	20IN STEEL CASING PIPE OPEN CUT METHOD	524.000	L.F.
795-15.25	16IN STEEL CASING PIPE OPEN CUT METHOD	550.000	L.F.
795-16.16	RELOCATE/RECONNECT 3/4IN WATER METER ASSEMBLY	49.000	EACH
795-16.17	RELOCATE/RECONNECT 1IN WATER METER ASSEMBLY	4.000	EACH
795-16.21	RELOCATE/RECONNECT 2IN WATER METER ASSEMBLY	1.000	EACH
795-21.02	RETIRE WATER VALVES AND HYDRANTS	(1)	LS
795-30.08	2IN HDPE CASING OPEN CUT	600.000	L.F.
795-99.03	6FT X 6FT METER VAULT	1.000	EACH
797-01.13	6IN EPOXY COATED DIP FORCE MAIN	100.000	L.F.
797-01.14	8IN EPOXY COATED DIP FORCE MAIN	100.000	L.F.
797-02.58	16IN HDPE GRAVITY SEWER 6FT-12FT DEPTH	970.000	L.F.
797-05.01	8IN DIP GRAVITY SEWER 0FT-6FT DEPTH	375.000	L.F.
797-05.02	8IN DIP GRAVITY SEWER 6FT-12FT DEPTH	470.000	L.F.
797-05.03	8IN DIP GRAVITY SEWER 12FT-18FT DEPTH	1,240.000	L.F.
797-05.04	8IN DIP GRAVITY SEWER >18FT DEPTH	50.000	L.F.
797-05.51	8IN PVC GRAVITY SEWER 0FT-6FT DEPTH	1,400.000	L.F.

Contract ID CNY205 - HAMBLEN

Item No.	Description	Quantity	Units
797-05.52	8IN PVC GRAVITY SEWER 6FT-12FT DEPTH	1,250.000	L.F.
797-06.64	BORE/JACK 16IN STEEL CASING PIPE-UNCON.	200.000	L.F.
797-06.90	OPEN CUT 16IN STEEL CASING PIPE	950.000	L.F.
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	11.000	EACH
797-07.03	48IN MANHOLE 6FT-8FT DEPTH	8.000	EACH
797-07.04	48IN MANHOLE 8FT-10FT DEPTH	11.000	EACH
797-07.05	48IN MANHOLE 10FT-12FT DEPTH	5.000	EACH
797-07.07	48IN MANHOLE 14FT-16FT DEPTH	5.000	EACH
797-07.08	48IN MANHOLE 16FT-20FT DEPTH	2.000	EACH
797-07.56	MANHOLE DROP CONNECTION ASSEMBLY	3.000	EACH
797-07.80	REMOVE SEWER MANHOLE	25.000	EACH
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	400.000	L.F.
797-08.08	6IN CLEAN OUT ASSEMBLY	10.000	EACH
797-09.07	6IN PLUG VALVE ASSEMBLY	4.000	EACH
797-09.08	8IN PLUG VALVE ASSEMBLY	2.000	EACH
797-10.02	CONNECT 8IN SEWER TO EXIST. MANHOLE	8.000	EACH
797-10.06	CONNECT 6IN LATERAL TO SEWER LINE	25.000	EACH
797-10.17	CONNECT TO 6IN FORCE MAIN	2.000	EACH
797-10.18	CONNECT TO 8IN FORCE MAIN	2.000	EACH
797-10.41	CONNECT 8IN PVC TO EXISTING SEWER LINE	2.000	EACH
797-11.15	48IN MH ADJUSTMENT INCREASE HEIGHT	22.000	V.F.
797-11.20	48IN MH ADJUSTMENT DECREASE HEIGHT	6.000	V.F.
797-11.25	RETIREIN PLACE 48IN MANHOLE	5.000	EACH
797-11.31	RETIREIN PLACE EXISTING SEWER 8IN-14IN	3,000.000	L.F.
797-11.35	REMOVE EXISTING SEWER 8IN-14IN	1,000.000	L.F.
797-11.38	BY-PASS PUMPING	(1)	LS
797-11.39	TV INSPECTION	7,500.000	L.F.
797-11.45	PIPE CHECK DAM	20.000	C.Y.
797-40.01	CONCRETE ENCASEMENT	175.000	L.F.

Contract ID CNY205 - HAMBLEN

() Item will be bid as lump sum.

Contract ID CNY253 - HAMILTON & MEIGS

Contract ID: CNY253

Letting Date: October 04, 2024 10:00 AM

Projects: R2SVAR-F3-053

HSIP-REG2(229)

Counties: HAMILTON, MEIGS

District:

DBE Goal Percent: 8.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 7/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	1,326.000	S.Y.
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (SEE PLANS)	5,094.000	L.F.
203-07	FURNISHING & SPREADING TOPSOIL	288.000	C.Y.
701-01.01	CONCRETE SIDEWALK (4 ")	11,929.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	32,664.000	S.F.
701-02.03	CONCRETE CURB RAMP	51.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	1,279.000	S.F.
701-99.91	RAISED CONCRETE MEDIAN	(1)	LS
702-01	CONCRETE CURB	64.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	161.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	2,003.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	858.000	L.F.
717-01	MOBILIZATION	(1)	LS
801-01	SEEDING (WITH MULCH)	29.000	UNIT

() Item will be bid as lump sum.

Contract ID CNY238 - HAWKINS

Contract ID: CNY238

Letting Date: October 04, 2024 10:00 AM

Projects: 37S066-F3-005
37S066-F8-005

STP/HSIP-66(58)
STP/HSIP-66(58)

Counties: HAWKINS

District:

DBE Goal Percent: 7.00

Description: The resurfacing on S.R. 66 from near Choptack Road (L.M. 19.23) to the Hancock County line (L.M. 29.84).

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	22.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	1,404.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	2,673.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	56.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	10,690.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	39.000	S.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	3.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	3.000	EACH
705-06.32	GR TERMINAL (GATING) (TYPE 21) MASH TL2	3.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,389.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	700.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	700.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	150.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	224.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	112.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	11.000	L.M.

Contract ID CNY238 - HAWKINS

Item No.	Description	Quantity	Units
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	43.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY247 - HENDERSON

Contract ID: CNY247

Letting Date: October 04, 2024 10:00 AM

Projects: 39I040-F8-005

NH-I-40-2(343)

Counties: HENDERSON

District:

DBE Goal Percent: 8.00

Description: The resurfacing on I-40 from near S.R. 104 (L.M. 6.00) to west of S.R. 22 (L.M. 12.71).

Contract Time: DT - 8/31/2025

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	358.000	S.Y.
203-06	WATER	21.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	27.000	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	2,864.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	165.000	TON
307-03.11	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING CW	25,582.000	TON
403-02.01	TRACKLESS TACK COAT	137.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	28.000	L.M.
411-03.10	ACS MIX(PG76-22) GRADING D	1,030.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	16,296.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	27.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	30,505.000	TON
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	2.000	EACH
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	15.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	15.000	EACH
706-01	GUARDRAIL REMOVED	750.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	970.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	310.000	EACH

Contract ID CNY247 - HENDERSON

Item No.	Description	Quantity	Units
712-05.03	WARNING LIGHTS (TYPE C)	906.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,315.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	57.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	951.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	920.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	167.000	S.Y.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	60.000	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	30.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	1,026.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	950.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	2.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	20.000	L.F.
730-14.02	SAW SLOT	500.000	L.F.
730-14.03	LOOP WIRE	1,200.000	L.F.
403-02.02	HOT APPLIED TACK COAT	188.000	TON
403-02.01	TRACKLESS TACK COAT	253.000	TON

() Item will be bid as lump sum.

Contract ID CNY211 - HUMPHREYS

Contract ID: CNY211

Letting Date: October 04, 2024 10:00 AM

Projects: 43029-3409-94

BRZ-910(10)

Counties: HUMPHREYS

District:

DBE Goal Percent: 8.50

Description: The construction of a welded steel plate girder bridge on Bakerville Road over the Duck River (L.M. 15.71), including grading, drainage, and paving.

Contract Time: DT - 6/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	2,200.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,797.000	C.Y.
203-01.77	ROAD AND DRAINAGE EXCAVATION (UNCLASS)	160.000	C.Y.
203-01.79	EXCAVATION/BACKFILL	390.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	30,700.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	9,110.000	C.Y.
203-06	WATER	75.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	190.000	C.Y.
203-10.01	EMBANKMENT (SOLID ROCK)	390.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-02.04	10" TEMPORARY SLOPE DRAIN	85.000	L.F.
209-03.30	STREAM MITIGATION (RIVER ROCK)	100.000	TON
209-03.42	STREAM MITIGATION - LIVE BRUSH LAYERING	60.000	L.F.
209-05	SEDIMENT REMOVAL	50.000	C.Y.
209-06.02	12" DIA COIR LOG (DESCRIPTION) (BANK STABILIZATION)	500.000	L.F.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	3,900.000	L.F.
209-08.07	ROCK CHECK DAM	3.000	EACH

Contract ID CNY211 - HUMPHREYS

Item No.	Description	Quantity	Units
209-08.08	ENHANCED ROCK CHECK DAM	3.000	EACH
209-08.09	FILTER SOCK CHECK DAM	3.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,517.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	19.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE 57)	1,400.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	691.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	453.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	7.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	21.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	4.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	266.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON- CONTINUOUS) (4IN WIDTH)	1.000	L.M.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	56.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	48.000	L.F.
611-01.07	MANHOLES, > 24' - 28' DEPTH	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	3.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	138.000	LB.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	4.000	EACH
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,700.000	L.F.
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	6.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	4.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	653.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	1,780.000	TON
710-04	FILTER CLOTH UNDERDRAIN (WITH PIPE)	360.000	L.F.
711-05.71	51IN SINGLE SLOPE CONCRETE BARRIER WALL	306.000	L.F.

Contract ID CNY211 - HUMPHREYS

Item No.	Description	Quantity	Units
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	200.000	L.F.
712-02.36	REMOVE AND RELOCATE PORTABLE BARRIER RAIL	200.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	160.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	20.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	30.000	EACH
712-06	SIGNS (CONSTRUCTION)	383.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	48.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	20.000	L.F.
712-09.09	REMOVABLE PAVEMENT MARKING (4" line)	4,600.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	0.500	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	106.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	131.000	LB.
713-11.21	P POST SLIP BASE	4.000	EACH
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	62.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	32.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	1.000	L.M.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	0.250	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.400	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-07.01	GEO GRID REINFORCEMENT	135.000	S.Y.
740-07.04	GEOGRID REINFORCEMENT TYPE 2	2,200.000	S.Y.
740-10.01	GEOTEXTILE (TYPE I)(SUBSURFACE DRAINAGE)	80.000	S.Y.

Contract ID CNY211 - HUMPHREYS

Item No.	Description	Quantity	Units
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	240.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	2,875.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	2,000.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	1.000	UNIT
801-01.34	GRASS SEED MIX (RIPZN/FLPL)	5.000	UNIT
801-03	WATER (SEEDING & SODDING)	190.000	M.G.
801-08	FERTILIZER (SUPPLEMENTAL APPLICATION)	0.300	TON
802-13.10	SAMBUCUS CANADENSIS (ELDERBERRY 2-5FT CNTNR GRWN)	360.000	EACH
802-16.01	SALIX NIGRA (BLACK WILLOW 3FT LIVE STAKES)	360.000	EACH
802-16.03	CEPHALANTHUS OCCIDENTALIS (BUTTONBUSH 3FT LIVE STAKES)	360.000	EACH
802-16.04	CORNUS AMOMUM (SILKY DOGWOOD 3FT LIVE STAKES)	360.000	EACH
803-01	SODDING (NEW SOD)	10,300.000	S.Y.
805-12.08	700 GRAM COIR FIBER EROSION BLANKET	115.000	S.Y.
920-10.04	(DESCRIPTION) (OSPREY NEST PLATFORM)	1.000	EACH
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. NO. 43-0910-15.71)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	264.000	C.Y.
204-05.01	CORE DRILLING AND SAMPLING	307.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	38.000	TON
602-04.01	STEEL STRUCTURES (LOCATION & DESCRIPTION) (BR. ID NO. 430A3160001, STA. 322+40.00)	(1)	LS
604-02.03	EPOXY COATED REINFORCING STEEL	212,591.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	283.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	77,414.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	140.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	718.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	2,380.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	2,400.000	S.Y.
604-11.01	EXPANSION DEVICE (DESCRIPTION) (ABUTMENT 2)	30.000	L.F.

Contract ID CNY211 - HUMPHREYS

Item No.	Description	Quantity	Units
606-03.03	STEEL PILES (12 INCH)	633.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	16.000	EACH
610-10.45	DECK DRAINS (DESCRIPTION) (GRATE INLET-TYPE 1)	24.000	EACH
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	1,709.000	L.F.
625-01.10	CAMERA INSPECTION - DRILLED SHAFT (DRY)	2.000	EACH
625-01.11	CAMERA INSPECTION - DRILLED SHAFT (UNDERWATER)	4.000	EACH
625-02.01	DRILLED SHAFT-SOIL (DIA.) (5'-0" DIA.)	122.000	V.F.
625-02.13	DRILLED SHAFT-ROCK (DIA.) (5'-0"/4'-6" DIA.)	56.000	V.F.
625-02.25	DRILLED SHAFT CASING-PERMANENT (DIA.) (5'-0" INSIDE DIAMETER)	157.000	V.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	251.000	C.Y.
625-02.44	DRILLED SHAFT REINFORCING STEEL	66,378.000	LB.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	115.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	46.000	L.F.
908-21.01	BEARINGS (DESCRIPTION) (ABUTMENT 2)	3.000	EACH
793-11.20	HANDHOLE 30INX48IN	2.000	EACH
793-13.07	4IN SCHEDULE 40 PVC	3,755.000	L.F.
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	1,727.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	194.000	L.F.
793-14.09	BRIDGE CONDUIT HANGER SYSTEM	(1)	LS
793-14.19	4IN SCH 80 ORANGE FLEXPipe	279.000	L.F.
793-16.04	DIRECTIONAL BORE 4IN/FLEX SLEEVE	279.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY263 - JEFFERSON

Contract ID: CNY263

Letting Date: October 04, 2024 10:00 AM

Projects: 45I081-F8-004
45I081-M3-003

NH-I-81-1(137)
NH-I-81-1(137)

Counties: JEFFERSON

District:

DBE Goal Percent: 7.00

Description: The resurfacing on I-81 from I-40 (L.M. 0.00) to the Hamblen County line (7.54), including bridge deck and expansion joint repairs, and thin epoxy overlay.

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
201-01	CLEARING AND GRUBBING	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	30.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	496.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	21,942.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	115.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	391.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	23,912.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	31.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	20,159.000	TON
502-08.01	RESEALING JOINTS (HOT POURED ELASTIC)	270.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	314.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	157.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,140.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	6.000	EACH

Contract ID CNY263 - JEFFERSON

Item No.	Description	Quantity	Units
712-08.12	QUEUE PROTECTION TRUCK	50.000	DAY
712-08.14	PORTABLE QUEUE WARNING SYSTEM	6.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,309.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,309.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	1,295.000	S.Y.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	2,842.000	L.F.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	5.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	1,560.000	L.F.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	48.000	L.F.
716-09.87	CONTRAST PAVEMENT MARKINGS WORDS AND SYMBOLS	6.000	EACH
716-09.89	CONTRAST PAVEMENT MARKING 12"	495.000	L.F.
716-09.90	CONTRAST PAVEMENT MARKING 6" DOTTED	9,604.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	48.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMT MRKNG (8IN BARRIER LINE)	7,140.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	5,000.000	L.F.
717-01	MOBILIZATION	(1)	LS
307-03.09	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING C	358.000	TON
604-10.30	BRIDGE DECK REPAIRS (FULL DEPTH OF SLAB)	40.000	S.Y.
604-10.44	EXPANSION JOINT REPAIRS	232.000	L.F.
604-10.50	BRIDGE DECK REPAIRS (PARTIAL DEPTH OF SLAB)	115.000	S.Y.
617-01	BRIDGE DECK SEALANT	1,136.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	2,980.000	S.Y.
403-02.01	TRACKLESS TACK COAT	352.000	TON

Contract ID CNY263 - JEFFERSON

Item No.	Description	Quantity	Units
403-02.02	HOT APPLIED TACK COAT	123.000	TON

() Item will be bid as lump sum.

Contract ID CNY248 - JEFFERSON & KNOX

Contract ID: CNY248

Letting Date: October 04, 2024 10:00 AM

Projects: R1SVAR-F3-041

HSIP-REG1(223)

Counties: JEFFERSON, KNOX

District:

DBE Goal Percent: 7.00

Description: The ADA curb ramp upgrades on various State Routes.

Contract Time: DT - 5/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	384.000	S.Y.
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (SEE PLANS)	1,936.000	L.F.
203-07	FURNISHING & SPREADING TOPSOIL	80.000	C.Y.
701-01.01	CONCRETE SIDEWALK (4 ")	3,448.000	S.F.
701-02.01	CONCRETE CURB RAMP (RETROFIT)	9,078.000	S.F.
701-02.03	CONCRETE CURB RAMP	774.000	S.F.
701-02.06	DETECTABLE WARNING SURFACE (REHABILITATION)	227.000	S.F.
702-01	CONCRETE CURB	15.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	84.000	C.Y.
712-01	TRAFFIC CONTROL	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	2.000	EACH
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	60.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	318.000	L.F.
717-01	MOBILIZATION	(1)	LS
801-01	SEEDING (WITH MULCH)	8.000	UNIT

() Item will be bid as lump sum.

Contract ID CNY242 - KNOX

Contract ID: CNY242

Letting Date: October 04, 2024 10:00 AM

Projects: 47S009-F3-002
47S009-F8-002

NH/HSIP-9(120)
NH/HSIP-9(120)

Counties: KNOX

District:

DBE Goal Percent: 9.50

Description: The resurfacing on U.S. 25W (S.R. 9) from the Anderson County line (L.M. 0.00) to near Schaad Road (L.M. 3.50).

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	12.000	L.M.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	75.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	3,420.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	8,031.000	TON
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	1.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	11,566.000	TON
701-02.01	CONCRETE CURB RAMP (RETROFIT)	650.000	S.F.
701-02.03	CONCRETE CURB RAMP	200.000	S.F.
702-03	CONCRETE COMBINED CURB & GUTTER	9.000	C.Y.
705-01.01	GUARDRAIL AT BRIDGE ENDS	50.000	L.F.
705-02.03	SINGLE GUARDRAIL (TYPE 2) LONG POST	780.000	L.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	1.000	EACH
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	3.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	2.000	EACH
706-01	GUARDRAIL REMOVED	780.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	256.000	EACH

Contract ID CNY242 - KNOX

Item No.	Description	Quantity	Units
712-05.01	WARNING LIGHTS (TYPE A)	128.000	EACH
712-06	SIGNS (CONSTRUCTION)	909.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	1,935.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	2,093.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	145.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	4,173.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	248.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	702.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	83.000	EACH
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	335.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	1,172.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	4.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	17.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	17.000	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	5,567.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	20,000.000	L.F.
730-14.03	LOOP WIRE	10,000.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY244 - KNOX

Contract ID: CNY244

Letting Date: October 04, 2024 10:00 AM

Projects: 47S034-F3-002
47S034-F8-002

STP/HSIP-34(134)
STP/HSIP-34(134)

Counties: KNOX

District:

DBE Goal Percent: 8.00

Description: The resurfacing on U.S. 11E (S.R. 34) from U.S. 25W (S.R. 9) (L.M. 0.00) to the Jefferson County line (L.M. 3.43).

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	14.000	L.M.
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	1,485.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	113.000	TON
411-03.13	ACS MIX(PG70-22) THIN LIFT D ASPHALT	7,423.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	6.000	L.M.
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	2,111.000	S.Y.
705-01.01	GUARDRAIL AT BRIDGE ENDS	50.000	L.F.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	2.000	EACH
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	264.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	132.000	EACH
712-06	SIGNS (CONSTRUCTION)	937.000	S.F.
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	90.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	220.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	460.000	EACH

Contract ID CNY244 - KNOX

Item No.	Description	Quantity	Units
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	770.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	200.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	435.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	19.000	EACH
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	1,136.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	821.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	4.000	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	16.000	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY227 - KNOX

Contract ID: CNY227

Letting Date: October 04, 2024 10:00 AM

Projects: 47NMSC-S3-012

N/A

Counties: KNOX

District:

DBE Goal Percent:

Description: The construction of a 40' x 40' and a 40' x 100' brine shed at 7345 Region Lane in Knoxville.

Contract Time: DT - 4/30/2025

Item No.	Description	Quantity	Units
680-02.01	BUILDING (DESCRIPTION) (40'x40')	1.000	EACH
680-02.02	BUILDING (DESCRIPTION) (40'x100')	1.000	EACH
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY239 - MONROE

Contract ID: CNY239

Letting Date: October 04, 2024 10:00 AM

Projects: 62S033-F3-005
 62S033-F3-006
 62S033-F8-005
 62S033-F8-006

STP-NH/HSIP-33(157)
 STP-NH/HSIP-33(158)
 STP-NH/HSIP-33(157)
 STP-NH/HSIP-33(158)

Counties: MONROE

District:

DBE Goal Percent: 8.50

Description: The resurfacing on U.S. 411 (S.R. 33) from near S.R. 68 (L.M. 5.32) to near Warren Street (L.M. 7.07) and from near the Little Tennessee River (L.M. 16.87) to near the Loudon County line (L.M. 18.11).

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	12.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	614.000	TON
307-01.15	ASC MIX (PG64-22) (BPMLC-HM) GRADING CS	382.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	63.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	3,819.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	6,681.000	TON
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	2.000	L.M.
411-12.03	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (8IN WIDTH)	3.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	6,395.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	127.000	S.Y.
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	1.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	318.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	159.000	EACH

Contract ID CNY239 - MONROE

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	1,906.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	252.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	101.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	384.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	737.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	1,300.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	400.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	29.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	2,086.000	L.F.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	4.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	3.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	468.000	S.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	10.100	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	13.200	L.M.
716-13.05	SPRAY THERMO PVMT MRKNG (60 mil) (6IN DOTTED LINE)	600.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-14.02	SAW SLOT	9,500.000	L.F.
730-14.03	LOOP WIRE	19,000.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY221 - MONROE

Contract ID: CNY221

Letting Date: October 04, 2024 10:00 AM

Projects: 62S322-S3-002

N/A

Counties: MONROE

District:

DBE Goal Percent:

Description: The grading, drainage, construction of a concrete Bulb-Tee beam bridge, signals, and paving on S.R. 322 over I-75, supporting Red Stag Fulfillment Center (L.M. 0.42 to L.M. 0.93).

Contract Time: DT - 6/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.50	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1.000	EACH
202-02.21	REMOVAL OF PIPE (DESCRIPTION) (EXISTING SIDE DRAIN AT BELCHER ROAD)	75.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	18,960.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	290.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	26,376.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	2,000.000	C.Y.
203-06	WATER	148.000	M.G.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	20.000	C.Y.
209-05	SEDIMENT REMOVAL	327.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	6,895.000	L.F.
209-08.07	ROCK CHECK DAM	2.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	13.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	11,729.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	1,181.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,944.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	1,611.000	TON

Contract ID CNY221 - MONROE

Item No.	Description	Quantity	Units
307-01.20	ASP. CONC. MIX(PG64-22) (BPMB-HM) GR. A-S	1,336.000	TON
313-03	TREATED PERMEABLE BASE	6,128.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	21.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	74.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	11.000	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	421.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	662.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.600	L.M.
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	0.100	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	75.000	TON
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	3,628.000	S.Y.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	70.000	L.F.
607-09.02	48" CONCRETE PIPE CULVERT (CLASS III)	8.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	7.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	254.000	LB.
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
702-01	CONCRETE CURB	10.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	1,347.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	5.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
705-20.25	TEMPORARY CRASH CUSHION (MASH TL-3)	11.000	EACH
706-01	GUARDRAIL REMOVED	1,030.000	L.F.
707-03.01	STOCK FENCE	152.000	L.F.
707-03.02	END, BRACED LINE, CORNER POST ASSEMBLY(STOCK FENCE)	1.000	EACH
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (EXISTING ROW FENCE)	288.000	L.F.

Contract ID CNY221 - MONROE

Item No.	Description	Quantity	Units
709-05.05	MACHINED RIP-RAP (CLASS A-3)	534.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	388.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	4,020.000	L.F.
710-05	LATERAL UNDERDRAIN	416.000	L.F.
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	16.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	5,000.000	L.F.
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	800.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	63.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	70.000	EACH
712-06	SIGNS (CONSTRUCTION)	378.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	24.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	2,500.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	9.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	1,550.000	LB.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	40.000	L.F.
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	2,116.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	873.000	LB.
713-11.03	2 1/2" DIA ROUND STEEL TUBE SIGN POST	212.000	LB.
713-11.05	SQUARE TUBE SIGN SUPPORT	1,398.000	LB.
713-11.21	P POST SLIP BASE	10.000	EACH
713-11.23	ROUND POST SLIP BASE	4.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	199.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	205.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	173.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	15.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS

Contract ID CNY221 - MONROE

Item No.	Description	Quantity	Units
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	2.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	5.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	140.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	26.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	13.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	252.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	22.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	630.000	L.F.
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	350.000	L.F.
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	6.000	EACH
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	2.000	EACH
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	80.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	2.270	L.M.
716-09.86	CONTRAST PAVEMENT MARKING 6"	0.770	L.M.
716-09.88	CONTRAST PAVEMENT MARKING 8"	0.190	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.700	L.M.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	1,400.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-02.08	SIGNAL HEAD ASSEMBLY (130 POLE MOUNTED)	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	4.000	EACH
730-02.59	SIGNAL HEAD ASSEMBLY (140 A4F WITH BACKPLATE)	1.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	3.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	1.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	195.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	722.000	L.F.

Contract ID CNY221 - MONROE

Item No.	Description	Quantity	Units
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	92.000	L.F.
730-12.26	CONDUIT 2" DIAMETER (PVC SCHEDULE 80)	162.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	3.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	2.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	1.000	EACH
730-16.04	CONTROLLER (ATC)	1.000	EACH
730-23.95	CANTILEVER SIGNAL SUPPORT (2 @ 45' & 45')	1.000	EACH
730-25.07	CANTILEVER SIGNAL SUPPORT (1 ARM @ 55')	1.000	EACH
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,956.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	569.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	4,490.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	106.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	212.000	UNIT
801-03	WATER (SEEDING & SODDING)	37.000	M.G.
803-01	SODDING (NEW SOD)	457.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	23,501.000	S.Y.
806-02.03	PROJECT MOWING	2.000	CYCL
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BRIDGE NO. 78-0A359-00.01)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	489.000	C.Y.
204-14	CORE DRILLING FOR PILES(ROCK)	300.000	L.F.
204-15	CORE DRILLING FOR PILES(SOIL)	388.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	42.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	213,078.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	479.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	84,776.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	296.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	593.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	5,857.000	S.Y.
604-04.41	THREE STAR STATE EMBLEM	8.000	EACH

Contract ID CNY221 - MONROE

Item No.	Description	Quantity	Units
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	2,109.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	1,688.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	30.000	EACH
615-01.14	PRESTRESSED CONCRETE BULB TEE BEAM (8" WEB)(BT-63)	2,375.000	L.F.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	768.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	176.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	38.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY219 - OBION

Contract ID: CNY219

Letting Date: October 04, 2024 10:00 AM

Projects: 66116-3216-04

N/A

Counties: OBION

District:

DBE Goal Percent:

Description: The construction of turn lanes on U.S. 51 (S.R. 3) at Greenfield Drive/N. Morgan Street (L.M. 20.52 to L.M. 20.84) for SIA support serving Williams Sausage HQ.

Contract Time: DT - 7/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (SIZE 18 INCH,STA. 79+85.64)	14.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (SIZE 24 INCH,STA. 83+88.36)	14.000	L.F.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CATCH BASIN, STA. 79+85.29 & STA. 83+88.93)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,493.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	63.000	C.Y.
203-06	WATER	23.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.500	L.M.
209-05	SEDIMENT REMOVAL	36.000	C.Y.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	3.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,490.000	TON
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	100.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	217.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	716.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	348.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	4.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	14.000	TON

Contract ID CNY219 - OBION

Item No.	Description	Quantity	Units
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	7.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	1,300.000	L.F.
411-02.10	ACS MIX(PG70-22) GRADING D	1,001.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	0.243	L.M.
411-12.02	SCORING SHOULDERS (NON-CONTINUOUS) (16IN WIDTH)	0.389	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	830.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	14.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	14.000	L.F.
611-38.02	CATCH BASINS, TYPE 38, > 4' - 8' DEPTH	1.000	EACH
611-38.03	CATCH BASINS, TYPE 38, > 8' - 12' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	50.000	L.F.
703-01	PORTLAND CEMENT CONCRETE DITCH PAVING	265.000	C.Y.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	467.000	L.F.
710-05	LATERAL UNDERDRAIN	45.000	L.F.
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	1.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	1.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	125.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	60.000	EACH
712-05.03	WARNING LIGHTS (TYPE C)	60.000	EACH
712-06	SIGNS (CONSTRUCTION)	568.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	4,200.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
713-16.20	SIGNS (DESCRIPTION) (BIKE ROUTE, D11-1)	2.000	EACH
713-16.21	SIGNS (DESCRIPTION) (WRONG WAY, R5-1A)	4.000	EACH

Contract ID CNY219 - OBION

Item No.	Description	Quantity	Units
713-16.23	SIGNS (DESCRIPTION) (KEEP RIGHT, R4-7)	2.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	44.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	36.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	41.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	220.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	76.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	8.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	1.000	EACH
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	7,150.000	L.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.563	L.M.
716-05.21	PAINTED PAVEMENT MARKING(4"DOTTED LINE)	200.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	1,240.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	1.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	200.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.563	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	172.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	4.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	4.000	UNIT
801-03	WATER (SEEDING & SODDING)	35.000	M.G.
803-01	SODDING (NEW SOD)	784.000	S.Y.

() Item will be bid as lump sum.

Contract ID CNY229 - PERRY

Contract ID: CNY229

Letting Date: October 04, 2024 10:00 AM

Projects: 68LCOU-F3-003

BRZ-921(17)

Counties: PERRY

District:

DBE Goal Percent: 8.00

Description: The construction of a concrete Bulb-Tee beam bridge on South Mill Street over the Buffalo River (L.M. 0.22) in Linden, including grading, drainage, and paving.

Contract Time: DT - 6/30/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	1,680.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CROSS DRAIN HEADWALL, 112+22.00)	(1)	LS
202-04.02	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CONCRETE DITCH & 12" CMP, 104+57.00)	(1)	LS
202-04.03	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CONCRETE DITCH & 12" CMP, 104+59.00)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,092.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	4,100.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	1,180.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	731.000	C.Y.
203-06	WATER	15.000	M.G.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	6.500	C.Y.
209-05	SEDIMENT REMOVAL	46.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	1,075.000	L.F.
209-08.07	ROCK CHECK DAM	3.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	2.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	2.000	EACH

Contract ID CNY229 - PERRY

Item No.	Description	Quantity	Units
209-40.30	CATCH BASIN PROTECTION (TYPE A)	1.000	EACH
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	1.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	800.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	494.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	837.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	75.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	2.800	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	8.500	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.100	TON
411-01.10	ACS MIX(PG64-22) GRADING D	113.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	43.000	TON
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	46.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	2.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	93.000	LB.
611-07.33	30IN ENDWALL (SIDE DRAIN)	1.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	1.000	EACH
620-05.10	CONCRETE PARAPET CURVED WALL (<=TO 40MPH)	24.000	L.F.
702-01	CONCRETE CURB	4.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	93.000	L.F.
705-06.26	THRIE BEAM BRIDGE TRANSITION MASH TL-2	1.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
705-20.22	REUSABLE CRSH CUSHION NARW (MASH TL-3)	2.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	380.000	L.F.
709-05.06	MACHINED RIP-RAP (CLASS A-1)	124.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	1,100.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	200.000	TON
711-05.81	32IN HALF SIZE SINGLE SLOPE CONCRETE BARRIER WALL	879.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH

Contract ID CNY229 - PERRY

Item No.	Description	Quantity	Units
712-05.01	WARNING LIGHTS (TYPE A)	32.000	EACH
712-06	SIGNS (CONSTRUCTION)	436.000	S.F.
712-07.02	TEMPORARY BARRICADES (TYPE II)	84.000	L.F.
713-02.26	CONCRETE BARRIER/PARAPET DELINEATOR	3.000	EACH
713-15.01	REMOVAL OF EXISTING SIGN POST	1.000	EACH
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	1.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	3.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	15.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.000	L.M.
716-15.10	PREFORMED PERMANENT TAPE (6IN LINE)	3,168.000	L.F.
717-01	MOBILIZATION	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	1,505.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	409.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	3,219.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	1,550.000	L.F.
801-01	SEEDING (WITH MULCH)	13.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	13.000	UNIT
801-01.35	GRASS SEED MIX (RIPZN/FLPL) W/MULCH	2.000	UNIT
801-03	WATER (SEEDING & SODDING)	3.000	M.G.
802-12.01	ACER NEGUNDO (BOX ELDER SEEDLNG B.R.)	22.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	22.000	EACH
802-12.31	QUERCUS FALCATA (SOUTHERN RED OAK SEEDLNG B.R.)	22.000	EACH
802-12.34	QUERCUS MUEHLENBERGII (CHINKAPIN OAK SEEDLNG B.R.)	22.000	EACH
802-16.01	SALIX NIGRA (BLACK WILLOW 3FT LIVE STAKES)	125.000	EACH
805-12.02	EROSION CONTROL BLANKET (TYPE II)	1,000.000	S.Y.
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BR. LOC. NO. 68-00921-00.22)	(1)	LS

Contract ID CNY229 - PERRY

Item No.	Description	Quantity	Units
204-02.01	DRY EXCAVATION (BRIDGES)	264.000	C.Y.
204-05.01	CORE DRILLING AND SAMPLING	478.000	L.F.
303-01.02	GRANULAR BACKFILL (BRIDGES)	57.000	TON
602-04.01	STEEL STRUCTURES (LOCATION & DESCRIPTION) (BR. ID NO. 68F02430001, 107+95.00)	(1)	LS
604-01.20	BOX TUBE SAFETY RAIL	879.000	L.F.
604-02.03	EPOXY COATED REINFORCING STEEL	237,434.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	343.000	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	53,921.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	230.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	968.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	2,189.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	2,327.000	S.Y.
604-11.01	EXPANSION DEVICE (DESCRIPTION) (STRIP SEAL, 4" MOVEMENT)	94.000	L.F.
606-02.03	STEEL PILES (10 INCH)	564.000	L.F.
606-02.06	PILE TIPS (STEEL PILES, 10 INCH)	20.000	EACH
610-10.45	DECK DRAINS (DESCRIPTION) (GRATE INLET-TYPE 2)	23.000	EACH
615-01.11	PRESTRESSED CONCRETE BULB TEE BEAM (6" WEB)(BT-63)	1,138.000	L.F.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	767.000	L.F.
625-01.10	CAMERA INSPECTION - DRILLED SHAFT (DRY)	6.000	EACH
625-01.11	CAMERA INSPECTION - DRILLED SHAFT (UNDERWATER)	6.000	EACH
625-02.01	DRILLED SHAFT-SOIL (DIA.) (4'-0" DIA.)	169.000	V.F.
625-02.13	DRILLED SHAFT-ROCK (DIA.) (4'-0"/3'-6" DIA.)	189.000	V.F.
625-02.25	DRILLED SHAFT CASING-PERMANENT (DIA.) (4'-0" INSIDE DIAMETER)	110.000	V.F.
625-02.40	DRILLED SHAFT (SH-SCC) CONCRETE	162.000	C.Y.
625-02.44	DRILLED SHAFT REINFORCING STEEL	56,713.000	LB.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	149.000	L.F.

Contract ID CNY229 - PERRY

Item No.	Description	Quantity	Units
710-09.02	6" PIPE UNDERDRAIN	40.000	L.F.
714-01	STRUCTURAL LIGHTING	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY236 - RUTHERFORD

Contract ID: CNY236

Letting Date: October 04, 2024 10:00 AM

Projects: 75I840-F8-007

NH-I-840(25)

Counties: RUTHERFORD

District:

DBE Goal Percent: 8.50

Description: The resurfacing on I-840 from the East Fork Stones River Bridge (L.M. 15.50) to the Wilson County line (L.M. 20.54).

Contract Time: DT - 11/30/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	21.500	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	4,271.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	556.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	18,459.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	104.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	2,500.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	11,135.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	21.500	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	16,405.000	TON
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	566.000	S.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	1,472.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	816.000	EACH
502-04.03	TRANSVERSE TIE-BARS	84.000	EACH
502-08.07	SEALING RANDOM CRACKS (SILICONE SEALANT)	755.000	L.F.
705-04.09	EARTH PAD FOR TYPE 38 GR END TREATMENT	2.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	390.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	97.500	EACH

Contract ID CNY236 - RUTHERFORD

Item No.	Description	Quantity	Units
712-06	SIGNS (CONSTRUCTION)	1,951.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	2.000	EACH
712-07.03	TEMPORARY BARRICADES (TYPE III)	72.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	10.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	120.000	DAY
713-02.11	REMOVAL OF EXISTING DELINEATORS	150.000	EACH
713-02.14	FLEXIBLE DELINEATOR (WHITE)	325.000	EACH
713-02.15	FLEXIBLE DELINEATOR (YELLOW)	103.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	4.000	EACH
713-16.20	SIGNS (DESCRIPTION) (R1-2)	1.000	EACH
713-16.21	SIGNS (DESCRIPTION) (W4-2L)	3.000	EACH
713-16.22	SIGNS (DESCRIPTION) (W4-2R)	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	900.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	900.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	76.000	L.F.
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,825.000	L.F.
716-04.06	PLASTIC PAVEMENT MARKING (WRONG WAY ARROW)	4.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	12.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	6.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	48.500	L.M.
716-08.30	HYDROBLAST REMOVAL OF PAVEMENT MARKING (LINE)	4.600	L.M.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	1.700	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	32.600	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN	17,222.000	L.F.

Contract ID CNY236 - RUTHERFORD

Item No.	Description	Quantity	Units
	DOTTED LINE)		
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	8,900.000	L.F.
716-15.10	PREFORMED PERMANENT TAPE (6IN LINE)	7,870.000	L.F.
716-15.11	PREFORMED PERMANENT TAPE (8IN LINE)	12,596.000	L.F.
716-15.20	PREFORMED PERMANENT TAPE (24IN BARRIER LINE)	2,250.000	L.F.
717-01	MOBILIZATION	(1)	LS
730-03.20	INSTALL PULL BOX (TYPE A)	2.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	20.000	L.F.
730-14.02	SAW SLOT	400.000	L.F.
730-14.03	LOOP WIRE	1,200.000	L.F.
403-02.02	HOT APPLIED TACK COAT	142.000	TON
403-02.01	TRACKLESS TACK COAT	106.000	TON

() Item will be bid as lump sum.

Contract ID CNY216 - RUTHERFORD

Contract ID: CNY216

Letting Date: October 04, 2024 10:00 AM

Projects: 75011-3245-94

NH-SIP-96(62)

Counties: RUTHERFORD

District:

DBE Goal Percent: 8.00

Description: The grading, drainage, and paving on S.R. 96 at the intersection of North Thompson Lane in Murfreesboro (L.M. 9.66 - L.M. 9.79).

Contract Time: DT - 7/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
202-08.10	REMOVAL OF CURB (DESCRIPTION) (THOMPSON LN.)	20.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	412.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	11.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	0.200	L.M.
209-05	SEDIMENT REMOVAL	34.000	C.Y.
209-08.08	ENHANCED ROCK CHECK DAM	2.000	EACH
209-08.09	FILTER SOCK CHECK DAM	11.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	802.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	192.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	208.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	136.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	2.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	6.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	1,000.000	L.F.
411-02.10	ACS MIX(PG70-22) GRADING D	350.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	249.000	TON

Contract ID CNY216 - RUTHERFORD

Item No.	Description	Quantity	Units
709-05.05	MACHINED RIP-RAP (CLASS A-3)	100.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	900.000	L.F.
710-05	LATERAL UNDERDRAIN	55.000	L.F.
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	5.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,250.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	2.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	50.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	63.000	EACH
712-06	SIGNS (CONSTRUCTION)	922.000	S.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	6.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVMENT MARKERS (MONO-DIR)(1 COLOR)	12.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	97.000	EACH
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	970.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	84.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	6.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	150.000	L.F.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	1,000.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.400	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.400	L.M.
717-01	MOBILIZATION	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	172.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	912.000	L.F.
801-01	SEEDING (WITH MULCH)	1.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	2.000	UNIT
801-03	WATER (SEEDING & SODDING)	0.300	M.G.

Contract ID CNY216 - RUTHERFORD

Item No.	Description	Quantity	Units
-----------------	--------------------	-----------------	--------------

() Item will be bid as lump sum.

Contract ID CNY234 - RUTHERFORD

Contract ID: CNY234

Letting Date: October 04, 2024 10:00 AM

Projects: 75013-3252-14

STP-99(39)

Counties: RUTHERFORD

District:

DBE Goal Percent: 10.00

Description: The grading, drainage, construction of concrete box bridges, signals, and paving on S.R. 99 (New Salem Highway) from west of Veterans Parkway (SW Loop) (L.M. 13.88) to Cason Lane (L.M. 15.97) in Murfreesboro.

Contract Time: DT - 12/15/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
108-03	CPM PROJECT SCHEDULE	(1)	LS
109-10.01	TRAINEE	5,600.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	60,035.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	17,600.000	TON
203-03	BORROW EXCAVATION (UNCLASSIFIED)	105,035.000	C.Y.
203-03.15	BORROW EXCAVATION (CLAY)	170.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	11,295.000	C.Y.
203-05	UNDERCUTTING	9,835.000	C.Y.
203-06	WATER	365.000	M.G.
203-08	CHANNEL EXCAVATION (UNCLASSIFIED)	360.000	C.Y.
204-06.01	FLOWABLE FILL (GENERAL)	40.000	C.Y.
209-02.07	18" TEMPORARY SLOPE DRAIN	1,575.000	L.F.
209-05	SEDIMENT REMOVAL	1,882.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	16,428.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	53,415.000	L.F.
209-08.07	ROCK CHECK DAM	71.000	EACH

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
209-08.08	ENHANCED ROCK CHECK DAM	13.000	EACH
209-09.01	SANDBAGS	2,000.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	6.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	209.000	EACH
209-10.20	TEMPORARY SEDIMENT TRAP	1,828.000	C.Y.
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	260.000	S.Y.
209-40.30	CATCH BASIN PROTECTION (TYPE A)	6.000	EACH
209-40.46	CATCH BASIN FILTER ASSEMBLY(TYPE 6)	185.000	EACH
209-40.47	CATCH BASIN FILTER ASSEMBLY(TYPE 7)	7.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	84.000	L.F.
209-65.04	TEMPORARY IN STREAM DIVERSION	1,900.000	L.F.
303-01.01	GRANULAR BACKFILL (ROADWAY)	6,113.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	333.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	852.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	19,178.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	22,293.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	14,312.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	86.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	916.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	8,415.000	TON
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	24.000	S.Y.
604-01.01	CLASS A CONCRETE (ROADWAY)	482.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	99,108.000	LB.
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	9,405.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	4,629.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	1,403.000	L.F.
607-07.02	36" CONCRETE PIPE CULVERT (CLASS III)	6,614.000	L.F.
607-08.02	42" CONCRETE PIPE CULVERT (CLASS III)	617.000	L.F.

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
607-16.01	23"X 14" HORIZONTAL OVAL CONCRETE PIPE CULVERT	124.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	499.000	L.F.
607-39.04	30" PIPE CULVERT (SIDE DRAIN)	112.000	L.F.
607-39.05	36" PIPE CULVERT (SIDE DRAIN)	58.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	11.000	EACH
611-01.03	MANHOLES, > 8' - 12' DEPTH	2.000	EACH
611-01.04	MANHOLES, > 12' - 16' DEPTH	1.000	EACH
611-01.21	REWORK MANHOLE	1.000	EACH
611-02.11	JUNCTION BOX, TYPE 2	1.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	21.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	2.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	5.000	EACH
611-07.60	30IN ENDWALL (CROSS DRAIN) 3:1	3.000	EACH
611-07.63	36IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.66	42IN ENDWALL (CROSS DRAIN) 3:1	7.000	EACH
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	13.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	24.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	122.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	29.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	14.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	5.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	350.000	L.F.
621-03.03	24" TEMPORARY DRAINAGE PIPE	253.000	L.F.
621-03.07	48" TEMPORARY DRAINAGE PIPE	160.000	L.F.
621-05.01	TEMPORARY SHORING	1,500.000	S.F.
701-01.01	CONCRETE SIDEWALK (4 ")	132,000.000	S.F.
701-02	CONCRETE DRIVEWAY	5,118.000	S.F.
701-02.03	CONCRETE CURB RAMP	3,580.000	S.F.

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
702-03	CONCRETE COMBINED CURB & GUTTER	1,738.000	C.Y.
705-01.04	METAL BEAM GUARD FENCE	394.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	2,977.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	5.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	8.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	5.000	EACH
706-01	GUARDRAIL REMOVED	4,811.000	L.F.
706-10.26	ROUNDED END ELEMENT	1.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	7,675.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	350.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	1,436.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	99.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	369.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	25,900.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	26,200.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	24.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	300.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	1,310.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	26.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,241.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	288.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	1.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	201.000	LB.
713-02.04	DELINEATOR (MILE MARKER) & STEEL POST	6.000	EACH
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	530.000	LB.
713-11.01	"U" SECTION STEEL POSTS	1,588.000	LB.

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	678.000	LB.
713-11.21	P POST SLIP BASE	18.000	EACH
713-11.22	U POST SLIP BASE	58.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	374.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	119.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	104.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	120.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	8.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
714-02.01	ENCASED CONDUIT (2" PVC, SCHEDULE 80)	120.000	L.F.
714-03	JACKED OR BORED CONDUIT	95.000	L.F.
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	11,075.000	L.F.
714-03.03	DIRECT BURIAL CONDUIT (DESCRIPTION) (2" PVC, SCHEDULE 80)	1,245.000	L.F.
714-05.04	PULL BOXES (TYPE C)	128.000	EACH
714-06.05	CABLE (1/C # 6 AWG)	19,475.000	L.F.
714-06.06	CABLE (1/C # 4 AWG)	20,295.000	L.F.
714-06.08	CABLE (DESCRIPTION) (1/C # 1/0 AWG)	8,060.000	L.F.
714-06.09	CABLE (DESCRIPTION) (#4 SOLID COPPER SOFT DRAWN)	240.000	L.F.
714-08.09	LIGHT STANDARDS (DESCRIPTION) (45' M.H., SINGLE)	82.000	EACH
714-08.10	LIGHT STANDARDS (DESCRIPTION) (45' M.H., DOUBLE)	1.000	EACH
714-08.20	FOUNDATION (ONLY) FOR LIGHT STANDARD	83.000	EACH
714-09.09	LUMINAIRES (DESCRIPTION) (155 WATT SINGLE LED OFFSET)	82.000	EACH
714-09.11	LUMINAIRES (DESCRIPTION) (155 WATT DOUBLE LED OFFSET)	2.000	EACH
714-09.12	LUMINAIRES (DESCRIPTION) (155 WATT LED OFFSET)	17.000	EACH

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
714-09.13	LUMINAIRES (DESCRIPTION) (155 WATT SINGLE LED OFFSET)	7.000	EACH
714-25.01	ELECTRICAL CONNECTION (DESCRIPTION) (PSA THRU PSF)	(1)	LS
714-25.02	ELECTRICAL CONNECTION (DESCRIPTION) (PSG THRU PSJ)	(1)	LS
714-25.03	ELECTRICAL CONNECTION (DESCRIPTION) (PSK)	(1)	LS
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	128.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	648.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	51.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	600.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	1,140.000	L.F.
716-02.11	PLASTIC PAVEMENT MARKING (6" DOTTED LINE)	4,464.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.350	L.M.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	4.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-04.04	PLASTIC PAVEMENT MARKING (TRANSVERSE SHOULDER)	500.000	L.F.
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	31.000	EACH
716-04.15	PLASTIC PAVEMENT MARKING-BIKE SYMBOL/ARROW SHARED	20.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	11.700	L.M.
716-05.04	PAINTED PAVEMENT MARKING (CHANNELIZATION STRIPING)	2,017.000	S.Y.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	165.000	L.F.
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	11.000	EACH
716-05.21	PAINTED PAVEMENT MARKING(4"DOTTED LINE)	750.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	4,450.000	L.F.
716-08.02	REMOVAL OF PAVEMENT MARKING (8" BARRIER LINE)	825.000	L.F.

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	400.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	125.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	12.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	100.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	17.300	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.01	REMOVE & RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	1.000	EACH
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	2.000	EACH
730-01.03	MODIFICATION OF EXISTING TRAFFIC SIGNAL EQUIPMENT	2.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	17.000	EACH
730-02.59	SIGNAL HEAD ASSEMBLY (140 A4F WITH BACKPLATE)	15.000	EACH
730-03.12	AERIAL SPLICE ENCLOSURE	4.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	14.000	EACH
730-03.23	INSTALL PULL BOX (FIBER OPTIC-TYPE A)	5.000	EACH
730-03.33	FIBER OPTIC SPLICE FUSION	44.000	EACH
730-03.40	NETWORK SWITCH (DESCRIPTION) (TYPE A)	3.000	EACH
730-03.53	FIBER OPTIC CABLE (DESCRIPTION) (36F)	11,830.000	L.F.
730-03.54	FIBER OPTIC DROP CABLE (12F)	370.000	L.F.
730-03.57	FIBER OPTIC DROP PANEL (DESCRIPTION) (12F)	3.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	3,170.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	5,575.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	505.000	L.F.
730-11.10	RISER ASSEMBLY (DESCRIPTION) (UTILITY POLE)	3.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	385.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	335.000	L.F.

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	335.000	L.F.
730-12.24	CONDUIT 3" DIAMETER (DIRECTIONAL BORE)	1,015.000	L.F.
730-13.08	VEHICLE DETECTOR (DESCRIPTION) (RADAR - STOP LINE)	8.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	6.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-16.04	CONTROLLER (ATC)	2.000	EACH
730-23.28	PEDESTAL POLE (TYPE A)	9.000	EACH
730-25.13	CANTILEVER SIGNAL SUPPORT (1 ARM @ 65')	1.000	EACH
730-25.14	CANTILEVER SIGNAL SUPPORT (1 ARM @ 70')	3.000	EACH
730-25.15	CANTILEVER SIGNAL SUPPORT (1 ARM @ 75')	1.000	EACH
730-25.16	CANTILEVER SIGNAL SUPPORT (1 ARM @ 80')	3.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	16.000	EACH
740-06.01	GEOMEMBRANE	1,200.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	2,843.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	16,240.000	S.Y.
790-74.35	FIBER STORAGE DOUBLE LOOP	8.000	EACH
797-05.03	8IN DIP GRAVITY SEWER 12FT-18FT DEPTH	629.000	L.F.
797-05.04	8IN DIP GRAVITY SEWER >18FT DEPTH	1,195.000	L.F.
797-05.52	8IN PVC GRAVITY SEWER 6FT-12FT DEPTH	514.000	L.F.
797-06.66	BORE/JACK 20IN STEEL CASING PIPE-UNCON.	314.000	L.F.
797-07.03	48IN MANHOLE 6FT-8FT DEPTH	1.000	EACH
797-07.04	48IN MANHOLE 8FT-10FT DEPTH	2.000	EACH
797-07.05	48IN MANHOLE 10FT-12FT DEPTH	1.000	EACH
797-07.08	48IN MANHOLE 16FT-20FT DEPTH	2.000	EACH
797-07.09	48IN MANHOLE 20FT-24FT DEPTH	2.000	EACH
797-07.56	MANHOLE DROP CONNECTION ASSEMBLY	1.000	EACH
797-07.60	ADJUST EXISTING MANHOLE	2.000	EACH
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	63.000	L.F.
797-10.02	CONNECT 8IN SEWER TO EXIST. MANHOLE	2.000	EACH

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
797-11.40	RESTORE ASPHALT	31.000	S.Y.
797-11.42	RESTORE GRAVEL	29.000	S.Y.
797-11.50	FRAME AND COVER (WATERTIGHT) (WATERTIGHT)	7.000	EACH
797-11.61	REMOVAL OF ASPHALT	31.000	S.Y.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	700.000	UNIT
801-01.35	GRASS SEED MIX (RIPZN/FLPL) W/MULCH	169.000	UNIT
801-01.36	SPECIAL WETLAND SEED MIXTURE	169.000	UNIT
801-03	WATER (SEEDING & SODDING)	242.000	M.G.
802-01.10	TREES (DESCRIPTION) (GLEDITSIA TRICANTHOS (HONEY LOCUST 2-5 FT CNTNR GRWN)	49.000	EACH
802-01.11	TREES (DESCRIPTION) (JUNIPERUS VIRGINIANA (EASTERN RED CEDAR 2-5 FT CNTNR GRWN)	40.000	EACH
802-01.12	TREES (DESCRIPTION) (CELTIS OCCIDENTALIS (HACKBERRY 2-5 FT CNTNR GRWN)	40.000	EACH
802-02.40	CUTTINGS: SALIX NIGRA (24-48IN LENGTH)	40.000	EACH
802-11.02	ACER RUBRUM (RED MAPLE 2-5FT CNTNR GRWN)	9.000	EACH
802-11.03	ACER SACCHARINUM (SILVER MAPLE 2-5FT CNTNR GRWN)	8.000	EACH
803-01	SODDING (NEW SOD)	60,382.000	S.Y.
204-08	FOUNDATION FILL MATERIAL	672.000	C.Y.
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	752.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	184,614.000	LB.
790-03.03	POLE 40FT CLASS 4 WOOD	1.000	EACH
790-03.08	POLE 40FT CLASS H2 METAL	10.000	EACH
790-04.02	POLE 45FT CLASS 2 WOOD	1.000	EACH
790-04.09	POLE 45FT CLASS H2 METAL	5.000	EACH
790-05.03	POLE 50FT CLASS 3 WOOD	1.000	EACH
790-05.08	POLE 50FT CLASS H2 METAL	6.000	EACH
790-06.08	POLE 55FT CLASS H2 METAL	14.000	EACH
790-07.08	POLE 60FT CLASS H2 METAL	23.000	EACH
790-08.04	POLE 65FT CLASS H2 METAL	20.000	EACH
790-09.06	POLE 70FT CLASS H3 METAL	17.000	EACH

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
790-10.06	POLE 75FT CLASS H3 METAL	1.000	EACH
790-20.31	FIELD POLE MODIFICTION	3.000	EACH
790-20.90	METAL TAG INSTALLATION	98.000	EACH
790-22.10	1PH SUSPENSION ANGLE 25KV	1.000	EACH
790-22.11	1PH DDE ANGLE 25KV	1.000	EACH
790-22.13	1PH DEAD END 25KV	2.000	EACH
790-22.15	1PH DEAD END TAP W/ EXTENSION 25KV	17.000	EACH
790-22.16	1PH DDE TANGENT 25KV	1.000	EACH
790-26.04	3PH CROSSARM SGL LRG COND ON ST POLE 25KV	53.000	EACH
790-26.10	3PH VERTICAL TANGENT 25KV	3.000	EACH
790-26.13	3PH CROSSARM DBL SM ANGLE LRG COND 25KV	2.000	EACH
790-26.15	3PH XARM DBL 10FT LRG COND SM ANGLE 25KV	13.000	EACH
790-26.20	3PH VERTICAL ANGLE LRG COND 25KV	1.000	EACH
790-26.21	3PH VERTICAL DDE ANGLE 25KV	3.000	EACH
790-26.26	3PH CROSSARM DEAD END 25KV	20.000	EACH
790-26.27	3PH CROSSARM DBL DDE 25KV	1.000	EACH
790-26.32	3PH CROSSARM 10FT FBRGLS X-ARM DDE 25KV	8.000	EACH
790-26.39	3PH XARM FBRGLS NEUT ON ARM BRCLESS 25KV	48.000	EACH
790-26.47	3PH SPECIAL CONST CROSSARM DDE 25KV	3.000	EACH
790-30.02	SECONDARY ASSEMBLIES LRG ANGLE	35.000	EACH
790-30.03	SECONDARY ASSEMBLIES DEADEND	6.000	EACH
790-32.01	DOWN GUY - THROUGH BOLT TYPE	6.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	31.000	EACH
790-32.29	DOWN GUY HEAVY CONSTRUCTION - PREFORM	150.000	EACH
790-33.17	ROCK ANCHOR EXPANDING TYPE	10.000	EACH
790-33.20	ANCHOR TRIPLE EYE POWER INSTALLED	18.000	EACH
790-33.21	ANCHOR TWIN EYE POWER INSTALLED	62.000	EACH
790-36.04	TRANSFER SERVICE	1.000	EACH
790-36.13	TRANSFER STREET LIGHT	2.000	EACH
790-36.14	TRANSFER CONDUCTOR	41.000	EACH

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
790-40.02	OH COND 2 7/1 ACSR SPARATE	4,112.000	L.F.
790-40.05	OH COND 3/0 6/1 ACSR PIGEON	8,098.000	L.F.
790-40.09	OH COND 336.4 18/1 ACSR MERLIN	7,991.000	L.F.
790-40.49	OH COND 795 37 AAC ARBUTUS	75,801.000	L.F.
790-41.03	UG PRI COND 1/0 AL 15KV	632.000	L.F.
790-41.06	UG PRI COND 4/0 AL 15KV	573.000	L.F.
790-41.12	UG PRI COND 1 AL 25KV	1,230.000	L.F.
790-41.30	UG PRI COND 500MCM CU 15KV	1,470.000	L.F.
790-41.40	UG PRI COND 500MCM CU 25KV	1,116.000	L.F.
790-41.49	UG SEC COND 4/0 AL TPLX	28.000	L.F.
790-42.02	CONDUIT - ROLLED PLASTIC 2IN DIA	829.000	L.F.
790-42.26	__ DUCT BANK @ __IN-__IN DEPTH (2@36-48)	194.000	L.F.
790-42.27	__ DUCT BANK @ __IN-__IN DEPTH (2@36-48)	327.000	L.F.
790-42.28	__ DUCT BANK @ __IN-__IN DEPTH (2@36-48)	628.000	L.F.
790-42.38	CONDUIT (DESCRIPTION) (SCH40, 2")	310.000	L.F.
790-42.39	CONDUIT (DESCRIPTION) (SCH40, 3")	436.000	L.F.
790-42.40	CONDUIT (DESCRIPTION) (SCH40, 4")	1,235.000	L.F.
790-42.42	CONDUIT (DESCRIPTION) (SCH40, 6")	817.000	L.F.
790-43.01	LOADBREAK ELBOW 200A 15KV	9.000	EACH
790-43.06	LOADBREAK JUNCTION 4 PT 200A 15KV	6.000	EACH
790-43.08	ELBOW ARRESTER 200A 15KV	6.000	EACH
790-43.10	SPLICE 200A 15KV	16.000	EACH
790-43.11	OUTDOOR TERMINATOR URD 15KV	26.000	EACH
790-43.17	LOADBREAK ELBOW 200A 25KV	9.000	EACH
790-43.27	OUTDOOR TERMINATOR URD 25KV	3.000	EACH
790-43.34	UG GROUND ROD ASSEMBLY	8.000	EACH
790-43.46	SECONDARY PULLBOX LARGE	4.000	EACH
790-43.47	PRIMARY PULLBOX	7.000	EACH
790-43.50	SECONDARY RISER W/ 2IN CONDUIT	1.000	EACH
790-43.51	SECONDARY RISER W/ 3IN CONDUIT	5.000	EACH

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
790-43.52	SECONDARY RISER W/ 4IN CONDUIT	7.000	EACH
790-43.58	3PH PRIMARY RISER W/ 6IN CONDUIT	21.000	EACH
790-43.67	SECONDARY PULLBOX (DESCRIPTION) (FOR SMART GRID FIBER)	12.000	EACH
790-43.80	LOADBREAK BUSHING INSERT 25KV	7.000	EACH
790-43.81	LOADBREAK BUSHING INSERT 15KV	6.000	EACH
790-43.82	INSULATED PROTECTIVE CAP	6.000	EACH
790-43.85	PRIMARY PULLBOX (DESCRIPTION) (TRAFFIC RATED)	1.000	EACH
790-44.16	PRIMARY VAULT (DESCRIPTION) (4' X 6' HEAVY DUTY CONCRETE)	3.000	EACH
790-44.17	PRIMARY VAULT (DESCRIPTION) (6' X 8' HEAVY DUTY CONCRETE)	3.000	EACH
790-49.02	3PH XFMR BNK POLE MTD W/ FUSE/ARRESTERS	1.000	EACH
790-59.03	CUTOUT KNIFE SWITCH-SNGL LOADBREAK 25KV	28.000	EACH
790-59.05	GOLB SWITCH 25KV	14.000	EACH
790-60.14	3PH SECTIONALIZING CABINET 15KV	2.000	EACH
790-61.01	1PH FUSE CUTOUT XARM MOUNT 25KV	34.000	EACH
790-61.11	3PH SECTLR OR RECL W/ BYP SW ELECTC 25KV	1.000	EACH
790-65.03	LIGHTNING ARRESTER ARM MTD 9 KV	104.000	EACH
790-65.05	LIGHTNING ARRESTER ARM MTD 18 KV	49.000	EACH
790-65.11	3PH REGULATOR PLATFORM MOUNT	1.000	EACH
790-68.10	MISCELLANEOUS ASSEMBLIES	84.000	EACH
790-68.11	DEAD END SHOE	12.000	EACH
790-68.12	LARGE BRACES	13.000	EACH
790-68.13	SGL PHASE MOUNTING BRACKET - FIBERGLASS	6.000	EACH
790-69.04	FIBERGLASS CROSSARM ASSEMBLY	17.000	EACH
790-69.06	HARDWARE FOR SGL PH CONV TRANS	12.000	EACH
790-69.08	GROUND-GROUND ROD	2.000	EACH
790-69.12	GROUND ASSEMBLY GROUND PLATE TYPE	87.000	EACH
790-69.22	POLE TOP PIN	1.000	EACH
790-69.26	EXTENSION LINK - EPOXY -1FT	26.000	EACH

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
790-69.28	EXTENSION LINK - EPOXY -6FT	141.000	EACH
790-69.30	POLE TOP PIN FOR ST POLE	1.000	EACH
790-69.32	ARM PIN	27.000	EACH
790-70.20	STREET LIGHT (DESCRIPTION) (M29-75-LEDA, SEE PLANS)	1.000	EACH
790-98.01	REMOVE WIRE	96,947.000	L.F.
790-98.02	REMOVE POLES	71.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	828.000	EACH
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
791-01.08	12IN STEEL GAS MAIN	9,637.000	L.F.
791-02.27	<=2 IN PE TEMP. BY-PASS FOR TIE-IN	(1)	LS
791-03.02	2IN HDPE GAS MAIN	358.000	L.F.
791-03.04	4IN HDPE GAS MAIN	385.000	L.F.
791-03.05	6IN HDPE GAS MAIN	11,335.000	L.F.
791-04.13	HDD 4IN PE PIPE - ROCK	1,058.000	L.F.
791-04.14	HDD 6IN PE PIPE - ROCK	870.000	L.F.
791-04.34	HDD 12IN STEEL PIPE - ROCK	1,255.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	1.000	EACH
791-06.03	CONNECT TO 4IN EX. PE MAIN	12.000	EACH
791-06.04	CONNECT TO 6IN EX. PE MAIN	14.000	EACH
791-06.35	CONNECT TO 12IN EX. STL MAIN W/ STOPPLE	2.000	EACH
791-07.02	4IN PE GAS VALVE ASSEMBLY	8.000	EACH
791-07.03	6IN PE GAS VALVE ASSEMBLY	6.000	EACH
791-07.13	12IN STEEL GAS VALVE ASSEMBLY	2.000	EACH
791-09.02	3-WIRE CATHODIC PROTECTION STATION	1.000	EACH
791-09.03	17LB MAGNESIUM ANODES	5.000	EACH
791-09.08	REMOVE REGULATOR STATION	2.000	EACH
791-09.22	FAULT CURRENT MITIGATION SYSTEM	1.000	EACH
791-12.31	12IN ANSI 300 WELD-IN INSULATOR	1.000	EACH
793-01.41	ANCHOR 1IN	26.000	EACH

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
793-07.16	12-96 FIBER(INSTALLATION ONLY)	10,815.000	L.F.
793-07.19	288-432 FIBER(INSTALLATION ONLY)	8,915.000	L.F.
793-07.23	FIBER OPTIC MAINTENANCE LOOP	26.000	EACH
793-10.20	EXPOSE EXISTING CABLE/CONDUIT (ALL DEPTHS)	126.000	L.F.
793-11.58	REMOVE HANDHOLE	2.000	EACH
793-12.02	REARRANGEMENT EXISTING CABLE	120.000	EACH
793-13.07	4IN SCHEDULE 40 PVC	743.000	L.F.
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	211.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	266.000	L.F.
793-13.33	6 DUCT FORMATION @ 48IN DEPTH	8,055.000	L.F.
793-13.34	6 DUCT FORMATION @ 60IN DEPTH	80.000	L.F.
793-13.35	6 DUCT FORMATION @ 72IN DEPTH	80.000	L.F.
793-14.01	SAND ENCASEMENT PER DUCT	44,280.000	L.F.
793-14.05	MH PRECAST 4-FT W X 8-FT L X 6-FT H	15.000	EACH
793-14.19	4IN SCH 80 ORANGE FLEXPIPE	978.000	L.F.
793-14.20	PLACE MANHOLE OVER EXISTING CABLE	4.000	EACH
793-16.04	DIRECTIONAL BORE 4IN/FLEX SLEEVE	978.000	L.F.
793-16.13	BORE/JACK 8IN CASING - ROCK	835.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	26.000	EACH
793-98.05	RETIRE BURIED FACILITIES IN PLACE	7,895.000	L.F.
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	140.000	L.F.
795-01.04	6IN DIP SLIP JOINT WATER LINE	140.000	L.F.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	120.000	L.F.
795-01.06	8IN DIP SLIP JOINT WATER LINE	100.000	L.F.
795-01.07	10IN DIP RESTRAINED JOINT WATER LINE	240.000	L.F.
795-01.08	10IN DIP SLIP JOINT WATER LINE	150.000	L.F.
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	120.000	L.F.
795-01.10	12IN DIP SLIP JOINT WATER LINE	100.000	L.F.
795-01.13	16IN DIP RESTRAINED JOINT WATER LINE	570.000	L.F.
795-01.14	16IN DIP SLIP JOINT WATER LINE	8,800.000	L.F.

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
795-01.22	30IN DIP SLIP JOINT WATER LINE	2,400.000	L.F.
795-05.77	BORE/JACK 12IN STEEL CASING PIPE-ROCK.	110.000	L.F.
795-05.79	BORE/JACK 16IN STEEL CASING PIPE-ROCK.	120.000	L.F.
795-05.80	BORE/JACK 18IN STEEL CASING PIPE-ROCK.	230.000	L.F.
795-05.81	BORE/JACK 20IN STEEL CASING PIPE-ROCK.	110.000	L.F.
795-05.82	BORE/JACK 24IN STEEL CASING PIPE-ROCK.	430.000	L.F.
795-05.83	BORE/JACK 30IN STEEL CASING PIPE-ROCK.	220.000	L.F.
795-07.03	6IN X 6IN TAPPING SLEEVE AND VALVE	2.000	EACH
795-07.06	8IN X 8IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-07.10	10IN X 10IN TAPPING SLEEVE AND VALVE	3.000	EACH
795-07.15	12IN X 12IN TAPPING SLEEVE AND VALVE	3.000	EACH
795-07.18	16IN X 8IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-07.19	16IN X 10IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-07.21	16IN X 16IN TAPPING SLEEVE AND VALVE	2.000	EACH
795-07.61	__IN X __IN TAPPING SLEEVE AND VALVE (30X20)	1.000	EACH
795-07.62	__IN X __IN TAPPING SLEEVE AND VALVE (30X16)	2.000	EACH
795-07.63	__IN X __IN TAPPING SLEEVE AND VALVE (20X16)	1.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	12.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.06	10IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.09	12IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.14	16IN GATE VALVE ASSEMBLY	12.000	EACH
795-08.24	__ IN GATE VALVE ASSEMBLY (30)	3.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	5.000	EACH
795-09.55	HDD 3IN HDPE CASING PIPE- ROCK	500.000	L.F.
795-09.62	1IN PEX SERVICE PIPE	900.000	L.F.
795-11.02	FIRE HYDRANT ASSEMBLY	11.000	EACH
795-13.01	DI FITTINGS	20,000.000	LB.
795-14.02	CLASS B CONCRETE	50.000	C.Y.
795-14.10	RESTORE GRAVEL	100.000	S.Y.

Contract ID CNY234 - RUTHERFORD

Item No.	Description	Quantity	Units
795-15.07	24IN STEEL CASING PIPE OPEN CUT METHOD	140.000	L.F.
795-16.16	RELOCATE/RECONNECT 3/4IN WATER METER ASSEMBLY	8.000	EACH
795-16.21	RELOCATE/RECONNECT 2IN WATER METER ASSEMBLY	5.000	EACH
795-16.23	RELOCATE/RECONNECT 4IN WATER METER ASSM	2.000	EACH
795-16.25	RELOCATE/RECONNECT 6IN WATER METER ASSEMBLY	2.000	EACH
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	62,826.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	198.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	702.000	TON
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	8,415.000	TON
309-01.01	MINERAL AGGREGATE (A-CBC)	26,075.000	TON
309-01.02	PORTLAND CEMENT (A-CBC)	1,007.000	TON
309-02	BITUMINOUS MATERIAL (A-CBC)	105.000	TON

() Item will be bid as lump sum.

Contract ID CNY264 - SEVIER

Contract ID: CNY264

Letting Date: October 04, 2024 10:00 AM

Projects: 78I040-F8-002

NH-I-40-8(191)

Counties: SEVIER

District:

DBE Goal Percent: 7.00

Description: The resurfacing on I-40 from the Knox County line (L.M. 0.00) to the Jefferson County line (L.M. 4.76).

Contract Time: DT - 10/31/2025

Item No.	Description	Quantity	Units
201-01	CLEARING AND GRUBBING	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	19.000	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	519.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	17,826.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	97.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	1,145.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	20,283.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	19.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	17,483.000	TON
502-08.01	RESEALING JOINTS (HOT POURED ELASTIC)	1,120.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	237.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	119.000	EACH
712-06	SIGNS (CONSTRUCTION)	3,306.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	4.000	EACH
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	10.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	50.000	DAY

Contract ID CNY264 - SEVIER

Item No.	Description	Quantity	Units
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,516.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,516.000	EACH
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	4.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	669.000	L.F.
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	4.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	4.000	EACH
716-04.08	PLASTIC PAVEMENT MARKING (OPTION LANE ARROW)	4.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	11.000	EACH
716-05.49	PAINTED PAVEMENT MARKINGS(8" LINE)	24.000	L.M.
716-09.86	CONTRAST PAVEMENT MARKING 6"	3.500	L.M.
716-09.87	CONTRAST PAVEMENT MARKINGS WORDS AND SYMBOLS	13.000	EACH
716-09.89	CONTRAST PAVEMENT MARKING 12"	267.000	L.F.
716-09.90	CONTRAST PAVEMENT MARKING 6" DOTTED	600.000	L.F.
716-10.50	PREFORMED PLASTIC PAVEMENT MARKING (INTERSTATE SHIELD)	6.000	EACH
716-10.51	PRFRMED PLSTC PVMNT MRKNG (STATE SHLD)	12.000	EACH
716-12.02	ENHANCED FLATLINE THERMO PVMNT MRKNG (6IN LINE)	24.000	L.M.
716-12.03	ENHANCED FLATLINE THERMO PVMNT MRKNG (8IN BARRIER LINE)	1,535.000	L.F.
716-12.05	ENHANCED FLATLINE THERMO PVMNT MRKNG (6IN DOTTED LINE)	2,760.000	L.F.
716-12.08	ENHANCED FLAT LINE THERMO (12IN BARRIER LINE)	2,350.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	3,170.000	L.F.
717-01	MOBILIZATION	(1)	LS
403-02.01	TRACKLESS TACK COAT	298.000	TON

Contract ID CNY264 - SEVIER

Item No.	Description	Quantity	Units
403-02.02	HOT APPLIED TACK COAT	224.000	TON

() Item will be bid as lump sum.

Contract ID CNY250 - SHELBY

Contract ID: CNY250

Letting Date: October 04, 2024 10:00 AM

Projects: 79028-3269-94

STP/M-NH-57(66)

Counties: SHELBY

District:

DBE Goal Percent: 10.50

Description: The grading, drainage, construction of a concrete box bridge, signals, and paving on U.S. 72 (S.R. 57, Poplar Avenue) from Eastley Street in Shelby County (L.M. 21.38) to S.R. 385 in Fayette County (L.M. 0.26).

Contract Time: DT - 7/31/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
109-10.01	TRAINEE	2,800.000	HOURL
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	537.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	19,070.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EXIST. BRIDGE #79SR05700007, STA. 42+63.52)	(1)	LS
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 5)	(1)	LS
202-06.02	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 6)	(1)	LS
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (CONCRETE -ALL TYPES)	1,321.000	L.F.
202-09.11	REMOVAL OF UNDERGROUND TANKS (TRACT NO.) (TRACT NO. 5)	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	38,577.000	C.Y.
203-03	BORROW EXCAVATION (UNCLASSIFIED)	2,989.000	C.Y.
203-03.01	BORROW EXCAVATION (SELECT MATERIAL)	9,982.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	3,941.963	C.Y.
203-06	WATER	315.000	M.G.

Contract ID CNY250 - SHELBY

Item No.	Description	Quantity	Units
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
209-03.22	FILTER SOCK (18 INCH)	300.000	L.F.
209-05	SEDIMENT REMOVAL	1,553.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	2,329.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	8,893.000	L.F.
209-08.07	ROCK CHECK DAM	16.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	11.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	1.000	EACH
209-09.41	CURB INLET PROTECTION (TYPE 2)	5.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	6.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	3.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	51.000	EACH
209-65.04	TEMPORARY IN STREAM DIVERSION	766.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	23,977.100	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	109.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	663.900	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	668.510	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	4,610.090	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	7,854.220	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	3,858.820	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	56.423	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	200.366	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	36.218	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	225.000	L.F.
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	42.130	TON
411-01.10	ACS MIX(PG64-22) GRADING D	415.020	TON
411-02.10	ACS MIX(PG70-22) GRADING D	2,262.360	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	896.900	S.Y.

Contract ID CNY250 - SHELBY

Item No.	Description	Quantity	Units
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	3,922.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	2,528.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	1,059.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	4.300	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	406.000	LB.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	2.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	6.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	29.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	1.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	11.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	2.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	1.000	EACH
621-05.02	TEMPORARY SHORING	(1)	LS
701-01.01	CONCRETE SIDEWALK (4 ")	45,531.000	S.F.
701-02	CONCRETE DRIVEWAY	4,075.000	S.F.
701-02.03	CONCRETE CURB RAMP	3,548.000	S.F.
702-01	CONCRETE CURB	10.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	805.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	406.250	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	2.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	2.000	EACH
706-01	GUARDRAIL REMOVED	671.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	400.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	312.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	302.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	10,400.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.10	PORTABLE BARRIER RAIL (MASH TL-3)	2,000.000	L.F.

Contract ID CNY250 - SHELBY

Item No.	Description	Quantity	Units
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	200.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	4.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	265.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	269.000	EACH
712-06	SIGNS (CONSTRUCTION)	375.500	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	145.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-09.03	REMOVABLE PAVEMENT MARKING(CHANNELIZING STRIPING)	122.000	S.Y.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	194.000	L.F.
712-09.05	REMOVABLE PAVEMENT MARKING (ARROW)	7.000	EACH
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	43,000.000	L.F.
713-11.01	"U" SECTION STEEL POSTS	609.000	LB.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	478.000	LB.
713-11.03	2 1/2" DIA ROUND STEEL TUBE SIGN POST	157.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	75.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.04	INSTALLATION OF LETTERS & ARROWS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	1.000	EACH
713-16.20	SIGNS (DESCRIPTION) (STREET NAME, MAST ARM MOUNTED)	8.000	EACH
713-16.21	SIGNS (DESCRIPTION) (R3-5L, 30"x36", MAST ARM MOUNTED)	7.000	EACH
713-16.22	SIGNS (DESCRIPTION) (R10-12, 30"x36", MAST ARM MOUNTED)	4.000	EACH
713-16.23	SIGNS (DESCRIPTION) (R10-10, 30"x36", BRIDGE MOUNTED)	2.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	222.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	280.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	1,220.000	S.Y.

Contract ID CNY250 - SHELBY

Item No.	Description	Quantity	Units
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	935.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	692.000	L.F.
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	11.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	4.000	EACH
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	27.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	6.730	L.M.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	35,000.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	10.300	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	1.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	16.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	4.000	EACH
730-02.18	SIGNAL HEAD ASSEMBLY (150 A2 POLE MOUNTED)	4.000	EACH
730-02.41	SIGNAL HEAD MODIFICATION (DESCRIPTION) (REPLACE YELLOW LED W/ YELLOW "ARROW" LED)	2.000	EACH
730-02.42	SIGNAL HEAD MODIFICATION (DESCRIPTION) (REPLACE GREEN LED W/GREEN "ARROW" LED)	2.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	8.000	EACH
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	2.000	EACH
730-03.31	FIBER DISTRIBUTION BOX	2.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.01	SIGNAL CABLE - 3 CONDUCTOR	2,000.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	5,400.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	2,000.000	L.F.
730-11.10	RISER ASSEMBLY (DESCRIPTION) (3")	2.000	EACH
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	100.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	700.000	L.F.
730-13.02	VEHICLE DETECTOR (VIDEO)	8.000	EACH

Contract ID CNY250 - SHELBY

Item No.	Description	Quantity	Units
730-13.06	VEHICLE DETECTOR (OPTICALLY ACTIVATED PRIORITY CONTROL)	8.000	EACH
730-14.02	SAW SLOT	415.000	L.F.
730-14.03	LOOP WIRE	1,030.000	L.F.
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-16.02	EIGHT PHASE ACTUATED CONTROLLER	2.000	EACH
730-23.36	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (47.5 FT ARM)	1.000	EACH
730-23.37	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (40 FT ARM)	1.000	EACH
730-23.38	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (48.5 FT ARM)	1.000	EACH
730-23.39	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (69.5 FT ARM)	1.000	EACH
730-23.96	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (58 FT ARM)	1.000	EACH
730-23.97	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (38.5 FT ARM)	1.000	EACH
730-23.98	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (67 FT ARM)	1.000	EACH
730-23.99	CANTILEVER SIGNAL SUPPORT (DESCRIPTION) (53.5 FT ARM)	1.000	EACH
730-26.06	PEDESTRIAN PUSHBUTTON POST	4.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	16.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	1,401.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	21,890.000	S.Y.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	1,760.000	L.F.
801-01	SEEDING (WITH MULCH)	10.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	410.000	UNIT
801-03	WATER (SEEDING & SODDING)	460.000	M.G.
803-01	SODDING (NEW SOD)	22,605.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	3,208.000	C.Y.

Contract ID CNY250 - SHELBY

Item No.	Description	Quantity	Units
204-08	FOUNDATION FILL MATERIAL	274.000	C.Y.
303-01.01	GRANULAR BACKFILL (ROADWAY)	5,614.000	TON
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	1,114.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	250,459.000	LB.
709-05.09	MACHINED RIP-RAP (CLASS C)	1,851.000	TON
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	907.000	S.Y.
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	31.000	L.F.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	26.000	L.F.
795-01.07	10IN DIP RESTRAINED JOINT WATER LINE	20.000	L.F.
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	373.000	L.F.
795-01.10	12IN DIP SLIP JOINT WATER LINE	3,442.000	L.F.
795-03.11	18IN PVC WATER LINE	45.000	L.F.
795-05.91	2IN PVC CASING PIPE OPEN CUT	232.000	L.F.
795-06.07	CONNECT TO 12IN WATER LINE	8.000	EACH
795-06.33	CUT AND CAP 6IN WATER LINE	2.000	EACH
795-06.34	CUT AND CAP 8IN WATER LINE	1.000	EACH
795-06.36	CUT & CAP 10IN WATER LINE	1.000	EACH
795-07.06	8IN X 8IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-07.20	16IN X 12IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-08.06	10IN GATE VALVE ASSEMBLY	2.000	EACH
795-08.09	12IN GATE VALVE ASSEMBLY	12.000	EACH
795-09.02	1IN WATER SERVICE METER ASSEMBLY	5.000	EACH
795-09.29	1IN COPPER SERVICE PIPE	414.000	L.F.
795-11.02	FIRE HYDRANT ASSEMBLY	5.000	EACH
795-11.04	RELOCATE FIRE HYDRANT	2.000	EACH
795-11.10	FIRE HYDRANT RISER	13.500	V.F.
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	2,960.000	L.F.
795-12.01	REMOVE FIRE HYDRANT	2.000	EACH
795-12.02	REMOVAL OF EXISTING LINE	(1)	LS
795-12.08	REMOVE WATER METER	5.000	EACH

Contract ID CNY250 - SHELBY

Item No.	Description	Quantity	Units
795-12.20	ADJUST EXISTING VALVE BOXES	24.000	EACH
795-12.32	REMOVE GATE VALVE	2.000	EACH
795-13.01	DI FITTINGS	7,408.000	LB.
795-14.07	CONCRETE VAULT	1.000	EACH
795-15.04	18IN STEEL CASING PIPE OPEN CUT METHOD	364.000	L.F.
795-16.17	RELOCATE/RECONNECT 1IN WATER METER ASSEMBLY	5.000	EACH
795-16.47	12IN NEW WATER MAIN TERMINATION	4.000	EACH
797-07.60	ADJUST EXISTING MANHOLE	10.000	EACH
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	250.000	L.F.
797-08.20	CONNECT SERVICE LINES (ALL SIZES)	2.000	EACH
797-09.40	CUT AND CAP (ALL LINES)	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNY217 - SHELBY

Contract ID: CNY217

Letting Date: October 04, 2024 10:00 AM

Projects: 79I040-M3-016

N/A

Counties: SHELBY

District:

DBE Goal Percent:

Description: The repair of the bridge on I-40 over the Mississippi River (L.M. 0.00).

Contract Time: DT - 3/31/2025

Item No.	Description	Quantity	Units
602-10.48	STRUCTURAL STEEL REPAIR(DESCRIPTION) (TYPE 1)	4.000	EACH
602-10.49	STRUCTURAL STEEL REPAIR(DESCRIPTION) (TYPE 3A)	1.000	EACH
602-10.51	STRUCTURAL STEEL REPAIR(DESCRIPTION)	2.000	EACH
602-10.52	STRUCTURAL STEEL REPAIR(DESCRIPTION)	2.000	EACH
602-10.53	STRUCTURAL STEEL REPAIR(DESCRIPTION)	1.000	EACH
602-10.54	STRUCTURAL STEEL REPAIR(DESCRIPTION)	1.000	EACH
602-10.55	STRUCTURAL STEEL REPAIR(DESCRIPTION)	2.000	EACH
602-10.56	STRUCTURAL STEEL REPAIR(DESCRIPTION)	2.000	EACH
602-10.57	STRUCTURAL STEEL REPAIR(DESCRIPTION)	6.000	EACH
602-10.58	STRUCTURAL STEEL REPAIR(DESCRIPTION)	1.000	EACH
602-10.59	STRUCTURAL STEEL REPAIR(DESCRIPTION)	3.000	EACH
602-10.72	STRUCTURAL STEEL CRACK REPAIR (DESCRIPTION) (TYPE 6)	3.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	288.000	EACH
712-06	SIGNS (CONSTRUCTION)	571.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	50.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	2.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	2.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	2.000	EACH

Contract ID CNY217 - SHELBY

Item No.	Description	Quantity	Units
712-08.12	QUEUE PROTECTION TRUCK	240.000	DAY
712-08.14	PORTABLE QUEUE WARNING SYSTEM	60.000	DAY
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	8,855.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	690.000	L.F.
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	9,675.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	1.700	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

Contract ID CNY209 - SUMNER

Contract ID: CNY209

Letting Date: October 04, 2024 10:00 AM

Projects: 83077-3224-94

HSIP-6(151)

Counties: SUMNER

District:

DBE Goal Percent: 3.00

Description: The miscellaneous safety improvements on U.S. 31E (S.R. 6) from Rock Bridge Road (L.M. 20.75) to near Mount Vernon Road (L.M. 24.91).

Contract Time: DT - 9/30/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
208-01.05	BROOMING & DEGRASSING SHOULDERS	1.000	L.M.
209-05	SEDIMENT REMOVAL	30.000	C.Y.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	350.000	L.F.
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	1.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	55.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	760.000	S.Y.
705-04.10	EARTH PAD FOR GUARD RAIL END TREATMENT	2.000	EACH
705-04.21	GUARDRAIL DELINEATION ENHANCEMENT	2,198.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	312.500	L.F.
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	2.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	292.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	144.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.20	SIGNS (DESCRIPTION) (R1-1, 36"x36")	5.000	EACH
713-16.21	SIGNS (DESCRIPTION) (W3-1, 36"x36")	4.000	EACH
713-16.22	SIGNS (DESCRIPTION) (S3-1, 36"x36")	1.000	EACH
713-16.23	SIGNS (DESCRIPTION) (S3-1, 48"x48")	3.000	EACH
713-16.24	SIGNS (DESCRIPTION) (W16-8P, 36"x8")	10.000	EACH

Contract ID CNY209 - SUMNER

Item No.	Description	Quantity	Units
713-16.25	SIGNS (DESCRIPTION) (W11-8, 48"x48")	1.000	EACH
716-01.40	REMOVE AND REPLACE LENS ON SNOWPLOWABLE REFLECTIVE MARKER	382.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	270.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	2.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	2.000	EACH
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	54.000	L.F.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.170	L.M.
717-01	MOBILIZATION	(1)	LS
730-02.21	SIGNAL HEAD ASSEMBLY (220)	4.000	EACH
730-02.27	SIGNAL HEAD ASSEMBLY (440)	2.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	600.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	400.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	400.000	L.F.
730-15.07	CABINET (DESCRIPTION) (NEMA TYPE 3R FLASHING SIGNAL)	2.000	EACH
730-16.03	CONTROLLER (FLASHING BEACON)	2.000	EACH
730-23.01	STEEL STRAIN POLE (SIGNAL SUPPORT)	4.000	EACH

() Item will be bid as lump sum.

Contract ID CNY161 - SUMNER

Contract ID: CNY161

Letting Date: October 04, 2024 10:00 AM

Projects: 83954-3565-54

STP-M-9307(12)

Counties: SUMNER

District:

DBE Goal Percent: 10.00

Description: The grading, drainage, construction of a concrete box bridge, paving, and signals on Walton Ferry Road/Old Shackle Island Road from Nokes Drive to Volunteer Drive in Hendersonville.

Contract Time: DT - 5/31/2027

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
108-03	CPM PROJECT SCHEDULE	(1)	LS
109-10.01	TRAINEE	2,800.000	HOUR
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	1,739.000	S.Y.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	277.000	S.Y.
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (CATCH BASINS, SEE TABLE)	(1)	LS
202-04.50	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (2 @ 10x4 RCBB, STA. 242+01.45)	(1)	LS
202-04.51	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (10x4 RCBC, STA. 242+68.52)	(1)	LS
202-06.01	REMOVAL OF BUILDINGS (TRACT NO.) (TRACT NO. 56)	(1)	LS
202-08.10	REMOVAL OF CURB (DESCRIPTION) (EXTRUDED/POST)	2,096.000	L.F.
202-08.15	REMOVAL OF CURB AND GUTTER (DESCRIPTION) (DESCRIPTION)	5,533.000	L.F.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	21,567.000	C.Y.
203-06	WATER	60.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	2,042.000	C.Y.
203-08	CHANNEL EXCAVATION (UNCLASSIFIED)	1,370.000	C.Y.

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
204-08	FOUNDATION FILL MATERIAL	183.000	C.Y.
209-02.07	18" TEMPORARY SLOPE DRAIN	27.000	L.F.
209-03.20	FILTER SOCK (8 INCH)	954.000	L.F.
209-03.23	FILTER SOCK (24 INCH)	44,623.000	L.F.
209-05	SEDIMENT REMOVAL	255.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	14,120.000	L.F.
209-08.07	ROCK CHECK DAM	72.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	59.000	EACH
209-09.01	SANDBAGS	6,366.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	16.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	159.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	175.000	S.Y.
209-40.33	CATCH BASIN PROTECTION (TYPE D)	50.000	EACH
209-40.41	CATCH BASIN FILTER ASSEMBLY(TYPE 1)	11.000	EACH
209-40.42	CATCH BASIN FILTER ASSEMBLY(TYPE 2)	92.000	EACH
209-40.47	CATCH BASIN FILTER ASSEMBLY(TYPE 7)	16.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	454.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	25,625.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	1,272.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	147.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	1,445.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	3,854.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	4,924.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	3,213.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	62.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	219.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	35.000	TON
407-20.05	SAW CUTTING ASPHALT PAVEMENT	335.000	L.F.

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
411-01.10	ACS MIX(PG64-22) GRADING D	975.000	TON
411-02.10	ACS MIX(PG70-22) GRADING D	2,275.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	310.000	TON
604-01.01	CLASS A CONCRETE (ROADWAY)	440.000	C.Y.
604-01.02	STEEL BAR REINFORCEMENT (ROADWAY)	98,231.000	LB.
607-03.30	18" PIPE CULVERT	4,624.000	L.F.
607-05.30	24" PIPE CULVERT	1,255.000	L.F.
607-06.30	30" PIPE CULVERT	989.000	L.F.
607-16.02	30"X 19" HORIZONTAL OVAL CONCRETE PIPE CULVERT	19.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	394.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	3.000	EACH
611-02.02	SPRING DRAIN BOX, TYPE 2A	1.000	EACH
611-02.11	JUNCTION BOX, TYPE 2	2.000	EACH
611-05.01	TRENCH DRAINS	140.000	L.F.
611-05.02	12IN PVC PIPE FOR TRENCH DRAINS	10.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	13.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	607.000	LB.
611-07.31	18IN ENDWALL (SIDE DRAIN)	8.000	EACH
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	3.000	EACH
611-07.57	24IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.60	30IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	42.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	30.000	EACH
611-12.03	CATCH BASINS, TYPE 12, > 8' - 12' DEPTH	4.000	EACH
611-14.01	CATCH BASINS, TYPE 14, 0' - 4' DEPTH	1.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	13.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	17.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	5.000	EACH
621-03.01	15" TEMPORARY DRAINAGE PIPE	698.000	L.F.

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
621-03.03	24" TEMPORARY DRAINAGE PIPE	20.000	L.F.
621-03.05	36" TEMPORARY DRAINAGE PIPE	246.000	L.F.
621-03.07	48" TEMPORARY DRAINAGE PIPE	276.000	L.F.
701-01.01	CONCRETE SIDEWALK (4 ")	41,520.000	S.F.
701-02	CONCRETE DRIVEWAY	23,266.000	S.F.
701-02.03	CONCRETE CURB RAMP	3,561.000	S.F.
701-03	CONCRETE MEDIAN PAVEMENT	474.000	C.Y.
702-01	CONCRETE CURB	10.000	C.Y.
702-01.01	EXTRUDED SLOPING CURB	41,195.000	L.F.
702-03	CONCRETE COMBINED CURB & GUTTER	900.000	C.Y.
705-01.04	METAL BEAM GUARD FENCE	141.000	L.F.
705-06.02	W BEAM GR (TYPE 2) MASH TL-3 (LONG POST)	1,563.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	1.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	13.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	4.000	EACH
705-06.30	GR TERMINAL (ENERGY ABSORBING) MASH TL-2	1.000	EACH
706-01	GUARDRAIL REMOVED	587.000	L.F.
706-10.26	ROUNDED END ELEMENT	14.000	EACH
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	904.000	L.F.
709-05.05	MACHINED RIP-RAP (CLASS A-3)	120.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	616.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	1,532.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	1,407.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	10,805.000	L.F.
710-05	LATERAL UNDERDRAIN	1,664.000	L.F.
712-01	TRAFFIC CONTROL	(1)	LS
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	1,100.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	3.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	204.000	EACH

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
712-04.50	BARRIER RAIL DELINEATOR	37.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	34.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,022.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	340.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	802.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	83.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	294.000	S.F.
713-14.21	STREET NAME SIGN (RIGID 0.100IN THICK	180.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	5.000	EACH
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	4.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	6.000	EACH
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	825.000	L.F.
716-02.04	PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)	15.000	S.Y.
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	580.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	29.000	EACH
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	604.000	L.F.
716-02.09	PLASTIC PAVEMENT MARKING (LONGITUDINAL CROSS-WALK)	564.000	L.F.
716-02.12	PLASTIC PAVEMENT MARKING (8IN LINE)	0.400	L.M.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	2.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	8.000	EACH
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	9.000	EACH
716-04.13	PLASTIC PAVEMENT MARKING (BIKELANE SYMBOL & ARROW)	42.000	EACH
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	6.200	L.M.
716-05.02	PAINTED PAVEMENT MARKING (8" BARRIER LINE)	2,134.000	L.F.
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	264.000	L.F.

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
716-05.06	PAINTED PAVEMENT MARKING (TURN LANE ARROW)	10.000	EACH
716-05.09	PAINTED PAVEMENT MARKING(STRAIGHT-TURN ARROW)	2.000	EACH
716-05.10	PAINTED PAVEMENT MARKING (RXR)	4.000	EACH
716-05.11	PAINTED PAVEMENT MARKING(STRAIGHT ARROW)	2.000	EACH
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	510.000	L.F.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	34.000	S.Y.
716-08.05	REMOVAL OF PAVEMENT MARKING (STOP LINE)	81.000	L.F.
716-08.06	REMOVAL OF PAVEMENT MARKING (TURN LANE ARROW)	10.000	EACH
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	142.000	L.F.
716-08.11	REMOVAL OF WORD PAVEMENT MARKING (DESCRIPTION) (RXR)	1.000	EACH
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	2.110	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.200	L.M.
716-13.02	SPRAY THERMO PVMT MRKNG (60 mil) (6IN LINE)	3.300	L.M.
717-01	MOBILIZATION	(1)	LS
730-01.01	REMOVE & RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	2.000	EACH
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	2.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	6.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	14.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	3.000	EACH
730-02.59	SIGNAL HEAD ASSEMBLY (140 A4F WITH BACKPLATE)	4.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	12.000	EACH
730-03.23	INSTALL PULL BOX (FIBER OPTIC-TYPE A)	15.000	EACH
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	5.000	EACH
730-03.33	FIBER OPTIC SPLICE FUSION	308.000	EACH
730-03.34	FIBER OPTIC TERMINATION CABINET	2.000	EACH

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
730-03.36	FIBER SPLICE ENCLOSURE (DESCRIPTION) (144F)	5.000	EACH
730-03.40	NETWORK SWITCH (DESCRIPTION) (TYPE A)	2.000	EACH
730-03.53	FIBER OPTIC CABLE (DESCRIPTION) (144F)	3,910.000	L.F.
730-03.54	FIBER OPTIC DROP CABLE (12F)	220.000	L.F.
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	3,610.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	2,525.000	L.F.
730-08.04	SIGNAL CABLE - 9 CONDUCTOR	390.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	615.000	L.F.
730-12.03	CONDUIT 3" DIAMETER (PVC SCHEDULE 40)	285.000	L.F.
730-12.08	CONDUIT 2" DIAMETER (RGS)	130.000	L.F.
730-12.09	CONDUIT 3" DIAMETER (RGS)	115.000	L.F.
730-12.23	CONDUIT 2" DIAMETER (DIRECTIONAL BORE)	510.000	L.F.
730-12.24	CONDUIT 3" DIAMETER (DIRECTIONAL BORE)	505.000	L.F.
730-12.26	CONDUIT 2" DIAMETER (PVC SCHEDULE 80)	2,085.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	6.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	2.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-23.28	PEDESTAL POLE (TYPE A)	6.000	EACH
730-25.05	CANTILEVER SIGNAL SUPPORT (2 @ 50' & 65')	2.000	EACH
730-25.13	CANTILEVER SIGNAL SUPPORT (1 ARM @ 65')	1.000	EACH
730-25.14	CANTILEVER SIGNAL SUPPORT (1 ARM @ 70')	1.000	EACH
730-25.15	CANTILEVER SIGNAL SUPPORT (1 ARM @ 75')	1.000	EACH
730-25.18	CANTILEVER SIGNAL SUPPORT (1 ARM @ 90')	1.000	EACH
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSHBUTTON & 15IN SIGN	16.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	2.000	EACH
730-40	TEMPORARY TRAFFIC SIGNAL SYSTEM	2.000	EACH
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	4,059.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	110.000	S.Y.

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
801-01	SEEDING (WITH MULCH)	34.000	UNIT
801-01.07	TEMPORARY SEEDING (WITH MULCH)	73.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	12.000	UNIT
801-03	WATER (SEEDING & SODDING)	131.000	M.G.
803-01	SODDING (NEW SOD)	9,238.000	S.Y.
805-01.01	TURF REINFORCEMENT MAT (CLASS I)	147.000	S.Y.
806-02.03	PROJECT MOWING	4.000	CYCL
604-02.01	CLASS A CONCRETE (BOX BRIDGES)	262.000	C.Y.
604-02.02	STEEL BAR REINFORCEMENT (BOX BRIDGES)	54,998.000	LB.
793-01.12	POLE 40FT CLASS 4 WOOD	1.000	EACH
793-01.41	ANCHOR 1IN	18.000	EACH
793-11.21	HANDHOLE (36IN X 24IN X 24IN)	10.000	EACH
793-13.07	4IN SCHEDULE 40 PVC	13,401.000	L.F.
793-13.12	1 DUCT FORMATION @ 36IN DEPTH	94.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	459.000	L.F.
793-13.22	3 DUCT FORMATION @ 36IN DEPTH	806.000	L.F.
793-13.27	4 DUCT FORMATION @ 36IN DEPTH	54.000	L.F.
793-13.37	9 DUCT FORMATION @ 36IN DEPTH	251.000	L.F.
793-13.42	12 DUCT FORMATION @ 36IN DEPTH	237.000	L.F.
793-13.51	___ DUCT FORMATION @ ___ IN DEPTH (5)	28.000	L.F.
793-13.52	___ DUCT FORMATION @ ___ IN DEPTH (8)	328.000	L.F.
793-13.53	___ DUCT FORMATION @ ___ IN DEPTH (11)	38.000	L.F.
793-13.54	___ DUCT FORMATION @ ___ IN DEPTH (15)	98.000	L.F.
793-14.02	CONCRETE ENCASEMENT PER DUCT	1,171.000	L.F.
793-14.03	MH PRECAST 6-FT W X 12-FT L X 7-FT H	5.000	EACH
793-14.20	PLACE MANHOLE OVER EXISTING CABLE	4.000	EACH
793-14.26	UNDERGROUND TO OVERHEAD RISER	13.000	EACH
793-98.04	REMOVE POLES ALL SIZES	5.000	EACH
793-98.05	RETIRE BURIED FACILITIES IN PLACE	1,607.000	L.F.
793-98.06	REMOVE PEDESTALS	1.000	EACH

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
793-98.08	REMOVE ANCHOR (ANY SIZE)	3.000	EACH
795-01.01	4IN DIP RESTRAINED JOINT WATER LINE	30.000	L.F.
795-01.03	6IN DIP RESTRAINED JOINT WATER LINE	765.000	L.F.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	415.000	L.F.
795-01.07	10IN DIP RESTRAINED JOINT WATER LINE	45.000	L.F.
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	1,350.000	L.F.
795-01.13	16IN DIP RESTRAINED JOINT WATER LINE	2,170.000	L.F.
795-06.03	CONNECT TO 4IN WATER LINE	1.000	EACH
795-06.04	CONNECT TO 6IN WATER LINE	11.000	EACH
795-06.05	CONNECT TO 8IN WATER LINE	6.000	EACH
795-06.06	CONNECT TO 10IN WATER LINE	2.000	EACH
795-06.07	CONNECT TO 12IN WATER LINE	20.000	EACH
795-06.09	CONNECT TO 16IN WATER LINE	4.000	EACH
795-06.32	CUT AND CAP 4IN WATER LINE	2.000	EACH
795-06.33	CUT AND CAP 6IN WATER LINE	11.000	EACH
795-06.34	CUT AND CAP 8IN WATER LINE	4.000	EACH
795-06.37	CUT AND CAP 12IN WATER LINE	13.000	EACH
795-06.39	CUT AND CAP 16IN WATER LINE	1.000	EACH
795-07.12	12IN X 6IN TAPPING SLEEVE AND VALVE	6.000	EACH
795-07.15	12IN X 12IN TAPPING SLEEVE AND VALVE	1.000	EACH
795-07.21	16IN X 16IN TAPPING SLEEVE AND VALVE	2.000	EACH
795-08.03	4IN GATE VALVE ASSEMBLY	1.000	EACH
795-08.04	6IN GATE VALVE ASSEMBLY	14.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	4.000	EACH
795-08.09	12IN GATE VALVE ASSEMBLY	6.000	EACH
795-08.14	16IN GATE VALVE ASSEMBLY	8.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	37.000	EACH
795-09.11	1-1/2IN COPPER SERVICE PIPE	125.000	L.F.
795-09.12	2IN COPPER SERVICE PIPE	125.000	L.F.
795-09.28	3/4IN COPPER SERVICE PIPE	1,330.000	L.F.

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
795-09.29	1IN COPPER SERVICE PIPE	200.000	L.F.
795-11.02	FIRE HYDRANT ASSEMBLY	10.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	2,820.000	L.F.
795-12.01	REMOVE FIRE HYDRANT	9.000	EACH
795-13.01	DI FITTINGS	19,400.000	LB.
795-14.03	CLASS C CONCRETE	78.000	C.Y.
795-14.05	CONCRETE ENCASEMENT	215.000	L.F.
795-14.08	RESTORE ASPHALT	500.000	S.Y.
795-15.25	16IN STEEL CASING PIPE OPEN CUT METHOD	55.000	L.F.
797-05.51	8IN PVC GRAVITY SEWER 0FT-6FT DEPTH	25.000	L.F.
797-05.52	8IN PVC GRAVITY SEWER 6FT-12FT DEPTH	480.000	L.F.
797-05.53	8IN PVC GRAVITY SEWER 12FT-18FT DEPTH	560.000	L.F.
797-07.02	48IN MANHOLE 4FT-6FT DEPTH	1.000	EACH
797-07.03	48IN MANHOLE 6FT-8FT DEPTH	8.000	EACH
797-07.04	48IN MANHOLE 8FT-10FT DEPTH	1.000	EACH
797-07.05	48IN MANHOLE 10FT-12FT DEPTH	1.000	EACH
797-07.06	48IN MANHOLE 12FT-14FT DEPTH	1.000	EACH
797-07.60	ADJUST EXISTING MANHOLE	1.000	EACH
797-07.75	TRAFFIC RATED FRAMES AND COVERS	12.000	EACH
797-08.02	PVC FITTINGS	35.000	LB.
797-08.04	4IN PVC PIPE FOR SERVICE LATERAL	10.000	L.F.
797-08.05	6IN PVC PIPE FOR SERVICE LATERAL	650.000	L.F.
797-08.08	6IN CLEAN OUT ASSEMBLY	23.000	EACH
797-08.20	CONNECT SERVICE LINES (ALL SIZES)	23.000	EACH
797-09.44	CUT AND CAP 8IN GRAVITY	3.000	EACH
797-10.09	CONNECT EX. 8IN SEWER TO NEW MANHOLE	2.000	EACH
797-10.28	CONNECT EX. 4IN SEWER TO NEW MANHOLE	1.000	EACH
797-11.15	48IN MH ADJUSTMENT INCREASE HEIGHT	15.000	V.F.
797-11.20	48IN MH ADJUSTMENT DECREASE HEIGHT	5.000	V.F.
797-11.25	RETIREIN PLACE 48IN MANHOLE	3.000	EACH

Contract ID CNY161 - SUMNER

Item No.	Description	Quantity	Units
797-11.31	RETIREIN PLACE EXISTING SEWER 8IN-14IN	260.000	L.F.
797-11.40	RESTORE ASPHALT	35.000	S.Y.
797-40.01	CONCRETE ENCASEMENT	200.000	L.F.

() Item will be bid as lump sum.

Contract ID CNY245 - UNICOI

Contract ID: CNY245

Letting Date: October 04, 2024 10:00 AM

Projects: 86006-3235-94

BR-STP-107(28)

Counties: UNICOI

District:

DBE Goal Percent: 8.00

Description: The construction of a concrete box beam bridge on S.R. 107 (Unicoi Drive) over North Indian Creek (L.M. 5.22) in Erwin, including grading, drainage, and paving.

Contract Time: DT - 10/31/2025

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01.50	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	3.000	EACH
202-02.01	REMOVAL OF PIPE (SIZE ,STA.) (12" ,STA. 216+08.31)	41.000	L.F.
202-02.02	REMOVAL OF PIPE (SIZE ,STA.) (18" ,STA. 215+11.35)	104.000	L.F.
202-02.03	REMOVAL OF PIPE (SIZE ,STA.) (18" ,STA. 214+26.31)	60.000	L.F.
202-02.04	REMOVAL OF PIPE (SIZE ,STA.) (12" ,STA. 212+91.74)	203.000	L.F.
202-02.05	REMOVAL OF PIPE (SIZE ,STA.) (15" ,STA. 212+67.83)	140.000	L.F.
202-02.06	REMOVAL OF PIPE (SIZE ,STA.) (15" ,STA. 211+96.85)	14.000	L.F.
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,314.000	S.Y.
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	1,910.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	523.000	TON
203-04	PLACING AND SPREADING TOPSOIL	105.000	C.Y.
203-06	WATER	22.000	M.G.
203-07	FURNISHING & SPREADING TOPSOIL	46.000	C.Y.
203-50	CONSTRUCTION OF HAUL ROAD	(1)	LS
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	2.000	C.Y.
209-05	SEDIMENT REMOVAL	67.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	582.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	514.000	L.F.

Contract ID CNY245 - UNICOI

Item No.	Description	Quantity	Units
209-08.07	ROCK CHECK DAM	4.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	6.000	EACH
209-09.03	SEDIMENT FILTER BAG (15' X 15')	1.000	EACH
209-09.43	CURB INLET PROTECTION (TYPE 4)	13.000	EACH
209-40.30	CATCH BASIN PROTECTION (TYPE A)	4.000	EACH
209-40.33	CATCH BASIN PROTECTION (TYPE D)	1.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	122.000	L.F.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	2,807.000	TON
303-01.01	GRANULAR BACKFILL (ROADWAY)	15.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	22.000	TON
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE)	532.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	512.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	452.000	TON
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	5.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	2.500	TON
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	24.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	278.000	TON
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	41.000	TON
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	541.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	54.000	L.F.
607-06.02	30" CONCRETE PIPE CULVERT (CLASS III)	78.000	L.F.
611-01.02	MANHOLES, > 4' - 8' DEPTH	1.000	EACH
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	2.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	93.000	LB.
611-12.01	CATCH BASINS, TYPE 12, 0' - 4' DEPTH	3.000	EACH
611-12.02	CATCH BASINS, TYPE 12, > 4' - 8' DEPTH	3.000	EACH
611-14.02	CATCH BASINS, TYPE 14, > 4' - 8' DEPTH	5.000	EACH
611-25.01	CATCH BASINS, TYPE 25, 0' - 4' DEPTH	1.000	EACH
611-25.02	CATCH BASINS, TYPE 25, > 4' - 8' DEPTH	1.000	EACH

Contract ID CNY245 - UNICOI

Item No.	Description	Quantity	Units
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	1.000	EACH
701-03	CONCRETE MEDIAN PAVEMENT	27.000	C.Y.
702-01	CONCRETE CURB	14.000	C.Y.
702-03	CONCRETE COMBINED CURB & GUTTER	46.000	C.Y.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	113.000	L.F.
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	1.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	3.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	4.000	EACH
706-01	GUARDRAIL REMOVED	142.000	L.F.
706-06.03	RADIUS RAIL	38.000	L.F.
706-10.26	ROUNDED END ELEMENT	1.000	EACH
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	10.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	50.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	28.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	1,335.000	TON
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	465.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	6.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	100.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	10.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	50.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,486.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	77.000	L.F.
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	1,406.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	48.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	840.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	1,500.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	2.000	C.Y.

Contract ID CNY245 - UNICOI

Item No.	Description	Quantity	Units
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR SIGN SUPPORTS)	225.000	LB.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	6.000	L.F.
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,257.000	LB.
713-11.05	SQUARE TUBE SIGN SUPPORT	233.000	LB.
713-11.21	P POST SLIP BASE	9.000	EACH
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	140.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	45.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	31.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	0.800	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	0.800	L.M.
717-01	MOBILIZATION	(1)	LS
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-07.04	GEOGRID REINFORCEMENT TYPE 2	800.000	S.Y.
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	875.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	1,105.000	S.Y.
740-11.02	TEMPORARY SEDIMENT TUBE 12IN	425.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	8.000	UNIT
801-01.38	NATVE SEED MX FINAL STABLIZATN OF SLOPES	8.000	UNIT
801-02	SEEDING (WITHOUT MULCH)	4.000	UNIT
801-03	WATER (SEEDING & SODDING)	5.000	M.G.
803-01	SODDING (NEW SOD)	472.000	S.Y.
805-12.02	EROSION CONTROL BLANKET (TYPE II)	451.000	S.Y.
806-02.03	PROJECT MOWING	6.000	CYCL
202-01.02	REMOVAL OF ASBESTOS	(1)	LS
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (EX. BR. NO. 86-SR107-05.22)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	176.000	C.Y.

Contract ID CNY245 - UNICOI

Item No.	Description	Quantity	Units
204-03.01	WET EXCAVATION (BRIDGES)	94.000	C.Y.
204-10.01	FOUNDATION PREPARATION(PR NO. ,STA) (PR NO. 1 ,STA. 210+80.00)	(1)	LS
303-01.02	GRANULAR BACKFILL (BRIDGES)	30.000	TON
604-02.03	EPOXY COATED REINFORCING STEEL	48,378.000	LB.
604-03.01	CLASS A CONCRETE (BRIDGES)	154.355	C.Y.
604-03.02	STEEL BAR REINFORCEMENT (BRIDGES)	26,409.000	LB.
604-03.04	PAVEMENT @ BRIDGE ENDS	230.000	S.Y.
604-03.09	CLASS D CONCRETE (BRIDGE DECK)	155.000	C.Y.
604-04.01	APPLIED TEXTURE FINISH (NEW STRUCTURES)	582.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	776.000	S.Y.
606-03.03	STEEL PILES (12 INCH)	1,176.000	L.F.
606-03.06	PILE TIPS (STEEL PILES, 12 INCH)	40.000	EACH
615-02.05	PRESTRESSED CONCRETE BOX BEAM (33" X 36")	578.000	L.F.
620-05.01	CONC PARAPET SINGLE SLOPE (STD-1-1SS)	289.000	L.F.
710-09.01	6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM	124.000	L.F.
710-09.02	6" PIPE UNDERDRAIN	27.550	L.F.
202-03.03	REMOVAL OF ASPHALT PAVEMENT	160.000	C.Y.
209-99.91	EROSION CONTROL	(1)	LS
407-20.05	SAW CUTTING ASPHALT PAVEMENT	855.000	L.F.
790-04.07	POLE 45FT CLASS 2 METAL	5.000	EACH
790-05.02	POLE 50FT CLASS 2 WOOD	1.000	EACH
790-05.06	POLE 50FT CLASS 2 METAL	2.000	EACH
790-06.06	POLE 55 FT CLASS 2 METAL	1.000	EACH
790-07.18	POLE 60FT CLASS H5 METAL	1.000	EACH
790-20.01	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (35FT CLASS 4 METAL)	2.000	EACH
790-20.08	POLE(SPECIFY POLE LENGTH, CLASS, AND MATERIAL) (55FT CLASS H5 METAL)	1.000	EACH
790-20.30	TOP EXISTING POLE	13.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	1.000	EACH

Contract ID CNY245 - UNICOI

Item No.	Description	Quantity	Units
790-21.11	1PH CROSSARM DEADEND 15KV	1.000	EACH
790-21.12	1PH CROSSARM DDE 15KV	1.000	EACH
790-25.06	3PH CROSSARM DBL 15KV	2.000	EACH
790-25.12	3PH CROSSARM DBL 10FT PRIM SUP 15KV	4.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	1.000	EACH
790-25.23	3PH CROSSARM DDE 15KV	4.000	EACH
790-31.02	SERVICE ASSEMBLY-POLE TYPE	9.000	EACH
790-31.04	SERVICE CONDUCTOR 6 AL DUPLEX	61.000	L.F.
790-31.11	SERVICE CONDUCTOR 2 AL TRIPLEX	549.000	L.F.
790-32.03	DOWN GUY - THROUGH BOLT ST PL	14.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	7.000	EACH
790-32.23	GUY GUARD	10.000	EACH
790-33.06	PLATE TYPE ANCHOR 10,000LB-12,000LB	2.000	EACH
790-33.25	SCREW TYPE ANCHOR 15,000LB	4.000	EACH
790-33.26	SCREW TYPE ANCHOR 28,000LB	9.000	EACH
790-33.27	SCREW TYPE ANCHOR 32,000LB	3.000	EACH
790-36.10	TRANSFER - LIGHT ASSEMBLY	2.000	EACH
790-36.11	TRANSFER EXISTING 1PH TRANSFORMER/RECLOSER	7.000	EACH
790-36.13	TRANSFER STREET LIGHT	1.000	EACH
790-36.14	TRANSFER CONDUCTOR	52.000	EACH
790-36.15	TRANSFER FRAMING/ASSOCIATED APPARATUS	16.000	EACH
790-40.01	OH COND 4 7/1 ACSR SWANATE	160.000	L.F.
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	2,208.000	L.F.
790-40.06	OH COND 4/0 6/1 ACSR PENGUIN	6,624.000	L.F.
790-41.46	UG SEC COND 1/0 AL TPLX	200.000	L.F.
790-42.08	2IN DIA PVC PIPE	230.000	L.F.
790-42.17	2 DUCT BANK @ 36IN-48IN DEPTH	130.000	L.F.
790-43.46	SECONDARY PULLBOX LARGE	2.000	EACH
790-43.50	SECONDARY RISER W/ 2IN CONDUIT	2.000	EACH

Contract ID CNY245 - UNICOI

Item No.	Description	Quantity	Units
790-68.01	POLE GROUND ROD TYPE	13.000	EACH
790-68.10	MISCELLANEOUS ASSEMBLIES	25.000	EACH
790-68.11	DEAD END SHOE	12.000	EACH
790-69.41	EXTENSION LINK - EPOXY -8FT	2.000	EACH
790-70.20	STREET LIGHT (DESCRIPTION) (70W LED)	2.000	EACH
790-72.07	GUY FACTORY FORMED WITH THIMBLE CLEVIS	9.000	EACH
790-74.20	108-144 FIBER(INSTALLATION ONLY)	4,219.000	L.F.
790-74.22	288-432 FIBER(INSTALLATION ONLY)	2,016.000	L.F.
790-74.31	FIBER TANGENT ASSEMBLY	10.000	EACH
790-74.32	FIBER DEADEND ASSEMBLY	46.000	EACH
790-74.35	FIBER STORAGE DOUBLE LOOP	12.000	EACH
790-98.01	REMOVE WIRE	15,376.000	L.F.
790-98.02	REMOVE POLES	13.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	192.000	EACH
790-98.20	TREE AND BRUSH REMOVAL OFF ROW	(1)	LS
791-01.05	6IN STEEL GAS MAIN	531.000	L.F.
791-02.02	2IN MDPE GAS MAIN	215.000	L.F.
791-04.02	HDD 2IN PE PIPE - UNCONSOLIDATED	245.000	L.F.
791-05.21	BORE/JACK 12IN - STEEL CASING PIPE - ROCK	80.000	L.F.
791-06.02	CONNECT TO 2IN EX. PE MAIN	2.000	EACH
791-06.12	CONNECT TO 6IN EX. STL MAIN	2.000	EACH
791-06.33	CONNECT TO 6IN EX. STL MAIN W/ STOPPLE	2.000	EACH
791-06.51	2IN PE HOT TAP CONNECTION	1.000	EACH
791-07.01	2IN PE GAS VALVE ASSEMBLY	3.000	EACH
791-07.11	6IN STEEL GAS VALVE ASSEMBLY	2.000	EACH
791-08.08	1IN PE SERVICE PIPE	10.000	L.F.
791-09.02	3-WIRE CATHODIC PROTECTION STATION	2.000	EACH
791-09.05	RESTORE ASPHALT	200.000	S.Y.
791-10.06	RETIRE IN PLACE 6IN SERV CUT & PLUG	2.000	EACH
793-01.08	POLE 35FT CLASS 5 WOOD	6.000	EACH

Contract ID CNY245 - UNICOI

Item No.	Description	Quantity	Units
793-01.40	ANCHOR 3/4IN	9.000	EACH
793-02.07	GUY WIRE 6.6M OR 1/4IN	2.000	EACH
793-02.08	GUY WIRE 10M OR 3/8IN	10.000	EACH
793-02.93	OVERHEAD GUY WIRE (DESCRIPTION) (10M)	3.000	L.F.
793-03.01	25 PAIR GROUP AERIAL SPLICE	158.000	EACH
793-03.02	6M STRAND	1,130.000	L.F.
793-03.03	10M STRAND	1,750.000	L.F.
793-03.12	50 PAIR CABLE	50.000	L.F.
793-03.16	200 PAIRCABLE	905.000	L.F.
793-03.18	400 PAIR CABLE	740.000	L.F.
793-03.19	600 PAIR CABLE	305.000	L.F.
793-04.01	RELASH/DELASH CABLE	3,977.000	L.F.
793-04.02	2 PAIR AERIAL DROP	1,610.000	L.F.
793-04.06	READY ACCESS CLOSURE	5.000	EACH
793-04.07	AERIAL SPLICE CLOSURE	5.000	EACH
793-04.08	TRANSFER AERIAL CABLE	22.000	EACH
793-11.13	BURIED RISER GUARD	4.000	EACH
793-12.08	600 PAIR UG CABLE	300.000	L.F.
793-13.17	2 DUCT FORMATION @ 36IN DEPTH	200.000	L.F.
793-14.01	SAND ENCASEMENT PER DUCT	400.000	L.F.
793-98.01	REMOVE AERIAL CABLE AND WIRE	6,875.000	L.F.
793-98.04	REMOVE POLES ALL SIZES	12.000	EACH
793-98.08	REMOVE ANCHOR (ANY SIZE)	11.000	EACH
795-01.01	4IN DIP RESTRAINED JOINT WATER LINE	10.000	L.F.
795-01.05	8IN DIP RESTRAINED JOINT WATER LINE	740.000	L.F.
795-01.09	12IN DIP RESTRAINED JOINT WATER LINE	310.000	L.F.
795-05.91	2IN PVC CASING PIPE OPEN CUT	115.000	L.F.
795-06.04	CONNECT TO 6IN WATER LINE	1.000	EACH
795-06.32	CUT AND CAP 4IN WATER LINE	2.000	EACH
795-07.01	4IN X 4IN TAPPING SLEEVE AND VALVE	2.000	EACH

Contract ID CNY245 - UNICOI

Item No.	Description	Quantity	Units
795-07.15	12IN X 12IN TAPPING SLEEVE AND VALVE	2.000	EACH
795-07.30	INSERTION VALVE (4IN)	1.000	EACH
795-07.34	INSERTION VALVE (12IN)	2.000	EACH
795-08.05	8IN GATE VALVE ASSEMBLY	2.000	EACH
795-09.09	RELOCATE/RECONNECT SERVICE ASSEMBLY	3.000	EACH
795-09.10	SAMPLE TAP	1.000	EACH
795-09.24	TI OF 2IN HDPE CASING FOR SERVICE PIPE-UNCON	155.000	L.F.
795-09.28	3/4IN COPPER SERVICE PIPE	270.000	L.F.
795-10.31	2IN BLOW-OFF ASSEMBLY	1.000	EACH
795-11.01	BLOW-OFF ASSEMBLY	1.000	EACH
795-11.12	RETIRE IN PLACE EXISTING WATER MAIN	1,111.000	L.F.
795-12.07	REMOVE EXISITNG VALVE	2.000	EACH
795-13.05	CREEK CROSSING (DESCRIPTION) (#1)	(1)	LS
795-20.01	RECONNECT SERVICE ASSEMBLY	2.000	EACH

() Item will be bid as lump sum.

Contract ID CNY240 - WILLIAMSON

Contract ID: CNY240

Letting Date: October 04, 2024 10:00 AM

Projects: 94I065-F8-002
94I065-F8-003

NH-I-65-1(79)
NH-I-65-1(80)

Counties: WILLIAMSON

District:

DBE Goal Percent: 9.00

Description: The resurfacing on I-65 from the Maury County line (L.M. 0.00) to south of S.R. 248 (L.M. 7.27).

Contract Time: DT - 11/15/2025

Item No.	Description	Quantity	Units
208-01.05	BROOMING & DEGRASSING SHOULDERS	23.400	L.M.
303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	3,094.000	TON
307-01.18	ASPHALT CONCRETE MIX (PG64-22) GRADING CM	6,847.000	TON
307-03.12	ASPHALT CONCRETE MIX (PG76-22) GRADING CM	21,382.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	139.000	TON
411-03.10	ACS MIX(PG76-22) GRADING D	456.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	17,568.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	23.400	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	22,412.000	TON
501-01.13	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10" FAST TRACK	13.000	S.Y.
502-07	SPALL REPAIR	14.000	S.Y.
712-01	TRAFFIC CONTROL	(1)	LS
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	500.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	26.000	EACH
712-06	SIGNS (CONSTRUCTION)	2,929.000	S.F.
712-06.16	SIGNS (CONSTRUCTION)(REDUCED SPEED WARNING)	6.000	EACH
712-07.03	TEMPORARY BARRICADES (TYPE III)	228.000	L.F.

Contract ID CNY240 - WILLIAMSON

Item No.	Description	Quantity	Units
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.08	SPEED FEEDBACK SIGN ASSEMBLY	4.000	EACH
712-08.09	DIGITAL SPEED LIMIT SIGN ASSEMBLY	13.000	EACH
712-08.12	QUEUE PROTECTION TRUCK	240.000	DAY
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	19.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	1,746.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	1,746.000	EACH
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	3.000	EACH
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	8.000	EACH
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	17.000	EACH
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	58.000	L.M.
716-08.04	REMOVAL OF PAVEMENT MARKING (CHANNELIZATION STRIPING)	701.000	S.Y.
716-08.20	REMOVAL OF PAVEMENT MARKING (LINE)	2.900	L.M.
716-09.94	CONTRAST PAVEMENT SHADOW MARKING 6"	1.100	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	27.000	L.M.
716-12.05	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	9,191.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	4,192.000	L.F.
716-15.11	PREFORMED PERMANENT TAPE (8IN LINE)	14,170.000	L.F.
716-15.20	PREFORMED PERMANENT TAPE (24IN BARRIER LINE)	6,595.000	L.F.
717-01	MOBILIZATION	(1)	LS
403-02.01	TRACKLESS TACK COAT	344.000	TON
403-02.02	HOT APPLIED TACK COAT	210.000	TON

() Item will be bid as lump sum.

