



**STATE OF TENNESSEE
DEPARTMENT OF TRANSPORTATION**

DESIGN DIVISION
SUITE 1200, JAMES K. POLK BUILDING
505 DEADERICK STREET
NASHVILLE, TENNESSEE 37243-1402
(615) 741-0835

HOWARD H. ELEY
COMMISSIONER

BILL LEE
GOVERNOR

INSTRUCTIONAL BULLETIN NO. 23-13

Update to Chapter 7 – Guardrail Removal Item

Effective with the September 27, 2023, turn-in (December 8, 2023, letting), Chapter 7 has been updated to include Item No. **706-01, GUARDRAIL REMOVED**. Headquarters Construction stated this item should be used on all projects with guardrail which will need to be removed.

A new item number **501-03.15, CONCRETE SHOULDER MILLED RUMBLE STRIPS**, has been created to allow for the use of concrete shoulder milled rumble strips. The item and unit of measurement has been added to the Chapter to be utilized on interstates when concrete paving exists.

The revised sections are shown below:

7-706.00 GUARDRAIL REMOVED

Item Number	Description	Unit of Measurement	Comment
706-01	GUARDRAIL REMOVED	L.F.	ALWAYS ADD WHEN GUARDRAIL WILL BE REMOVED

7-501.00 CONCRETE SHOULDER MILLED RUMBLE STRIPS

Item Number	Description	Unit of Measurement	Comment
501-01.01	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 8"	S.Y.	SP109A; RP-J-23
501-01.02	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 9"	S.Y.	SP109A; RP-J-23
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	S.Y.	SP109A; RP-J-23
501-01.04	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 11"	S.Y.	SP109A; RP-J-23
501-01.05	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 12"	S.Y.	SP109A; RP-J-23
501-01.06	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 13"	S.Y.	SP109A; RP-J-23
501-01.07	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 14"	S.Y.	SP109A; RP-J-23
501-01.10	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 7" FAST TRACK	S.Y.	SP109A; RP-J-23
501-01.11	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 8" FAST TRACK	S.Y.	SP109A; RP-J-23
501-01.12	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 9" FAST TRACK	S.Y.	SP109A; RP-J-23
501-01.13	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10" FAST TRACK	S.Y.	SP109A; RP-J-23
501-01.14	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 11" FAST TRACK	S.Y.	SP109A; RP-J-23
501-01.15	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 12" FAST TRACK	S.Y.	SP109A; RP-J-23
501-01.16	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 13" FAST TRACK	S.Y.	SP109A; RP-J-23

501-01.20	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 3" ULTRATHIN	S.Y.	SP109A
501-01.21	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 4" ULTRATHIN	S.Y.	
501-01.30	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) ULTRATHIN	S.Y.	
501-02.01	COMPOSITE PORTLAND CEMENT CONCRETE PAVEMENT	S.Y.	
501-03.01	COLORED CONCRETE SHOULDERS	S.Y.	
501-03.02	CONCRETE SHOULDERS	S.Y.	
501-03.10	CONCRETE SHOULDER RUMBLE STRIPS	L.F.	RP-CS-1; RP-CS-2
501-03.12	CONCRETE SHOULDER RUMBLE STRIP (MECHANICAL)	L.M.	
501-03.15	CONCRETE SHOULDER MILLED RUMBLE STRIPS	L.M.	TO BE USED ON SHOULDERS OF INTERSTATES CONSTRUCTED WITH CONCRETE
501-03.20	CONCRETE PAVEMENT GROOVING	S.Y.	
501-04.01 to 501-04.02	ROLLER COMPACTED CONCRETE PAVEMENT(DEPTH)	C.Y.	SP501RC
501-04.03 to 501-04.04	ROLLER COMPACTED CONCRETE PAVEMENT(DEPTH)	S.Y.	SP501RC
501-05.90	REMOVE EXISTING BITUMINOUS MATERIAL	L.S.	
502-01	CLEANING AND SEALING JOINTS	L.F.	
502-01.02	CLEANING JOINTS	L.F.	



Shane Hester, PE
State Engineering Director